




M19487



22101625639



49-d.11-







OPERATIVE SURGERY



3  
a

# OPERATIVE SURGERY

ADAPTED TO THE

LIVING AND DEAD SUBJECT

BY

C. F. MAUNDER,

SURGEON TO THE LONDON HOSPITAL; FORMERLY DEMONSTRATOR  
OF ANATOMY IN GUY'S HOSPITAL.



Second Edition

WITH ONE HUNDRED AND SIXTY-FOUR ILLUSTRATIONS.



LONDON

J. & A. CHURCHILL, NEW BURLINGTON STREET

1873

14060

WELLCOME INSTITUTE LIBRARY	
Coll.	welMOmec
Call	
No.	<del>W0500</del>
	<del>1873</del>
	<del>M450</del>

M19487



## PREFACE TO SECOND EDITION.

---


SINCE the publication of the first edition of this volume many years have elapsed. During this period the London Hospital has afforded me a vast field for operative experience. The first edition contained no novelty; but now I venture to claim originality for an improvement on the method of excising the elbow-joint, and also on the usual mode of operation on the lower jaw.

The work has been altered somewhat, and a few additions have been made. While it is, however, very short of exhausting the range of Operative Surgery, I trust that so far as it goes it will be found instructive to the Student.

C. F. MAUNDER.

16, *Queen Anne-street, Cavendish-square, W.*

*December, 1872.*



Digitized by the Internet Archive  
in 2015

<https://archive.org/details/b2039214x>

## PREFACE TO FIRST EDITION.

---

WHEN conducting a course of operations on the dead subject in Paris, gentlemen working with me regretted that the English Professional Library did not contain a sufficiently concise, systematic, and illustrated guide to the operations applicable as well to the dead as to the living subject.

While compiling this volume, with a view to satisfying the demand, I was forestalled in my idea by the publication of a work of a somewhat similar kind. Notwithstanding, I determined to carry out my project, and hope that I may not have failed to produce something useful to the student of Practical Surgery.

Let me observe, that I pretend to nothing new in this volume, my sole object being to give certain general rules for guidance, and to describe as clearly and briefly as may be, what, in my judgment, is the best mode of performing certain operations.

It will be readily understood that the cost of an illustrated work of this kind with original wood-cuts would be enormous; in order, therefore, to offer this volume to the Student at a moderate price, I have borrowed, by permission, a large number of the illustrations from other authors.

C. F. MAUNDER.

\*





# CONTENTS.

---

## CHAPTER I.

PAGE

Compress—Splints—Bandages—Strapping—Suture— Knots .. .. .	1—15
--	------

## CHAPTER II.

Ligatures—Ligatures to Tumours .. .. .	16—19
--	-------

## CHAPTER III.

Cupping—Venæsection—Varix — Nævus — Transfusion of blood and injection of saline fluids .. .. .	20—28
--	-------

## CHAPTER IV.

### OPERATIONS ON ARTERIES.

Compression — Torsion — Cauterization — Arteriotomy — Ligature — Tenaculum-foreeps — Carbolic ligature — Sponging — Acupressure — Ligature in the continuity of an artery — Aneurism needle — Aphorisms .. .. .	29—45
---	-------

## CHAPTER V.

### LIGATURE OF SPECIAL ARTERIES.

Arteria innominata—Common carotid—External carotid —Internal carotid—Superior thyroid—Lingual— Facial—Occipital—Temporal—Subelavian—Verte-
--

bral—Inferior thyroid—Internal mammary—Axillary; upper third; lower third—Brachial; middle third; at bend of elbow—Radial; upper third; lower third—Ulnar; upper third; lower third—Abdominal aorta—Common iliac; anatomical relations—External iliac; anatomical relations—Internal iliac; anatomical relations—Ligature of external iliac—Ligature of internal and common iliac—Femoral artery; anatomical relations; operation; at the apex of Scarpa's triangle; at the base of Scarpa's triangle; in the middle third of thigh (caution)—Popliteal—Posterior tibial; at the middle third of leg (caution); another method; at the lower third of leg—Anterior tibial; in the middle third of leg (caution)—Dorsalis pedis ..	46—99
---	-------

## CHAPTER VI.

## OPERATIONS ON THE BONES.

Excision of joints, bones, and portions of bones—Excision of upper jaw; one method, chain saw, lion forceps; another method; third method—Excision of lower jaw; of symphysis; from symphysis to angle; N.B.; from angle to articulation; without wound of cheek—Excision of clavicle—Excision of scapula—Excision of head of humerus; another method—Excision in the continuity of humerus, un-united fracture—Excision of elbow-joint; author's method to preserve extension; dressing the wound—Excision of radius and elbow—Excision of wrist-joint; another method; Lister's method—Excision of metacarpal bone of thumb—Excision of a phalangeal articulation—Excision of hip-joint; another method—Excision in the continuity of the femur—Excision of knee-joint—Excision of fibula—Excision of ankle-joint; excision director—Excision of metatarso-phalangeal articulation—Subperiosteal excision—Bifid fingers and toes—Excision of tarsal bones; of astragalus;

	PAGE
of os calcis; another method—Un-united fracture; pegging—Compound fracture—Compound commi- nated fracture—Exostoses—Abscess in bone— Necrosis and caries; necrosis and exfoliating bone; caries—The trephine—Hey's saw—Anchylosis; false; true—the bow-saw .. .. .	100—156

## CHAPTER VII.

## OPERATIONS ON THE SURFACE OF THE BODY.

Abscess, acute and chronic—Acupuncture—Caustics, fluid and solid—Actual cautery—Galvanic cautery —Exploration—Issue—Seton—Seton-needle—Vac- cination .. .. .	157—162
---	---------

## CHAPTER VIII.

## AMPUTATION.

Double flap; saw; after-treatment; length of flaps; varieties and modifications—By circular incision— Comparative merits of flap and circular incision— By oval incision—In the contiguity of a limb ..	163—180
--	---------

## CHAPTER IX.

## LOWER EXTREMITY.

The foot—The toes; amputation of great toe; by oval incision; by flap—Toes <i>en masse</i> —Amputation of metatarsal bone—Metatarsal bone of great toe— Fifth metatarsal bone—Metatarsal bones <i>en masse</i> — Tarso-metatarsal amputation—Medio-tarsal ampu- tation—Tibio-tarsal amputations—Comparative value of transverso amputations of the foot—Am- putation of the leg—Of the thigh through knee- joint—Through hip-joint .. .. .	181—235
--	---------

## CHAPTER. X.

## UPPER EXTREMITY.

## PAGE

The fingers; anatomy—Amputation of fingers—Of metacarpal bone—Through wrist-joint—Of forearm—Through elbow-joint—Of arm—Through shoulder-joint .. .. .	236—258
--	---------

## CHAPTER XI.

Tracheotomy—Laryngotomy—Paracentesis thoracis—Œsophagotomy—Gastro-stomachotomy—Paracentesis-abdominis—The trocar—Abdominal hernia; taxis—Herniotomy; radical cure—Lumbar artificial anus—Abdominal artificial anus—Ovariectomy; treatment of the pedicle—Cæsarian section—Removal of tumours—Removal of integument—Removal of mamma—Hare-lip—Cleft palate—Abscission of tonsil—Plugging the posterior nostril—Catheterism of nasal duct—Catheterism of the Eustachian tube—Removal of tongue—The eye; extirpation of globe—Strabismus—Artificial pupil; by iridectomy; by iridodesis—Staphyloma removed by abscission—Cataract—Entropion—Blepharoplasty—Rhinoplasty—Genito-urinary organs; phymosis—Amputation of penis—Hydrocele—Varicocele—Castration—The catheter—Stricture—Puncture of the bladder—Lithotomy—Lithotriety—Lacerated perinæum—Catheterism in the female—Vesico-vaginal fistula—Calculus in the female—Tenotomy—The spring-eyed needle—The tubular aneurism and suture needle .. .. .	259—368
--	---------



# OPERATIVE SURGERY.



## CHAPTER I.

COMPRESS—SPLINT—BANDAGE—STRAPPING.

THE practice of surgery may be subdivided into “manipulative” and “operative;” the term “manipulative” being applied to the employment of certain supports, such as compresses, bandages, splints, and strapping; the term “operative” implying the use of cutting or wounding instruments.

A *compress* is used to maintain parts in apposition; to check hæmorrhage by offering resistance to a bandage; and may be made of lint, sponge, cork, lead, and even stone, both substance and size depending upon the requirements of the case.

*Splints* are employed to insure rest, to maintain or restore the natural form of the body, whether idiospathically or traumatically altered. They are of various shapes, sizes, and material: of *shape*, according to the form of the part to which they are to be

applied, and the injury which they are called upon to remedy; of *size*, in proportion to the stature of the patient; and of *density*, corresponding to the amount of resistance to be borne.

In the case of fracture, of the leg for example, a splint to be of use must be well padded, and press equally on all parts; it must also have two fixed points in order that it may counteract the action of muscles, one above, the other below the seat of fracture, say the knee and ankle—situations at which counter-extension and extension are made and maintained so long as may be necessary.

*Bandages* are of the utmost value, for without them the compress and splint would be useless. They are of themselves more or less sufficient to support and maintain portions of the body at rest, and in their natural relative positions; and as the extent to which they may be multiplied is almost indefinite, I shall restrict myself by an allusion to the more useful only.

Bandages are of various lengths and widths, and are classified under a nomenclature in accordance with the supposed resemblance which they bear to certain well-known mathematical or other figures, such as the figure of 8 bandage, the T bandage. The object in the employment of a bandage being to procure rest and to give support, it is obviously desirable that pressure should be equable and the application carefully and evenly effected. It should also, with few exceptions, be applied to favour the

return of blood towards the heart—as, for example, from the fingers and toes upwards—lest strangulation and mortification unhappily follow the opposite mode of proceeding.

In order to prevent retraction of the soft parts after amputation, strapping or a bandage may, contrary to the rule, be cautiously adapted from above downwards.

The *simple roller* (Fig. 1) of the required length and width is made by rolling a strip of calico tightly upon itself into the form of a cylinder, leaving one extremity free, the outer surface



FIG. 1.

of which extremity should be first applied to the part of the body to be invested, while the cylinder is manipulated by the surgeon and gradually unrolled. In applying the simple roller or bandage, to the leg for example, in order to insure equal pressure, the free end being fixed by one or two turns, the roller should be carried gradually round and round the limb to the required height, and be thus unrolled without having been removed from the limb except to make a “turn,” and always under the same tension from the hand of the surgeon.

Fig. 2 shows the simple band adapted to a limb of conical shape, the leg.

Fig. 3 displays the band investing the arm, each circle of which overlaps the one below to the extent of one-third or one-half, so as to insure complete investment; but the arm being of nearly the same

diameter throughout its extent, the "turns," as represented in Fig. 2, are not required.



FIG. 2.




FIG. 3.



FIG. 4.

The *double-headed* bandage (Fig. 4), formed by rolling up both ends of the calico till the cylinders meet in the centre of it, is applicable to the surgery of the head. It is adapted by placing the external surface of the portion of the bandage between the cylinders upon the forehead. Holding a cylinder in each hand, carry them round to the back of the head, cross and change hands with the cylinders simultaneously, repeat the circle and crossing, carry one end of the bandage across the top of the head, first on one side of the median line and then on the other, from behind forwards and from before backwards alternately, taking care to fix each crossing



by a circular turn of the other end of the bandage, and so on, from within to without till the head be covered.

The *figure 8 bandage* is much employed, and is readily adapted to the joints; it is especially applicable to fractures of the clavicle and surgery of the shoulder.

The *T bandage* (Figs. 5 and 6) is employed in the surgery of the anus and vagina, and consists of a horizontal portion going round the pelvis, to which




FIG. 5.

is attached behind, in the median line, a vertical portion: this passed under the perinæum, and split into two parts, one of which runs on either side of the scrotum, if the patient be a male, is attached by pins or thread to the front and middle of the horizontal line.

The *starched bandage*.—To insure complete im-




FIG. 6.

mobility, either a solution of starch, or equal parts of gum and chalk, moistened with water, and in which a bandage has been allowed to soak, and is also smeared during its application, is of eminent service in cases in which the injury need not be daily under the eye of the surgeon. It insures rest by forming a solid case to the limb, and allows the patient to take gentle exercise without risk of disturbing the injury.

The *plaster of Paris bandage* has some advantages over the former, as it dries quickly and is much firmer. Dry plaster is to be well rubbed into the meshes of a common bandage (the meshes should be large), first on one side and then on the other, and as this is being effected the bandage is to be re-rolled. The limb to be enveloped must be protected either by a flannel or common roller. The plaster bandage is now applied around the limb in the usual way, and as it is unrolled it is to be well moistened with water, holding in suspension more or less plaster in order to insure firm support. The process should be quickly effected lest the plaster harden too soon.

The *many-tailed bandage*, *buckles and straps*, and *tapes*, are superior to the simple roller in some cases of fracture, in being readily adapted or removed without danger of disturbing the injured parts.

The *four-tailed bandage*, especially useful in injuries to the lower jaw, consists of a piece of wide roller split at either end into two portions to within a few inches of each other, the centre to correspond with the chin. The upper tail of either side is to be carried behind the head, and there fixed by a knot and bow; or, the ends crossing each other behind, may be brought forward and fixed on the forehead or side of the head. The lower tail of either side, carried directly upwards, may be tied together on the top of the head, or, crossing the vertex, may be tied under the chin.

The *broad roller* for the chest or abdomen may be single or double-headed.

To *remove* the common roller, for example from the leg, undo the fastenings at the upper end, and unroll in a direction opposite to that pursued in adapting the bandage, passing the bandage alternately under and over the limb, and collecting it into a tolerably neat ball, rather than to drag the end as each turn is unrolled.



FIG. 7.

The *handkerchief*, of varied shape and size, will be found useful in many cases. It is commonly used as a sling for the hand and forearm (Fig. 7), the whole length of which should be included to prevent fatigue of any one part, and

the hand should be elevated above the elbow to favour the return of blood, and avoid swelling.

The *anti-chordee bandage*.—To prevent erections during the night, three or four turns of a bandage may be made round the root of the scrotum and penis, so as to bind the two organs together; the weight of the testicles will prevent erection.

*Strapping*.—Besides its use in maintaining the apposition of the edges of wounds, similar general observations may be applied to it as to bandages. In cases of fractured ribs of one side only, broad pieces of strapping, from two to three inches wide, and long enough to reach from the spine to the sternum, are sometimes employed instead of a broad bandage. The strapping applied to the injured side only does not interfere with the movements of the opposite side.

In applying strapping to a wound, the adjoining surface should be wiped and dried, and then one end of the plaster should be fixed to the skin, first on one side of the wound, and to a moderate extent of surface. This done, the edges of the wound are to be held in apposition with the finger and thumb; and while traction is made on the adhering strapping, the integuments on the opposite side should be also drawn towards the wound, so as to favour relaxation at the wound, and at this moment the strapping is passed across the wound and fixed on the opposite side.

The effect of strapping thus employed may be

increased by adapting a compress of folded lint to each side of the wound previous to fixing the plaster as above described.

Unless the whole limb be bandaged or strapped from below upwards to the required extent, a single strip of plaster should not be made to cover the whole circumference of the limb; it would either interfere more or less with the cutaneous circulation, or prevent instead of assist approximation of the edges of a wound.

To remove strapping and other dressings from an open wound, commence at each end of the piece, raising the ends simultaneously towards the wound, so as to avoid tearing open the wound in any way. Under certain circumstances, dressings and bandages may be cut up by running a knife or pair of scissors along a director passed beneath them.

#### OPERATIONS.

*Operations* are either *minor* or *capital*: minor, such as a simple incision, or which usually cannot be said to endanger life; capital, such as an amputation, which cannot be performed without risk to life; at the same time it should never be forgotten that the most simple operation is occasionally followed by fatal consequences, and should, therefore, never be wantonly undertaken.

An operation implies a solution of continuity, effected by a cutting or wounding instrument; as,



for example, the ordinary straight scalpel, or bistoury, used in the performance of very many operations.

The most simple operation is *an incision*, whether straight or otherwise.

To effect incision, the scalpel is held differently, in accordance with the fancy of the surgeon, the result which it is required to produce, or the region in which it is employed.

*Incisions* may be single or multiple. A simple incision is usually made with one sweep of the knife, and should be effected with a sharp knife, so as to avoid causing unnecessary pain, and offer no obstacle to speedy union. A knife, however sharp, is a fine saw, and to effect the required incision must be drawn across the part to be divided, with more or less force, and not be pressed only upon the **part**. The length of incision decided upon, the integuments may, if necessary, be shaved, fixed and made tense, either by the operator's left hand, or by the aid of an assistant, care being taken not to disturb the relation of the integumental surface to the parts beneath. The scalpel held as a pen, either at a right angle or at an angle of  $45^{\circ}$  to the surface, is plunged into the integuments, which it is made to divide to the required extent, while carried towards or from the operator, and brought out after completing the incision at a right angle to the surface, so as to insure complete division. All secondary division of deeper parts should be made parallel to, and of the same length as the primary. In per-

forming a delicate operation, let the incision be rather long than short; it allows light to enter, gives space to work in, and cannot influence the result.

*Suture.*—The operation completed, it may be necessary to close the incision, the edges of the wound being approximated and kept in apposition by one of the varieties of suture, to effect which a needle and thread play an important part.

*Needles* are of various shapes and sizes, whether straight and cylindrical, straight and triangular, or curved and double-edged. The *hare-lip pin* has a button at one end, instead of an eye; it supports the *twisted suture*, the thread being adapted in the form of the figure 8 (see Fig. 12).

*Threads* are of various sizes and material, whether flaxen, silken, catgut, or metallic, according to the fancy of the surgeon, or the peculiar nature and seat of the wound.

Before using a suture, hæmorrhage should have ceased, all foreign bodies be removed, and the edges of the wound be adjusted by the eye and finger. If possible, the lips of the wound being held together, the needle should be passed through both at once, and at a depth in proportion to the tension to be resisted. The knot should be drawn tight enough to insure apposition of the edges of the wound without the risk of strangulation, either directly or indirectly, from swelling. Tension may be moderated by the use of strapping and a bandage,



and by a position favourable to the relaxation of integument and muscles.

Fig. 8 shows the ordinary *interrupted suture*, the knot being on one side of the wound that it may not interfere with close approximation of the lips of the latter. To effect this, a needle, armed with the requisite thread, is entered on one side of the wound




FIG. 8.




FIG. 9.

or through one lip of the incision, and brought out through the other side or lip. The edges of the wound being held in apposition, either a double knot or a single knot and bow is tied, and the suture is fixed.

The *uninterrupted suture* will be readily understood by a reference to Fig. 9.




FIG. 10.

The *quill suture* (Fig. 10) is made by passing a double ligature, and enclosing portions of quill, rolls of strapping, or elastic bougie, as *points d'appui*. This variety is employed when some force is requisite to keep the edges of a wound together, and also to approximate the deeper parts.

The introduction of a body capable of resisting traction prevents ulceration at the points of suture, by distributing the force over a larger area.

The *zigzag suture* (Fig. 11) operates in a manner similar to the former.




FIG. 11.




FIG. 12.

The *twisted suture* (Fig. 12) has been already noticed.

The *metallic suture*.—In many cases, the metallic suture, whether of silver or of annealed iron wire, will be employed with advantage, inasmuch as it gives rise to less local irritation than the ordinary thread does, when left in for a similar period. It may be fixed by a knot or twist, or by buttons or clamps passed along it; and, when adapted, squeezed upon and so fixed to it by a pair of appropriate forceps. These buttons and clamps have also the property of distributing the traction over a larger area, after the manner of the quill suture.

To *remove a suture*.—Previous to the removal of a suture, the edges of the wound, say in a stump, should be carefully maintained in apposition, by the appli-

cation of strips of strapping, or other means of support, passed between the points of suture. The stump should also be well supported by the hands of an assistant, lest the flaps separate by their weight alone. Sutures may also be removed at intervals of a day or more, those being taken away first which cause the greater amount of irritation.

The *serres fines* (Fig. 13) are delicate wire forceps, used instead of sutures in regions where the skin is very thin, as that of the prepuce; they are readily applied and removed.




FIG. 13.



FIG. 14.

Various *knots* are employed in surgery, as the *simple knot* (Fig. 14).

The *double-reef knot* (Fig. 15), a repetition of the former.

The *surgeon's knot* (Fig. 16), made by twisting one end of the ligature twice round the other end.



FIG. 15.



FIG. 16.

The *slip-knot* (Fig. 17) is very useful where the

above cannot be readily applied; it also is easily loosened and re-adjusted, and afterwards fixed by the simple knot.




FIG. 17.

The *clove-hitch* (Fig. 18) is the extending apparatus employed in the reduction of certain dislocations:




FIG. 18.

the more you pull, the more firmly it holds the part embraced by it.

## CHAPTER II.

### LIGATURE—APPLICATION OF LIGATURE TO TUMOURS.

LIGATURES are employed to check the flow of blood through its natural channels, and to cut off the supply of blood from abnormal growths, and so cause them to perish and fall off. In some few instances, the application of the ligature is only a temporary measure, as in venæsection at the arm, and the use of the tourniquet. Ligatures are of different material, whether of thread, of silk, of cord, of catgut, or of wire, according to the whim of the surgeon, and the uses to which they are to be adapted, and also of proportionate strength. For the ligature of arteries, the well-known silk thread is employed, small and round if the artery be healthy, larger and broader if the vessel be degenerated. A similar thread may be used for the constriction of tumours; and since these latter are of various shapes and sizes, the selection of the material and the mode of its application must necessarily differ.

Should the tumour to be removed be attached to the trunk by a narrow base, its pedicle may be constricted

by a single thread tied tightly round it, the skin having been previously divided so as to form a groove for the ligature to lie in, and also to occasion less pain and expedite the sloughing. Should the base of the tumour be broad, a needle armed with a thread may be passed under the base of the tumour in one, two, or more directions, thus isolating portions of the tumour, and rendering them susceptible to the ligature. Just before fastening the ligature, the tumour, if vascular and very tense, may be punctured with a lancet, in order to diminish its bulk.




FIG. 19.

Fig. 19 represents a subcutaneous tumour, the dark line being skin, and the dotted interior (*a*) the tumour itself, to be removed by three ligatures, of which the first (*c, d, e*) has been passed under the skin along part of the circumference, from *c* to *e*, on a curved cutting needle. A straight needle is now threaded with the same ligature, and passed across the base of the tumour (Fig. 20), entering at *c*, and




FIG. 20.




FIG. 21.

making exit at *b*, and carrying the thread (*d*) with it. Cut now the loop of the thread (*b*, Fig. 21), and



liberate the needle (*e*). By these means the upper segment of the tumour is inclosed, and also one thread placed *in situ*, ready to assist in the constriction of the central portion of the tumour when the




FIG. 22.

lower segment has been treated similarly to the upper. Fig. 22 shows the ligatures in position, and the tumour may be constricted at any moment by tying the ends (*a*, *b*, *c*).

In many cases it may be necessary to tighten the ligature daily. The most simple plan is to include, between the first and second knots, a thread which, on being pulled against the second knot, will loosen it, and permit of re-adjustment of the ligature. When practicable, the skin should be saved by dissecting it carefully off the surface of the tumour, if the subcutaneous method be not applicable to the case. Besides the above, the ingenuity of the surgeon will devise other modes of passing ligatures according to the requirements of the case: some practitioners pass needles across the base of a tumour, and endeavour to strangulate the mass by tying a cord below the needles.

The *figure 8* knot is applicable to many cases. A needle armed with a double ligature is passed across the base of a tumour, and brought out on the opposite side; care being taken to have several inches of ligature on either side of the tumour. Select one thread near the needle and divide it, leaving the



other thread still in the needle ; take now the originally free end of the thread just divided, and pass it through the eye of the needle, and thrust the latter, thus armed, across the tumour, at a right angle to the first ligature. A little careful manipulation will show that the figure 8 form given to each of the two ligatures, enables each one to constrict two quarters of the tumour.

## CHAPTER III.

### OPERATIONS ON THE VASCULAR SYSTEM.

CUPPING—VENÆSECTION AT THE BEND OF THE ELBOW; AT THE  
EXTERNAL JUGULAR VEIN—VARIX—NÆVUS—TRANSFUSION OF  
BLOOD AND INJECTION OF SALINE FLUIDS.

CUPPING is performed with the ordinary *cupping-glass*, of which there are many shapes and sizes, in proportion to the quantity of blood to be drawn and the extent of surface to which the glass can be applied. The operation is performed either with or without scarification; the latter method is termed *dry cupping*, and is effected by exhausting the air of the cupping-glass by the lighted torch of a spirit lamp, or some other inflammable material, placed in it till combustion can be no longer sustained. The oxygen of the air having been consumed, the flame goes out, and at this moment the mouth of the glass should be gently pressed upon the surface of the body, when atmospheric pressure will cause the blood rushing to the spot in order to fill the vacuum in the glass to raise and redden the integument. The

operation is completed, and may be repeated at pleasure on the adjacent tissues. Care should be taken to select a soft and even surface for the application of the cupping-glass, perhaps even by shaving the part. To withdraw blood, the glass having been removed, the *scarificator* should be applied to, or scarification be made with a very sharp instrument on the elevated integument. The skin divided, the air must be again exhausted, and the glass applied, when, if the operation is successful, blood will flow to the required quantity. It may be necessary to use the scarificator at more than one point, and to apply the glass repeatedly over the incisions. Should the integument be forced high into the glass, the edge of the latter may constrict the former, and hinder the flow of blood; to avoid which inconvenience the operator should raise the glass gently from the body, so as to relieve the constriction, but avoiding the entrance of air. The operation completed, wash and dry the incisions, and close them with adhesive plaster.

*Venæsection.*—Blood-letting is usually performed at the bend of the elbow, such position being convenient both for the surgeon and patient, and in the following way:—Tie a tape or finger bandage around the arm two inches above the elbow, sufficiently tight to prevent the return of blood up the arm through the superficial veins, but not so as to check the downward flow of blood through the brachial artery to the hand. Examine carefully the

relation of the veins at the bend of the elbow, and explore the surface with the finger, to ascertain that no artery be abnormally placed, as sometimes happens, and might, through negligence, be wounded. Ascertain the exact position of the median basilic vein with regard to the brachial artery, and select for the operation some portion of the vein not immediately over the artery. Support the arm of the patient by placing the palm and three inner fingers of the left hand behind the elbow, keeping the thumb and forefinger in front; the thumb to press on the vein below the position of the intended puncture, to prevent the escape of blood before a vessel can be placed to receive it, and the forefinger to press upon and steady the vein above the point of puncture. The lancet should be held by the semi-flexed thumb and forefinger of the right hand, the little finger of the latter resting on the fore-arm of the patient. Puncture of the integument and vein will be effected by extending the thumb and forefinger sharply, while the wound may be enlarged by causing the lancet to cut its way out in a forward direction. The vein should be opened obliquely, either from below, upwards, and inwards, or upwards and outwards. To facilitate the flow of blood, the patient may exercise the muscles of the wounded fore-arm by squeezing something with the hand. The operation completed, place the thumb of the left hand upon the wound, and remove the bandage from the arm; cleanse the arm with sponge

and water, and then put a thick pad of lint over the wound, and apply a figure 8 bandage to maintain the compress in position, and exercise pressure sufficient to prevent the further flow of blood. The student may practise the use of the lancet on the veins of a cabbage-leaf, with advantage.

Fig. 23 shows the relative position of the superficial veins and nerves in front of the elbow, also the brachial artery just as it is about to pass behind the aponeurotic expansion from the tendon of the biceps. Passing from without to within, are seen the cephalic vein (*a*), external to the biceps muscle, formed by the junction of the radial (*b*), and median cephalic vein (*c*); *d* marks the union of a deep vein with the median vein of the fore-arm, and its bifurcation into median cephalic vein on the outer side of the tendon of the biceps, and the median basilic vein (*f*) on the inner side of the biceps tendon, to which latter are joined the ulnar veins (*e*, *g*), so as to form the basilic vein (*i*). The median basilic vein is usually chosen for this operation because it is larger than the median cephalic, and more superficial than it, in consequence of




FIG. 23.

being, as it were, stretched over the aponeurotic arch coming from the biceps. In this region, however, large branches of the internal cutaneous nerve pass superficial to the vein, while the brachial artery (*h*) lies behind the vein; and for these two circumstances some persons bleed from the median cephalic vein. Again, it will be observed that the arrangement of veins in this region varies much, and in such cases it will be well to select the largest and most superficial vein in the neighbourhood.

Blood may likewise be drawn from any superficial vein, as from the veins of the scrotum, and external jugular vein. When operating on the external jugular vein, select a spot lying over the sterno-mastoid muscle. In this position the vein is




FIG. 24.

covered by the platysma muscle; and in order to favour the flow of blood through the wound, the



fibres of the platysma should be cut transversely, that is, from below upwards and outwards, thus allowing the divided muscular fibre to contract and hold the wound open, as it were, while the vein is divided obliquely. Pressure with the thumb below the point of puncture, or with a compress and bandage, will check the natural current of the blood, and render the vein prominent. Fig. 24 shows the mode of operating—*a*, the wound in the external jugular vein; *c*, the compress maintained in position on the vein by a bandage (*b*) carried under the opposite armpit; and *d*, the lancet held by the right forefinger and thumb. Pressure on the vein by means of the thumb or compress should always be kept up until the wound has been closed by lint and strapping, lest air enter the circulation and lead to a fatal result.

#### VARIX.

Various operations have been proposed and resorted to for the cure of varicose veins; and of these, obliteration by needle and ligature, and by subcutaneous division, rank first.

By *needle*: pass a needle transversely behind the vein, and a small portion of elastic bougie having been placed on the surface of the skin over and at a right angle to the needle, constrict the whole with moderate pressure by the twisted suture. The part may thus be left during from three to six days; also from three to six needles may be used on one extre-



mity. If swelling and inflammation be not excessive, the needles may be allowed to cut their way out.

By *subcutaneous section* : pass two needles transversely behind the vein, with an interval of one inch and a half. Having protected the skin either with a piece of bougie or cardboard, apply a ligature about each needle, beginning with the uppermost, tight enough to stop the circulation, but not to strangle the part. After the lapse of forty-eight hours, divide the vein subcutaneously between the ligatures, and apply a compress and bandage. After the lapse of another forty-eight hours the needles may be withdrawn. Care must be taken to pass the needle or pin behind and not through a vein.

#### NÆVUS.

Treatment by *ligature* as already described under article "Ligature."

By *pressure* : a mode only to be adopted when the disease lies over bone.

By *injection* of some irritant fluid, as tincture of iodine, or a solution of perchloride of iron: a puncture sufficiently large to admit the nozzle of a small syringe is made in the skin, and a quantity of the fluid, from five to fifteen drops, in proportion to the size of the tumour, is injected after *subcutaneous incision* has been adopted. Inflammation, followed either by obliteration and absorption or by suppuration and cicatrization, is the result.

By *seton* : one or more threads may be passed through the tumour.

By *vaccination* : applicable to very small examples of this disease.

By *subcutaneous incision* : the blade of a knife, or cutting needle, being passed in various directions, so as to break up or cut up the enlarged vessels.

By *actual cautery* : either by one or more wires being passed through the tumour, and heated by electricity, or by repeated puncture with a hot needle.

By *ligature* of one or more arteries, or even a main artery : applicable to those cases in which arteries enter largely into the formation of the tumour, and perhaps previous to the free use of ligatures or setons at various points, or under circumstances consequent on position, where the tumour cannot be treated locally.

By *caustics* : one of these agents being applied to the surface, or introduced into the interior, on a probe or needle.

By *excision* : the surgeon must cut wide of the tumour, otherwise bleeding may be profuse.

When this plan can be adopted, it should be had recourse to, because, when the wound heals, a linear cicatrix is the result ; but often, by other means which destroy much skin, an ugly scar is produced, and increases in size as the patient, if a child, arrives at manhood.

In all cases the surgeon should destroy as

little skin as possible, to avoid ugly scars and deformities.

TRANSFUSION OF BLOOD AND INJECTION OF  
SALINE FLUIDS.

This operative proceeding consists in laying bare a superficial vein of the arm by an oblique incision, and passing a ligature behind the vein, which is now to be opened to receive the nozzle of a syringe. The injection completed, the ligature and pipe, or syringe, are to be withdrawn, and the wound closed by compress and bandage.

## CHAPTER IV.

### OPERATIONS ON THE ARTERIES.

COMPRESSION—TORSION — CAUTERISATION — ARTERIOTOMY — LIGATURE—THE TENACULUM—FORCEPS—APPLICATION OF LIGATURE  
—ACUPRESSURE—LIGATURE IN THE CONTINUITY OF AN ARTERY  
—ANEURISM NEEDLE.

COMPRESSION is either *direct* or *indirect* : direct, when made upon the vessel itself, without the intervention of soft parts, as in wounds of the arteries of the hand, and during the performance of operations, by the tips of the fingers ; indirect, when made over the course of an artery, and something, such as the soft parts of the body, intervenes between the compress and the compressed. Compression may be either *partial* or *complete* : partial, where the flow of blood through an artery is moderated only, as in the treatment of aneurism, by pressure ; complete, when the current is quite stopped, as it should be, during the performance of certain operations. The usual means of compression employed during operations are either the fingers of a trustworthy assistant or the tourniquet ; the former means is preferable, provided that the operation does

not last long enough to tire the fingers of the assistant, who can, however, under most circumstances, be replaced by another; in this way, too, the venous circulation is not interfered with, and the patient loses less of the vital fluid than when the tourniquet is used. Of this instrument there are many varieties; the most simple consists of a pad to be placed over the artery, and exercising pressure thereon by means of a strap going round the limb and fastened by a buckle. This strap is objectionable, because it hinders the ready return of blood through the superficial veins. The best forms of tourniquet will be hereafter referred to.

When about to apply compression, the surgeon selects a spot at which the artery is comparatively superficial and lying over bone, against which it may be compressed. It will be readily understood that the skin will not bear the pad of a tourniquet pressing on it for a length of time; if, therefore, it be necessary to exert pressure on the course of any artery during a long period, two tourniquets should be adapted and tightened alternately, or one tourniquet and a weight suspended from a cradle, for example, as in the treatment of popliteal aneurism.

*Digital* compression prolonged over many hours is a favourite method of treating some varieties of aneurism. In a case of popliteal aneurism under the author's care, digital compression effected a cure in less than twenty-four hours, when various other methods had failed.

A pebble twisted up in a handkerchief, and the latter tied tightly round the limb; a wet and tightly rolled bandage; a door-key, the handle of which is protected by a strip of lint wound round it, are good substitutes for the tourniquet.

*Torsion.*—When vessels bleed, and it is important to close the wound without ligatures, the extremity of the divided artery being seized by a pair of forceps, should be twisted several times on itself, and the channel remaining closed, a further flow of blood is rendered impossible.

Two kinds of clasp-forceps are made for this purpose, both with broad nibs, but one with, and the other without elaws. The instrument without elaws is to be used when the artery can be fairly seized; that with teeth is to be employed when the end of the vessel has become retracted, and some surrounding tissue must be included. The extremity of the artery is to be seized in the direction of its axis, and the forceps is then to be rotated also upon its axis until a sense of thorough yielding on the part of the vessel is appreciated by the operator, and then, when the instrument is removed, the tortured end of the vessel should have no tendency to untwist. The femoral artery has been repeatedly twisted successfully.

*Cauterization.*—The actual cautery may be used with advantage in regions in which, in consequence of the depth of the wound, a ligature cannot be applied; also in hæmorrhage from bone. In the



latter case hæmorrhage may be stopped by breaking down the cancelli at the bleeding point.

*Arteriotomy.*—The vessel usually selected for this operation is the anterior branch of the temporal artery (Fig. 25, *a*). It is easily felt through the skin,



FIG. 25.

and can be readily compressed. Should this branch be small, the main trunk (*b*) may be opened, just over the zygoma, in front of the tragus.

To bleed from an artery, ascertain its position, and shave the part, if necessary; place the points of the forefinger and of the middle finger of the left hand with an interspace of about an inch upon the artery, in order to steady it; then, holding the knife in the



right hand, divide the tissues layer by layer at right angles to the course of the vessel, till the artery be reached and opened. The desired quantity of blood having been taken, complete the section of the artery, and apply a compress and bandage. If the hæmorrhage be not controlled by this means, place a ligature on both ends of the divided vessel.

*Ligature.*—The ligature generally used in this country in operations on arteries, is made of silk, waxed previous to being applied. Arteries are ligatured under two conditions; either at their extremity after division, as after amputation, or in their continuity, as in the operation for true aneurism.

In the case of ligature of the extremity of an artery, various instruments have been invented to aid in the application of the ligature; and of these two are in general use, the dissecting forceps and the tenaculum.

The *tenaculum* may be described as a sharp-pointed hook, used to secure an artery when it has retracted more than ordinarily, and cannot be readily reached by the forceps. Generally some portion of the adjacent soft tissues are included by the ligature, thus delaying the separation of the same; the tenaculum therefore should never be used except under extreme necessity. Sometimes the ligature will not hold even when the tenaculum has been employed. An instance of this kind happened to me after an amputation of the thigh. The end of the femoral artery was surrounded by tissues so thick-

ened by old inflammatory deposit, that I could secure the vessel neither with the forceps nor with the tenaculum. I accordingly formed, by careful dissection, a pedicle of soft tissue including the artery, and, passing a double ligature on a needle, secured each half. The patient recovered.

The *forceps* most under the control of the surgeon is the common dissecting forceps, with moderately broad points. Many others are used, some with springs or fastenings, to maintain the points of the instrument in contact when so placed; others with springs and claws. These latter may be used by a surgeon operating without assistants. Having reflected upon the position of the chief vessels of the part, the surgeon should proceed to tie them in the order of size. The extremity of the artery being taken hold of by the forceps, the operator must ascertain by pulling *very gently* upon the vessel, and so isolating it *slightly*, that the adjacent soft parts are not included, whether muscle, fibrous tissue, vein, or nerve, lest pain be occasioned, and the separation of the ligature be delayed. To assist him the surgeon may use either his finger-nail or a second pair of forceps. The artery seized, an assistant manœuvres to cast a ligature around the forceps, and holding one end of the thread in each hand forms the *simple knot* (Fig. 14) loosely about the forceps, gradually tightening and reducing the size of the loop thus formed until it encircles the artery, when it should be tied, so as to divide the two inner coats of the

vessel and strangulate the outer. The assistant must avoid tying the end of the forceps instead of the artery, and, when fixing the ligature permanently upon the artery, must not disturb the vessel by dragging or pulling upon it, lest he interfere with the relation of the vessel to its sheath, and, by tearing the vasa vasorum, deprive the coats of the artery of their requisite supply of blood.

To ensure a careful application of the ligature, the assistant, holding one end of the thread firmly in each hand, should place the point of one forefinger upon either thread in close proximity to the artery, and pull or tighten the thread by flexing the thumb, while the artery is maintained in position by the points of the fingers. Fig. 26 shows the mode of fixing a ligature in the continuity of an artery, also




FIG. 26.

after the manner above described. To complete the ligature, tie a second knot like the first, or the surgeon's knot. The ligature completed, either twist

the two ends together, or cut one end off near the artery, tying a knot in the distal extremity of the ligature of the main artery. Should there be more than one ligature, bring them all out at one angle of the wound, if possible, so as to interfere as little as need be with the healing process. The occurrence of hæmorrhage having been guarded against by ligature of the chief vessels, pressure, which up to this moment has been maintained upon the continuity of the main artery, should be suddenly removed, in order to test the efficiency of the ligatures already applied, and to indicate the necessity for any further application.

*Carbolic Ligature.*—The surgeon may prefer to treat his ligature with carbolic acid before using it, and to cut it short as advised by Mr. Lister, and as was successfully practised by the author in a case of ligature in the continuity of the common carotid artery. The wound healed over the silk ligature.

*Sponging.*—When applying ligatures to the extremities of arteries, a sponge is generally used to remove extravasated blood, and expose a bleeding orifice. For this purpose, the sponge should have been freed from dirt by washing, be of fine texture, and soft, and just moist. It is to be pressed with moderate force upon the surface to be examined, and when time has been allowed for absorption by it of effused fluids, should be quickly removed, so as to afford the operator the opportunity of seeing the

exact spot whence the blood flows. The sponge is to be *pressed upon* and not *rubbed* roughly over the raw surface.

*Acupressure.*—The second and third methods of Sir J. Y. Simpson will sufficiently illustrate the operation :—

“*Second Method.*—A common short sewing needle, threaded with a short piece of iron wire for the purpose of afterwards retracting and removing it, is dipped down into the soft textures a little to one side of the vessel, then raised up and bridged over the artery, and then finally dipped down again, and thrust into the soft tissues on the other side of the vessel. In bridging over the vessel, care must be taken to press the end of the needle down upon the mouth or tube of the bleeding artery with force sufficient to shut the arterial tube and arrest the hæmorrhage. The end of the finger pushed against the side of the projecting portion of the needle is often required thus to compress and close the vessel adequately, before the tip of it is sent onwards and fixed in the tissues beyond.

“*Third Method.*—This method is the one which will probably be most frequently followed. It consists in compressing the vessel between the threaded sewing needle and a duplicate of passive iron thread. Here, as in the method last related, the cutaneous surface is left intact ; but the needle is passed *below*, instead of over or above the artery. The point of the needle is entered a few lines to one side of the



vessel, then passed under or below it, and afterwards pushed on, so that the point again emerges a few lines beyond the vessel. The noose or duplicature of wire is next thrown over the point of the needle; then, after being carried across the mouth or site of the vessel, and passed around the eye-end of the needle, it is pulled sufficiently tight to close the vessel; and lastly, it is fixed by making it turn by a half-twist or twist around the stem of the needle. A slight half-twist usually fixes a rigid wire-thread quite perfectly. If the operator prefers, he may keep the two threads of the noose open after they bridge across the artery, and tie them below or behind the eye-end of the needle, in the form of a common single or double knot. A common silk thread may be used in the same way. But the tie with any kind of thread takes much longer time than the twist with metallic thread, and certainly is not more efficient. When in either case—whether the twist or tie has been adopted—the operator wishes to remove this simple aëupressure apparatus after a period of, say five, twenty, thirty, or more hours, all he has to do in order to withdraw the needle is to pull it out, by dragging at the twisted wire with which it is threaded. The noose of wire-thread is thus at once loosened and liberated, and can be withdrawn. To distinguish easily between the wire-thread passed through the eye of the needle and the duplicature of wire, it is always convenient to mark the former by having it plaited



or twisted ; or a knot for the same purpose can be tied on the end of it."

The advantage claimed for acupressure over the ligature is, that from twenty-four to seventy-two hours after operation all foreign bodies are removed from the wound.

*Ligature in the continuity of an Artery.*—Previous to the application of a ligature in the continuity of an artery, the operator should contemplate with his mind's eye the relative anatomy of the region in which he is about to operate, and reflect upon the possible abnormalities which he may encounter in his progress. With the subject or patient before him, the surgeon should observe the various points of bone, the position of known muscles, ligaments, nerves, veins and tendons, which bear a certain relation to the course of the artery, and would indicate the position for the first incision. He may also mark out upon the surface, with his eye, an imaginary line drawn between certain points, indicating the normal course of the artery, and, if the subject be living, test the correctness of his observation by the pulsation of the artery. The instruments requisite are—scalpel, director, pair of dissecting forceps, couple of copper spatulas or of blunt hooks, aneurism needle, ligatures and sutures, with compress, strapping, and bandage.

The subject should be placed on the table, in a position, if possible, convenient both to the operator and to the patient. If necessary, the part should be

shaved, and the operation begun by incising the skin and superficial fascia, immediately over and in a line with the artery in most instances. To indicate the length of incision, to steady the skin, and so to assist the action of the knife, the operator's left hand may be allowed to press firmly on the patient with the points of the fore and middle fingers separated and placed so as to mark the points at which the incision is to be begun and to be terminated. Let this incision be free and cut cleanly at both ends, so as to allow plenty of space to work in, and light to enter. The edges of the wound will now become separated by the natural elasticity of the skin, and the surgeon must take care that his assistants do not drag upon the skin in such a manner as to alter the relation of the wound in the integument with the deeper structures. The various structures must now be divided in turn on a director,\* the operator carefully observing the nature and course of the tissues as they come into view, with the object of ascertaining his position with regard to the artery. To use the grooved director, the operator first raises

\* It is scarcely necessary to add that precise instructions in reference to the *director*, &c., are intended only for the inexperienced. The surgeon who is personally familiar with operations will often complete with facility the ligature of an artery with the aid of a scalpel, forceps, and needle only. The author has himself ligatured twenty-three arteries, varying in size from the anterior tibial to the common iliac, and the majority without a director. Each layer (*couche par couche*) of tissue is to be severed the length of the skin wound and put aside with the blade of the knife before another layer is touched. All bruising is to be avoided.

the fascia in the centre of the wound with the dissecting forceps, and makes a small incision with the scalpel held in the right hand, sufficiently large to admit the end of the director, the flat of the blade being towards the patient. The point of the director is now introduced and pushed gently, rather beyond one extremity of the wound, behind the tissue to be divided, and the knife being now run along the groove, sets the director free. The other half of the fascia is to be treated in a similar manner, and so all the layers of fascia till the sheath of the vessel be reached. Large veins and nerves and muscles should not be unnecessarily divided, but be held aside by a blunt hook or spatula. In using a director care should be taken, while passing it behind tissues, to keep the point well up against the structure to be divided, by either elevating or depressing the handle, in order to avoid injury to deeper structures. The sheath of the vessel being reached, it is now to be seized with the forceps (Fig. 27), and nicked sufficiently only to admit the point of the aneurism needle. This done, the knife may be laid aside; and holding the divided sheath, first on one side of the artery, and then on the other side with the forceps, the operator gently and cautiously separates the sheath from the artery with the end of a director carefully introduced between them, so as to form a passage for the needle. The sheath must be separated from the artery as little as possible longitudinally, lest, by dividing the small

vessels which nourish the coats of the artery, serious results follow. To assist in reaching an artery, strong unyielding fasciæ may be nicked transversely so as




FIG. 27.\*

to widen the wound, and muscles should be put into a state of relaxation; also seek an artery through an intermuscular space rather than through the substance of a muscle itself.

The *aneurism needle* (Fig. 28) is a blunt hook, with an eye at the extremity to carry the ligature, the curve being adapted to the requirements of the case. During the introduction of the aneurism needle,

\* Fig. 27 shows the sheath of the vessel seized by the forceps, and the knife held ready to nick the sheath, the flat of the blade being towards the patient. Also, the artery exposed when the sheath has been nicked.

especial care must be taken to include nothing but the artery, and to avoid wounding any companion vein, by keeping the point of the needle well up against the artery, but without piercing its walls.



FIG. 28.\*

The needle being armed with the ligature, the operator holding one side of the divided sheath with the forceps in the left hand, enters the end of the needle on that side on which the most important organs are situated, and brings it out on the opposite side. One thread of the ligature must now be seized with a pair of forceps, and held firmly while the needle is withdrawn by the way it came, leaving a single ligature behind the artery. Sometimes the point of the needle requires to be freed from some areolar tissue which it has carried before it in its passage behind the artery; it should be liberated by cutting (not scraping) upon the end of the needle itself. Previous to completing the ligature, the operator should ascertain if he has placed it around the right vessel, and to do this must press with the point of his forefinger upon the artery, while, at the same time, elevating it slightly from its bed by pulling equally on both ends of the ligature. If by this means pulsation in the aneurismal sac be stopped, the operation has been so far successful, and the

\* Walters, Moorgate-street.



ligature may be completed by tying a double-reef knot (Fig. 15).

The ends of the ligature may now be twisted, brought out of the wound, and fixed in a convenient position by strapping; then sutures, strapping, compress, and bandage having been applied, the operation is finished. The limb must be kept warm, and points of bone be protected from pressure. The limb should also be placed in such a position that the artery which has undergone ligature may be relaxed as much as possible.

The ligature of an artery, such as the femoral, becomes detached from the twelfth to the twentieth day, and its tenacity may be occasionally tested by twisting it upon itself with the finger and thumb. From what has been said, it will appear that, in order to ligature an artery with the hope of a favourable result—

1st. A free incision should be made usually, but not invariably, over and parallel to the course of the artery.

2nd. Divide important organs which come into view as little as possible.

3rd. Disturb the relation of the artery to its sheath in the least necessary degree.

4th. Use a sharp, rather than a blunt instrument, to divide tissues.

5th. Be sure that the ligature has been placed around the artery, and not around any other organ; also, that no other organ is included with the artery.



6th. Place the ligature so far from the disease as is convenient, and at a distance, if practicable, from the origin of a large branch.

7th. Ascertain that the right artery is the subject of the ligature.

8th. The length of the incision made will depend partly upon the degree of obesity and muscularity of the subject.

N.B.—In the case of wound in the continuity of an artery, seek the bleeding orifice, and place a ligature on either side of it, and close to it, and not upon the main trunk, at a distance from the wound.

## CHAPTER V.

### LIGATURE OF SPECIAL ARTERIES.

*The Arteria Innominata. Anatomical relations.*—This artery runs from below upwards, and from left to right, from the arch of the aorta to the right sterno-clavicular articulation, opposite to which it divides into right carotid and right subclavian arteries. In front of it are the first piece of the sternum, the origins of the sterno-hyoid and thyroid muscles, and the left vena innominata crosses it; on the left are the root of the left carotid artery, and higher up the trachea; on the right is the right vena innominata; behind, are the trachea at first, and then the longus colli muscle.

### OPERATION.

Various incisions have been proposed to facilitate the ligature of this vessel, and of these the following is convenient.

External indications,—a fossa or pit above the clavicle, marking the cellular interval between the two heads of the sterno-mastoid muscle, more or less

visible, in proportion to the non-muscularity of the subject.

The shoulders of the patient being raised, the head thrown back, and the face turned to the left, the sterno-mastoid muscle is put on the stretch, and the sternal and clavicular origins, with the intervening fossa, can be both seen and felt. Incise the skin, superficial fascia, and platysma, and deep fascia, to the extent of three inches, directly upwards over the fossa, between the muscular fasciculi, the incision being begun rather below the clavicle; now throw the head slightly forwards and separate the heads of the muscle with the fingers, after dividing the connecting areolar tissue; divide carefully on a director the layers of deep cervical fascia, which conceal the sheath, and also, if necessary, the sterno-hyoid and thyroid muscles transversely. By this proceeding, if the muscular fasciculi be well separated by assistants, the origin of the carotid and subclavian arteries is readily found, and the *arteria innominata* reached. The ligature should be passed from right to left, in order to avoid implicating the right *vena innominata*. While using the knife, the position of the anterior jugular vein behind the sterno-mastoid muscle, and also of the middle thyroid vein passing outwards across the root of the carotid artery to open into the internal jugular vein, must not be forgotten. Fig. 29 shows *a* the internal, and *b* the external heads of the sterno-mastoid muscle forcibly separated by hooks, and exposing to view embedded

in more or less areolar tissue, *c*, the vertebral artery; *d*, the pneumogastric nerve; *e*, the recurrent laryngeal nerve; *f*, the internal jugular vein, pulled aside; *g*, the first part of the subclavian and its branches; and *h*, the arteria innominata, with the ligature passed.




FIG. 29.

I have found the above incision to be enlarged with advantage by dividing along the clavicle the integument and sternal origin of the sterno-mastoid muscle, thus forming a flap.

*Another method* consists, the surgeon standing on the left-hand side of the patient, in making an

oblique incision across the root of the neck, commencing half an inch below the right sterno-clavicular articulation, and terminating about two inches above the sternum at the inner margin of the left sterno-mastoid muscle. After dividing skin, superficial and deep fasciæ, the right sterno-thyroid, and perhaps also the sterno-hyoid muscles, should be divided transversely on a director, or be held aside, while the inferior thyroid veins are wounded as little as possible. The intervening layer of cervical fascia should now be cautiously divided, and the forefinger of the left hand following downwards, the trachea will readily reach the artery, around which from before, backwards, and from right to left, the ligature is to be passed.

The application of a ligature to arteries at the root of the neck will be facilitated by throwing the head backwards and depressing the shoulder. Moderately large veins, too, if they must be divided, should be ligatured previous to division, both above and below the intended point of section.

*Common Carotid Artery. Anatomical relations in the neck* (Fig. 30.)—This vessel extends, in a direction upwards and outwards, from the bifurcation of the arteria innominata opposite the sterno-clavicular joint, to the upper border of the thyroid cartilage, where it divides into internal and external carotid arteries. It lies in a groove between the sterno-mastoid muscle on the outside, and the trachea and larynx on the inside, and may be here compressed



against the roots of the cervical transverse processes by pressure directed backwards.

In front, the artery is crossed about its middle and opposite to the cricoid cartilage by the anterior belly (*i*) of the omohyoid muscle. *Above* this muscle the vessel is comparatively superficial, being covered




FIG. 30.

by skin, superficial fascia, platysma, deep cervical fascia, and somewhat overlapped by the anterior border of the sterno-mastoid muscle. Parallel to, and either without or within the sheath, is the descendens noni nerve (*h*); crossing it from within outwards, the superior thyroid vein (*g*). *Below* the omo-



hyoid muscle the artery is deeply placed, being covered in by skin, superficial fascia, more or less platysma, layers of deep fascia, sternal head of sterno-mastoid muscle, sterno-hyoid and thyroid muscles, and is crossed from within outwards by the anterior jugular (*l*) and middle thyroid veins. The internal jugular vein partially conceals the artery in front, excepting at the root of the neck, where is an interval in which is lodged the pneumogastric nerve (*k*). The lateral lobe of the thyroid body has an anterior relation to this vessel. The artery is attended in its sheath by the internal jugular vein to its right side, and the pneumogastric nerve behind and between the two blood-vessels. Behind the sheath, the artery rests on the recurrent laryngeal nerve, inferior thyroid artery, sympathetic nerve, longus colli and rectus anticus major muscles; internally it is bounded by the trachea and larynx; and on the outside by the internal jugular vein and pneumogastric nerve.

The above description is applicable equally to the left common carotid in the neck, with this exception, that the internal jugular vein almost conceals the artery at the root of the neck.

#### OPERATION.

The common carotid artery may be ligatured at any point of its course, and with facility at the *point of selection above* the omohyoid muscle. An imaginary line on the surface drawn from the

sterno-clavicular joint to a mid-point between the mastoid process and the angle of the lower jaw, will sufficiently indicate the course of the artery. The head being thrown back, and the face turned to the opposite side, the surgeon ascertains the relation of the anterior border of the sterno-mastoid muscle to the artery, and will observe that the artery above the cricoid cartilage can be readily felt lying along the border of this muscle, and slightly overlapped by it.

To expose the artery, an incision begun opposite to the cricoid cartilage, and carried upwards to the extent of about two and a-half inches, or begun opposite the greater cornu of the hyoid bone and carried downwards to a similar extent, along the inner border of the sterno-mastoid muscle, should divide in order, skin, superficial fascia, platysma, and deep fascia, and expose the fibres of the sterno-mastoid muscle. The edges of the wound being now held apart, and the superior thyroid vein and descendens noni nerve avoided, the sheath of the vessel should be opened so as to admit the aneurism needle to be passed from without inwards. The coats of the internal jugular vein are so thin, and the vessel is often so close to the artery, that unless great caution be used, the vein will either be mistaken for fascia and opened with the knife, or perforated by the aneurism needle. Should the vein be injured, the wound only,\* and not the whole calibre

\* I adopted this mode successfully when assisting a friend in the removal of a tumour from the neck.

of the vein, may be closed by a fine ligature. To facilitate the passage of the aneurism needle, the vein may be compressed by the finger introduced at the upper angle of the wound. The pneumogastric nerve must be carefully avoided by the needle. As a guide to the artery, the course of the fibres of the various muscles exposed should be studied; those of the sterno-mastoid running from above, downwards and forwards, those of the sterno-hyoid and thyroid downwards and outwards.

To tie the common carotid *below* the omohyoid muscle, an incision, three inches in length, beginning at the sternum and carried upwards, should be made, also along the inner border of the sterno-mastoid muscle; but the operator must recollect that since the sterno-mastoid muscle crosses the artery obliquely in passing from the mastoid process to the sternum, the incision made as directed is not immediately over the artery, but internal to it. The skin, superficial fascia, platysma, and deep fascia being divided, the head should be carried slightly forward, whilst the sterno-mastoid muscle is pulled on one side, and the sterno-hyoid and thyroid muscles either similarly treated on the other side, or severed. In opening the sheath and passing the ligature on the left side of the neck, the anterior relation of the internal jugular vein to the artery\* must not be forgotten.

\* The author, Mr. Heath, and others, have tied the common carotid and subclavian arteries simultaneously, for suspected innominate aneurism.

The situation *best* adapted to expose the root of the common carotid artery on the right side, is that recommended for the ligature of the brachio-cephalic trunk, viz., the interval between the sternal and clavicular origins of the sterno-mastoid muscle.\*

Fig. 31 shows one incision, made sufficiently long at the inner margin of the sterno-mastoid muscle to expose the common carotid artery both above and below the omohyoid muscle: *a* is the anterior belly of the omohyoid muscle; *b*, the common carotid artery; *c*, the internal jugular vein; *d*, the pneumogastric nerve; *e*, the sterno-mastoid muscle pulled aside.†

*External Carotid Artery. Anatomical relations.*—This vessel extends from the bifurcation of the common carotid artery opposite the upper border of the thyroid cartilage, to the neck of the condyle of the lower jaw. A line on the surface, drawn from a point midway between the angle of the jaw and the mastoid process, downwards and forwards in the direction of the cricoid cartilage, will mark the

\* In an instance in which I tied the lower part of the common carotid, in the Crimea, for secondary hæmorrhage, after wound of an artery in the pterygo-maxillary fossa, the anatomical relation of parts was so altered by swelling that I accidentally ligatured the vessel between the two heads of the sterno-mastoid muscle. My attention was called to this mode of exposing the common carotid by observing that in Paris the man who injected the bodies with preservative fluid, selected this spot for exposing the artery with ease.

† It will be observed that in the plates the relative anatomy is not strictly correct, because, were it so, important organs referred to could not be displayed on paper.

course of the artery in the locality in which it is comparatively superficial. It is here covered in, before it is crossed by the digastric and stylo-hyoid muscles and




FIG. 31.

the hypoglossal nerve, by the skin, superficial fascia and platysma, deep fascia, and slightly overlapped by the sterno-mastoid muscle. The internal carotid artery is on a plane, somewhat behind and external to the external carotid artery in this region, as is also the internal jugular vein. The facial and lingual veins cross the external carotid artery from within outwards.

#### OPERATION.

To place a ligature on this artery, an incision two and a half inches in length should be made in the



direction already given, the centre of the incision being just below the level of the greater cornu of the hyoid bone. Divide skin, superficial fascia and platysma, deep fascia, and, if necessary, ligature and divide veins which cross the incision, and also tie any branch of artery which may be troublesome. Hold aside or remove any lymphatic glands which come into view. The edges of the wound should now be separated by assistants; and the sheath opened as usual, the aneurism needle may be passed from without inwards so as to avoid injury to the internal carotid artery.

*The Internal Carotid Artery. Anatomical relations in the Neck.*—The internal carotid extends in the neck from the bifurcation of the common carotid to the base of the skull. Below the digastric and stylo-hyoid muscles, this vessel, like the external carotid, is comparatively superficial, and can be reached with tolerable facility in its position somewhat external to and behind the external carotid artery, and having the internal jugular vein to its outer side. But as the internal carotid ascends, it passes internal to the external carotid artery, and is much deeper than it, lying along the side of the pharynx and on the prevertebral muscles.

Thus deeply situated beneath important structures, it will be readily understood that the internal carotid artery cannot be ligatured, without the risk of doing serious injury, above the point at which the posterior belly of the digastric muscle crosses



it. Guthrie has described an operative proceeding by which he proposed to tie the vessel if wounded high up. It is, however, so complicated that almost any other mode should be tried first, especially one adopted by Dr. Keith, and attended by success. "An incision was made from below the ear, along the ascending ramus of the lower jaw to below its angle, and a ligature passed around the vessel with less difficulty than could have been anticipated."\*

#### OPERATION.

To tie the internal carotid artery just above its origin, an incision should be made over it, and of dimensions similar to that employed to expose the external carotid, but behind the latter, and, as it were, a continuation of that used to expose the common carotid artery. The same parts will be divided as in exposing the external carotid artery; and the sheath being opened, the aneurism needle should be passed from without inwards between the internal jugular vein and the artery, and be brought out between the internal and external carotid arteries.

*Superior Thyroid Artery.*—This vessel may be exposed by an incision somewhat internal to, but parallel to, that made to lay bare the external carotid artery. It should be about two inches in length, and its centre should correspond to the upper

\* A rather short description of the mode of performing a difficult operation!

border of the thyroid cartilage. After dividing the skin, superficial fascia, platysma, and deep fascia, the artery will be found passing upwards and inwards previous to bending downwards, and probably attended by its companion vein, which latter may or may not receive the lingual vein.

*The Lingual Artery. Course and anatomical relations.*—This vessel usually arises from the external carotid just below the greater cornu of the hyoid bone, and, passing inwards, forwards, and upwards, gets above the hyoid bone, and under cover of the hyo-glossus muscle.

#### OPERATION.

To expose the vessel, turn the face to the opposite side and make an incision one-and-a-half inches in length, just above the great cornu of the hyoid bone and parallel to it, the centre of the incision to correspond with the point of the greater cornu, which should be made prominent by pressing upon the opposite side of the bone. Divide skin, superficial fascia and platysma, and deep fascia. The edges of the wound being separated, look for the posterior belly of the digastric muscle, passing downwards and forwards; and, just below this, for the white cord of the hypoglossal nerve, also passing forwards (Fig. 30). Feel for the greater cornu of the hyoid bone, and observe the upward course of the fibres of the hyo-glossus muscle; and if its free border be visible, the artery will be found immedi-

ately behind it; should the free border not be visible, a few fibres of the hyo-glossus muscle divided transversely will allow the artery to be seen and ligatured. The facial vein, if seen, should be held on one side.

*Another Mode.*—This vessel may also be ligatured in front of the posterior belly of the digastric muscle, by an incision begun nearer the middle line of the neck, but the submaxillary gland must be disturbed in order to reach it in this position, where it lies in a triangular space, bounded by the two bellies of the digastric muscle, and the hypoglossal nerve above, forming the base of the triangle. The hypoglossal nerve is superficial to the hyo-glossus muscle, but the lingual artery is beneath this muscle.

*The Facial Artery.*—This vessel, after passing deeply under the jaw, becomes superficial on the face. It first occupies a groove in the border of the lower jaw, an inch in front of the angle; then passes upon the side of the jaw, in front of the masseter muscle, upwards and inwards towards the angle of the mouth. While on the side of the jaw the vessel can readily be felt pulsating, and may be ligatured by an incision made over it and parallel to it. The accompanying vein should not be included in the ligature.

An incision made transversely, instead of parallel, to the course of the artery, will be less likely to injure branches of the facial nerve, and may be preferred on that account.

*The Occipital Artery.*—This vessel may be exposed as soon as it has passed backwards from under cover of the mastoid process. On the surface, a line drawn from behind the mastoid process of the temporal bone towards the posterior occipital protuberance will mark the course of the artery. An incision made in the above direction, dividing the skin, aponeurosis of the sterno-mastoid muscle, and also the splenius capitis muscle, will expose the artery.

*The Temporal Artery.*—This vessel, as already mentioned in reference to arteriotomy (Fig. 25), may be readily exposed, as it lies on the zygoma, about one-third of an inch in front of the tragus. An incision one inch in length should be made over and parallel to the course of the artery, dividing the integuments and some dense areolar tissue covering the artery. The temporal vein and auriculo-temporal nerve accompanying the artery must not be included in the ligature. The vein usually is behind the artery.

*The Subclavian Artery.*—This vessel extends, on the right side from the bifurcation of the innominate artery, opposite the sterno-clavicular articulation, to the lower margin of the first rib. In its course it forms a curve, with the convexity upwards, and, for the sake of description, is divided into three portions by the position of the scalenus anticus muscle, which corresponds to the second part of the vessel. The vessel on the left side, in the two outer thirds of its

course, corresponds to a similar extent of the right subclavian artery; while its first portion extends almost vertically from the arch of the aorta to the inner border of the anterior scalenus muscle, behind which it passes outwards at nearly a right angle. The left subclavian artery is therefore more deeply placed in its whole course than the right subclavian artery. Both may be compressed, above the clavicle, upon the first rib, with the handle of a door-key protected by lint folded tightly round it.

The right subclavian artery may be ligatured in any part of its course with more or less difficulty, while ligature of the first part of the left subclavian artery may scarcely be attempted in consequence of its complicated relations.

FIRST PART.—*Anatomical relations.* In front are integument, platysma more or less, deep fascia, sterno-mastoid, sterno-hyoid, and sterno-thyroid muscles, cervical fascia, internal jugular vein, vertebral vein, pneumogastric nerve, phrenic nerve. Below is the pleura. Behind, the recurrent laryngeal nerve and the sympathetic nerve.

#### OPERATION.

The vessel may be best exposed in this situation, by a vertical incision (see Fig. 29) three inches in length made opposite the interval between the sternal and clavicular heads of the sterno-mastoid muscle, dividing skin, superficial fascia, more or less platysma, deep fascia, cellular connections between



the heads of sterno-mastoid muscle, cervical fascia, sterno-hyoid and thyroid muscles (which may be cut transversely if necessary, or held aside), and cervical fascia. The veins and nerves referred to must be carefully held aside; and the sheath having been opened, the aneurism needle should be passed from before backwards, and from below upwards, keeping the point of the needle close to the vessel, lest the bag of the pleura be opened.

THIRD PART.—*Anatomical relations.* Here (Fig. 32) the vessel (*b*) lies in the postero-inferior triangle of the neck, a space bounded internally by the sterno-mastoid muscle (*e*), above, by the posterior belly of the omohyoid muscle, and below, by the middle third of the clavicle. The vessel is covered in by skin, superficial fascia, platysma, and layers of cervical fascia; running parallel with and behind the clavicle, are the supra-scapular artery and vein; crossing the vessel from above downwards, and perforating the cervical fascia to join the subclavian vein, is the external jugular vein. Above, external to and behind the artery, are the nerves of the brachial plexus (*a*); below, the artery rests on the first rib (*c*); and in front and below it is the subclavian vein; in front, and internal to the artery, is the scalenus anticus muscle (*d*), attached to the tubercle on the first rib, and separating the subclavian artery from the subclavian vein.

In some muscular subjects the trapezius and sterno-



mastoid muscles take origin each from half the clavicle. In these instances, the subclavian artery




FIG. 32.

would here be covered by an additional muscular layer.

#### OPERATION.

To expose this vessel, the patient having the head thrown back and face turned to the opposite side, and the shoulder depressed so as to lower the clavicle and render the artery as superficial as possible, make an ink-mark over the artery, and then draw the integument down from the neck upon the clavicle, and divide it upon the middle of the

bone to the extent of three inches; in this way the skin, superficial fascia and platysma are divided without the risk of wounding the external jugular vein. On removing the impediment, the elasticity of the skin will carry the wound upwards, and allow it to correspond to the position of the artery above the clavicle, as in the figure. If it be necessary, divide either the sterno-mastoid or the trapezius muscle or both to the required extent on a director. Divide also the layers of cervical fascia *without* a director, and gently hold aside the external jugular vein, or, having placed two ligatures upon it, divide the vein between them. Remove or hold aside lymphatic glands. Tie also any small artery which interferes with the operation, and avoid touching the veins lest they bleed. Towards the inner angle of the wound feel with the point of the index finger for the round scalenus anticus muscle, and trace it down to its attachment to the tubercle on the first rib. Upon the rib external to the tubercle, the artery will be found, sometimes with a small vein running upon it.\* Open the sheath, and pass the needle from before backwards, taking care not to include a nerve of the brachial plexus, or even to pass a ligature around a nerve only.

I have repeatedly seen the ligature passed around the seventh cervical nerve.

\* In a stout patient submitted to ligature of this vessel by the author, this small vein was seen at the bottom of a very deep wound, and enabled the operator to find the artery at once, and while the patient was faint.

If the above incision be insufficient, a second vertical cut may be made, falling at right angles either to the centre or to the inner extremity of the first.

SECOND PART.—This artery may be ligatured in the middle of its course by dividing some of the fibres of the scalenus anticus muscle, behind which it lies, as well as the clavicular portion of sterno-mastoid muscle, and the parts already mentioned in tying the third part.

In this position, however, the artery lies over the pleura, and the phrenic nerve would be endangered.

The *point of selection* for ligature of the subclavian artery is the outer third, because in this position the vessel is tolerably high in the neck, comparatively superficial, out of relation with the pleura, and usually gives off no large branch.

For the sake of practice, the student may exercise the application of the ligature upon the vertebral, inferior-thyroid, and internal mammary arteries, branches of the first part of the subclavian artery.

*Vertebral Artery.*—This vessel may be exposed by dissection similar to that described for ligature of the first part of the subclavian artery. The finger introduced into the wound will detect the prominent anterior tubercle of the transverse process of the sixth cervical vertebra, and immediately below this the artery will usually be found ascending, to enter the foramen in the transverse process. The vertebral artery is placed between the longus colli muscle on

the inside and the scalenus anticus muscle on the outside, is surrounded by branches of sympathetic nerve, and its accompanying vein is superficial to it.

*Inferior-Thyroid Artery.*—This vessel passes upwards and inwards in a tortuous manner behind the sheath of the carotid artery, and may be ligatured while it lies between that vessel and the lateral lobe of the thyroid body. An incision about three inches in length should be made along the inner border of the sterno-mastoid muscle, the centre of the incision corresponding to the first rings of the trachea.

The thyroid body and the carotid sheath being held apart, the vessel will be found lying upon the longus colli muscle. The inferior-thyroid veins do not accompany the inferior-thyroid artery, but pass down in front of the trachea to join the innominate vein, while the middle thyroid veins will be seen crossing the line of the incision from within outwards, to open into the internal jugular vein, but quite superficial to the inferior-thyroid artery.

*Internal Mammary Artery.*—This vessel may be ligatured with tolerable facility where it lies behind the costal cartilages, between the internal intercostal muscle and the pleura.

Make an incision one inch in length parallel to and half an inch external to the border of the sternum, dividing the integument, pectoralis major muscle, aponeurotic expansion between the cartilages of the ribs supplying the place of external intercostal muscle, and internal intercostal muscle; the vessel

will be found with its *venæ comites*, and must be ligatured carefully lest the pleural sac be opened.

*Axillary Artery. Anatomical relations.*—This vessel, the continuation of the subclavian artery, extends from the lower border of the first rib to the lower border of the tendons of the *latissimus dorsi* and *teres major* muscles. It may be ligatured at any point with more or less difficulty, but opposite the lower border of the *pectoralis major* muscle with comparative ease. In the upper two-thirds of its course, this artery is covered in by one or both pectoral muscles.

In the upper third, it will be found between the clavicle and upper margin of the *pectoralis minor* muscle, having the brachial plexus above and external to it, the axillary vein below and internal to it, and, when distended with blood, slightly overlapping the artery.

#### OPERATION.

Various incisions have been proposed to lay bare the artery while it is behind the pectoral muscles, and of these one parallel to the clavicle is as convenient as any.

Make an incision at least three inches in length, just below and parallel to the middle of the clavicle, dividing the integuments, fibres of the *pectoralis major* muscle, a layer of fascia between the upper border of the *pectoralis minor* muscle and the clavicle, on a director; and carefully avoiding the trunk



of the thoracica-acromialis artery coming forward over the upper margin of the pectoralis minor muscle, and the cephalic vein crossing the axillary artery from without inwards to join the axillary vein, open the sheath of the vessels prolonged from the costo-coracoid membrane, and pass the aneurism needle from within, outwards and upwards, avoiding the vein on the inside and the nerves on the outside. Fig. 33



FIG. 33.

shows the artery (*a*) with the ligature *in situ*, the vein (*b*) below and internal to the artery, and the brachial plexus (*c*), which, in a surgical point of view, may be considered as one cord in this position, external to and above the vessel. Tie all vessels which bleed and impede the progress of the operation.



*Another mode* consists in making an incision from the clavicle downwards, corresponding to the interval between the pectoralis major and deltoid muscles. These muscles separated, the pectoralis minor passing upwards and outwards will come into view, and may be divided on a director introduced above it. The sheath opened, the artery will be found surrounded by the nerves of the brachial plexus, the two heads of the median becoming blended in front of it, while the vein lies to the inner side of the artery. In consequence of the proximity of the nerves to the artery, the vessel cannot be readily ligatured in this position. Prior to making the first incision, the course of the cephalic vein lying in the groove between the pectoralis major and deltoid muscles should be determined by making pressure near the clavicle, so as to obstruct the flow of blood through it.

*Ligature of the Lower Third.*—Below the pectoralis minor muscle the axillary artery may be readily exposed, while lying posteriorly on the tendons of the latissimus dorsi and teres major muscles, and externally on the coraco-brachialis muscle. It is covered in by skin, superficial and deep fasciæ; the median nerve is external to it, the internal cutaneous nerve is in front of it, and the axillary vein is internal to it.

To expose the axillary artery in its lower third, remove the arm from the side, and place it at nearly a right angle to the body. Feel for the round bundle of the coraco-brachialis muscle lying along the inner

side of the arm, and immediately behind the anterior fold of the axilla. Now divide the space between the anterior and posterior folds of the axilla into thirds; the point of junction between the anterior and middle thirds will mark the position of the artery.

Make an incision two and a half inches in length, parallel to the course of the artery, and at a distance from the anterior fold, as described above, dividing the integument only; complete the remaining necessary incisions on a director, lest the vein be wounded; and the sheath being opened, pass the aneurism needle from within outward. Fig. 34 shows the position of the patient's arm and the required incision, also the




FIG. 34.

axillary vein (*a*), the arm-pit (*b*), the median nerve (*e*), the ulnar nerve (*d*) held aside, the internal

cutaneous nerve (*c*), the axillary artery with the ligature in position (*f*), the coraco-brachialis muscle (*g*).

The *point of selection* for ligature of the axillary artery will be its lower third, because it is here comparatively superficial.

*Brachial Artery. Anatomical relations.* — This vessel extends from the termination of the axillary artery along the inner side of the upper half of the arm, but passing in front towards the lower part of the arm, to end in the middle of the bend of the elbow opposite to the neck of the radius. Throughout its extent it is covered in by skin, superficial fascia, and deep fascia, and in the middle of the arm is overlapped by the belly of the biceps muscle. The artery is attended by *venæ comites*, into one of which the basilic vein, running up to this point superficial to the artery, usually empties itself about the middle of the arm. The median nerve has different relations to the artery in various parts of the arm. Above, it is external to; in the middle, crosses in front or behind; below, it is internal to the vessel. The coraco-brachialis and biceps form a projection along the outer side of the whole course of the artery; and a groove or depression behind and internal to these muscles, readily seen and felt on the surface, also marks the position of this vessel. The round cord of the median nerve can usually be felt through the skin, and will serve as a guide to the artery.

## OPERATION.

*Ligature in the middle of the arm.*—From what has been said above, the student will have determined the position of the artery; and since this vessel is superficial throughout, it may be ligatured with comparative ease at any point of its course. An incision from two to three inches in length should be made, for example, in the middle of the arm, dividing only, and with care, the skin, lest the basilic vein be wounded; the superficial fascia and deep fascia should be divided upon a director just on the inner side of the median nerve, which latter can be readily felt by the finger lying usually in front of the artery, but occasionally behind it. Flex now the forearm, separate the edges of the wound, and draw the biceps muscle and median nerve aside; the artery will be found in its sheath, with a vena comes on either side of it. The operator must take care not to make his incision too far back, lest he fall upon the ulnar nerve instead of the median; he would never find the artery behind the ulnar nerve. When in doubt, observe the direction of the muscular fibres already exposed, and follow the course of the nerve for a short distance to ascertain the direction it is taking; the ulnar nerve, after reaching the middle of the arm, will be found passing downwards and backwards, and should not then be mistaken for the median. I have repeatedly seen the ulnar nerve mistaken for the median, by students performing operations under my superintendence in Paris.



Fig. 35 represents the operation in the middle of the arm. The edges of the wound are held apart, exposing the artery (*c*), the biceps muscle (*d*), venæ comites (*a*), the median nerve (*b*); the white cord of the ulnar nerve is also seen along the floor of the wound.

*Ligature at the bend of the elbow.*—The brachial artery may also be readily reached at the bend of the elbow, where it lies on the front of the arm, beneath the aponeurotic expansion from the biceps tendon.





FIG. 35.

An oblique incision, two and a half inches in length (Fig. 36), should be made over the artery, on the inner side of the tendon of the biceps, which will serve as a guide to the vessel. The large veins of the region should not be unnecessarily divided. The tendinous aponeurosis (*f*) having been slit up, the artery (*a*) will be found attended by venæ comites

and lying between the tendon of the biceps muscle (*c*) on the outside, and the median nerve (*b*) on the inside. Prior to the operation the student should



*a b c J*

FIG. 36.

manipulate the limb, so as to ascertain the exact position of the biceps tendon, and have the forearm extended during the performance of the operation.

*Radial Artery. Anatomical relations.*—This vessel, the smaller of the two terminal branches of the brachial artery, extends from the middle of the bend of the elbow to the root of the thumb, when it turns backwards to the hand. It is comparatively superficial in its whole extent, especially in the lower half of the forearm. The artery is bounded on its outer side throughout by the belly and tendon of the supinator longus muscle; on the inner side it is bounded in its upper third by the pronator teres muscle; in its lower two-thirds, by the flexor carpi radialis tendon. In a muscular subject the belly



of the supinator longus muscle overlaps the upper portion of the radial artery.

#### OPERATION.

The radial artery may be ligatured at any point in the forearm, as, for example, in the upper and lower thirds.

*Ligature in the Upper Third.*—In this position, before commencing the operation, the position of superficial veins should be noticed, and by manipulation a groove may be traced downwards by the finger, marking the spot at which the bellies of the supinator longus and pronator radii teres muscles are




FIG. 37.

in apposition. Along this groove, over and parallel to the course of the artery, an incision (Fig. 37) two inches in length should be made, dividing the skin and superficial fascia; the deep fascia should be slit up on a director, and after flexing the arm slightly, so as to relax the neighbouring muscles, and drawing

aside the supinator longus muscle (*a*), the sheath containing the radial artery (*b*) and its venæ comites will be exposed, as also the radial nerve, to the outer side of the vessels. The ligature may be passed from without inwards.

*Ligature at the Lower Third.*—Here the vessel lies external to the tendon of the flexor carpi radialis muscle, which latter can be readily detected through the skin by manipulating the hand. An incision an inch and a half in length (Fig. 38) should divide the integuments, just external to the above tendon. Slit up the deep fascia (*a*) on a director, and having opened the sheath, pass the ligature around the artery (*c*), so as to avoid including either vein (*b*).




FIG. 38.

The radial nerve does not accompany the artery in the lower third of its course. In a thin subject the vessel will be quickly reached.


*Ulnar Artery.*—This vessel, the larger of the two terminal branches of the brachial artery, is covered in by the superficial layer of muscles arising from the inner condyle. It extends from the centre of

the bend of the elbow in a curved direction, the convexity looking inwards, to the outer side of the pisiform bone. The artery is thus deeply placed, and can only be ligatured with comparative ease in its lower third, in which position even it is not so superficial as the radial artery. The vessel may also be exposed at the junction of the middle with the upper third of the forearm.

#### OPERATION.


*Ligature in the Upper Third.*—A line drawn from the apex of the internal condyle, downwards and forwards, to the outer side of the pisiform bone, will indicate the anterior and outer margin of the flexor carpi ulnaris muscle. The forearm being extended, an incision begun three fingers' breadth below the point of the inner condyle must be carried downwards in the direction indicated along the inner side of the forearm, dividing the integuments to the extent of three inches. Separate the edges of the wound, and look for a white pearly line, also running towards the hand, and indicating the septum between the flexor carpi ulnaris muscle on the inside and the flexor sublimis muscle on the outside; divide this aponeurotic line to the same extent as the integuments, taking especial care to get *between* the two muscles above indicated, and not into the substance of either. Flex now the hand and the forearm, and separate the superficial set of muscles behind which the artery lies, from the flexor profundus digitorum

upon which the vessel lies, with the forefingers. The ulnar nerve will be first seen, and soon, external to it but on the same plane with it, the ulnar artery with its venæ comites will be reached. Fig. 39 shows the operation above described, and the parts interested;



the flexor sublimis muscle (*a*) pulled aside, the ulnar nerve (*b*) resting on the flexor profundus muscle (*c*), the ulnar artery (*e*), with its venæ comites (*d*).

*Ligature in the Lower Third.*—Here the artery lies between the tendons of the flexor carpi ulnaris muscle on the inside, and slightly overlapped by it, and the



flexor sublimis on the outside. The hand being supine, make an incision (Fig. 40) two inches in



length over the tendon of the flexor carpi ulnaris muscle, dividing the integuments (*c*), and the deep fascia (*e*) on a director; flex the hand, and draw inwards the tendon of the flexor carpi ulnaris muscle (*a*), which overlaps the artery (*d*), and having opened the sheath pass the ligature from within outwards, so as to avoid both ulnar nerve and vena comes (*b*).

*Abdominal Aorta.*—This vessel, lying somewhat to the left of the median line, occupies the extent of the four upper lumbar vertebræ; it is covered in by peritoneum, and on its right side lies the inferior vena cava. It may be ligatured between the origin of the inferior mesenteric artery and its bifurcation, by a vertical incision three or four inches in length, the middle of which should correspond to the umbilicus, but not include it, dividing the integuments, linea alba, and then on a director, the layer of peritoneum immediately behind this; separate now the edges of the wound, and while the small intestines are pushed over to the right side, scratch through the peritoneum covering the aorta with a director, and carefully avoiding injury to the vena cava, pass the aneurism needle from right to left behind the artery.

*Another and preferable mode.*—Make an incision on the left side of the body from the tip of the last rib to the crest of the ilium, prolonging the same forwards along the crest, if necessary, and dividing integuments, muscles, and transversalis fascia only; with the fingers separate carefully the peri-

toneum from the parts behind it, until the aorta be reached, when the ligature must be passed as above directed.

Previous to the performance of operations, which might be rendered difficult by the presence of loaded bowels, a dose of castor-oil, followed by an enema of warm water, should be administered. In order also to relax the abdominal muscles concerned in the operation, the thighs may be flexed upon the abdomen, and the head and shoulders also raised and bent forwards.

*Common Iliac Arteries. Anatomical relations.*—These vessels extend outwards, from the bifurcation of the abdominal aorta opposite to the lower margin of the fourth lumbar vertebra, to the intervertebral substance between the last lumbar vertebra and the sacrum, at which point they divide into internal and external iliac arteries. Both vessels are covered by peritoneum, and crossed by the ureter at the bifurcation. The relation of veins on either side differs: on the right side, the common iliac vein lies behind and external to its artery; on the left side, the common iliac vein is at first behind and internal to its artery, and afterwards behind the right common iliac artery.

*External Iliac Artery. Anatomical relations.*—This vessel extends downwards and outwards from the bifurcation of the common iliac artery, lying along the inner border of the psoas muscle, to the centre of Poupart's ligament; internal to and behind it is the



external iliac vein; running upon it sometimes is a branch of the genito-crural nerve; near its termination, or about half an inch above Poupart's ligament, two large branches arise, deep epigastric and deep circumflex ilii arteries; the vein accompanying the latter artery crosses the external iliac artery from without inwards to join the external iliac vein. The artery is covered by peritoneum, and some lymphatic glands are adjacent to it.

*Internal Iliac Artery. Anatomical relations.*—This vessel extends downwards from its bifurcation to the margin of the sacro-sciatic foramen. It lies on the pyriformis muscle, and lumbo-sacral cord; its companion vein is behind it; in front, the ureter crosses the vessel; the obturator nerve passes to its destination external to the artery, and the peritoneum covers it.

#### OPERATION.

*Ligature of the External Iliac Artery.*—This vessel is best reached by an incision, begun about half an inch above Poupart's ligament, at the junction of the inner and middle third of the space between the symphysis pubis and the antero-superior spine of the ilium, and carried outwards to the extent of three inches towards the antero-superior spine of the ilium, parallel to Poupart's ligament. Divide thus the integuments, the aponeurosis of the external oblique muscle (Fig. 41) (*c*), raise or divide the fibres of the internal oblique and transversalis muscles (*a*)

on a director; let an assistant hold aside the cord, and slit up the transversalis fascia also on a director: with the fingers carefully push up the peritoneum (*d*), and seek the artery above the origin of the deep epigastric and deep circumflex ilii arteries; a branch of the genito-crural nerve will be occasionally seen




FIG. 41.

upon the vessel. The aneurism needle should be passed from within outwards, avoiding the external iliac vein, the deep circumflex ilii vein and the genito-crural nerve. Fig. 41 shows the external iliac artery (*b*) exposed, the origin of the deep epigastric artery, and the genito-crural nerve, in this

instance, outside the main artery, and the external iliac vein, internal to its companion vessel.

#### OPERATION.

##### *Ligature of the Internal and Common Iliac Arteries.*

—These vessels may be exposed by a proceeding very similar to the preceding, the incision being begun about the middle of Poupart's ligament, and carried upwards and outwards, with the convexity looking downwards and outwards, to the extent of about five inches. Similar strata will be divided, and all vessels which bleed should be immediately tied.\*

*Femoral Artery. Anatomical relations.*—This vessel (Fig. 42) extends through the upper two-thirds of the thigh, from the centre of Poupart's ligament to the opening in the adductor magnus muscle, through which it passes to become popliteal. On the surface, the thigh being abducted and rotated outwards, a line drawn from the centre of Poupart's ligament downwards and inwards, along the front and inner side of the thigh to the centre of the popliteal space, will indicate the course of the artery. In the upper third of the thigh the artery (*b*) traverses Scarpa's triangle, from the centre of its base to its apex, and is covered in by skin, superficial fascia which at the

\* In a case of inguinal aneurism of the right side, for which the author tied the right common iliac artery, the incision extended from the tip of the last rib downwards and forwards to a point within and below the level of the antero-superior spine of the ilium. Through this the hand passed readily to the artery.

upper and inner part consists of at least two layers;




FIG. 42.

with superficial vessels and lymphatic glands intervening, and fascia lata; one or two branches of the anterior crural nerve cross the artery from without inwards. On the outside, at the distance of about half an inch, lies the trunk of the anterior crural nerve (*a*), two large branches of which gradually approach the artery. On the inside, and not closely applied to the artery at first, is the femoral vein (*c*), which lower down is found posterior to the artery, and only separated from it by a very thin cellular septum. Behind the

artery are certain muscles and portions of the pro-



funda artery, profunda vein, and of the femoral vein. The profunda artery usually arises at the distance of about one inch and a half below Poupart's ligament, from the posterior and outer side of the femoral artery, and pursues a course outwards, downwards, inwards, and then again downwards, parallel to but deeper than the femoral artery, thus forming a curve external to the femoral artery, and leaving a space between the two vessels, through which a knife might pass without wounding either of them. The fact is worthy of recollection in reference to wounds of the arteries of the thigh. It should also be borne in mind that a stab in a certain part of the thigh might transfix both femoral and profunda arteries.

#### OPERATION.

The femoral artery can be ligatured in any part of its course, but with comparative ease in Scarpa's triangle. In a case of popliteal aneurism requiring ligature of the main vessel, the *point of selection* for ligature is the apex of Scarpa's triangle, corresponding to the convergence of the adductor longus muscle from the inside and the sartorius muscle (*d*) from the outside. This situation is preferred, because the artery is comparatively superficial, at a moderate distance from a large branch (profunda), through which, if nearer, the current of blood flowing might prevent union of the divided coats and the formation and organization of a firm clot to plug the vessel; the profunda artery being also above the ligature,



the nutrition of the limb is not interfered with in a dangerous degree.

*Ligature at the apex of Scarpa's triangle.* — The patient being recumbent, with the leg partially flexed upon the thigh, and the thigh slightly abducted and rotated outwards, the position of the internal saphena vein should be ascertained by making pressure upon it near its junction with the femoral vein, so as to check the flow of blood through and cause it to swell; the position also of the sartorius muscle, especially the inner margin of the upper portion, which borders the artery and crosses the thigh from above inwards and downwards, should be ascertained by causing the subject, if living, to bring the muscle into action. The part having been shaved, if necessary, and the course of the artery known by its pulsation, if the subject be alive, and by the surface line indicated above, an incision commenced at a distance of four fingers' breadth below Poupart's ligament should divide the integuments only, parallel to the artery to the extent of three inches, leaving the saphena vein on its inner side; any lymphatic glands intervening should be held aside or removed, while the deep fascia is divided on a director. Seek now the inner margin of the sartorius muscle, the fibres of which run downwards and inwards, and along this border, or just under cover of it, the artery will be seated. The sheath of the vessel having been opened as directed, the aneurism needle must be passed with the utmost care around the artery from within out-

wards, the point of the needle being kept closely applied to the artery, lest the vein, which in this locality is particularly near the artery and generally behind it, should be wounded. (I have repeatedly seen the vein wounded, and a segment of it included with the artery, where ligature of the femoral artery has been practised, by gentlemen attending my "course of operations" in Paris.) Fig. 43 shows




FIG. 43.

the incision and parts interested in the above operation. The integuments are divided, as also the deep

fascia (*a*); the sartorius muscle (*b*) is pulled to the outer side, exposing the artery (*d*) and the vein (*c*).

*Ligature at the base of Scarpa's triangle.* — In this position the artery is superficially placed, being covered in by skin, superficial fascia, lymphatic glands, cribriform fascia or deep fascia, having the trunk of the anterior crural nerve on the outer side, about half an inch from it, the femoral vein on its inner side occupying the central partition of the crural sheath, but separated from the artery by a distinct and moderately firm cellular septum.




FIG. 44.

Make an incision in the direction of the artery already indicated, commencing at Poupart's ligament and terminating two inches below it, dividing

the skin, and then the layers of fascia on a director, till the sheath be reached ; open the sheath, and pass the aneurism needle from within outwards. The vessel will thus be ligatured midway between the origins of the deep epigastric and deep circumflex ilii arteries, branches of the external iliac artery above, and the profunda artery, the largest branch of the femoral artery below. Fig. 44 shows the parts exposed by the above incision ; *a* is the deep fascia, *b* marks the artery, and *c* is the femoral vein, internal to the artery, and separated from it by a distinct septum, a portion of which is seen in the figure. Any superficial artery which bleeds during the operation should be immediately ligatured or twisted.

*Ligature in the middle third of the Thigh.*—In this position the femoral artery is more deeply seated, and in the case of popliteal aneurism would be nearer the disease ; also the vessel lies in an aponeurotic canal, along which pus might readily and injuriously burrow. This site should never be selected from preference.

The limb being in the position of partial flexion and rotation outwards, make an incision three inches in length over the line of the artery, dividing the integuments and deep fascia, but carefully avoiding the internal saphena vein ; the fibres of the sartorius muscle will now be exposed, and may be recognised by their downward course. Separate the edges of the wound, and seek the anterior and outer margin of



the last-named muscle, and turn it inwards, so as to expose the anterior and inner wall of Hunter's canal, formed by a fibrous aponeurosis, extending from the tendons of the adductors longus and magnus downwards and inwards, to join the tendinous origin of the vastus internus muscle. This aponeurosis covers in the artery, also the femoral vein lying somewhat to the outer side and behind the artery, and the long saphena nerve lying in front and external to the artery. If the subject be thin, the long white cord of the saphena nerve may be readily seen through the aponeurosis, and will serve as a guide to the position of the artery.

Caution.—The operator must be careful not to mistake the tendinous origin of the vastus internus muscle for the aponeurotic expansion above mentioned, nor the nerve or any branch of the nerve which supplies the vastus internus muscle, for the long saphena; both these sources of fallacy are external to the position of the artery. It may be remembered that the fibres of the vastus internus muscle run from above, downwards and outwards, while those of the sartorius in this position are nearly vertical.

Hunter's canal being now exposed, should be opened on a director to a similar extent as the superficial structures, so as to favour the exit of pus, if any form, and to prevent burrowing of matter. The aneurism needle should be passed from without to within, so as to avoid including either the nerve or vein in the ligature.



*Popliteal Artery.*—This vessel traverses the centre of the popliteal space vertically. In front of it are the femur, with more or less fat intervening, the posterior ligament of the knee-joint, and the popliteus muscle; behind the vessel and external to it are the popliteal vein, which in this region is joined by the short saphena vein from below, and the internal popliteal nerve, superficial to and also external to the vein; laterally the artery is bounded by the various muscles, inclosing the space. The deep fascia, a prolongation of the fascia lata, strengthened by additional transverse fibrous bands, binds together all the above organs, as well as some lymphatic glands which lie about the artery. In the lower half of this space branches of these popliteal vessels and internal popliteal nerve form a network about the artery, and therefore induce the surgeon to select the upper part of the vessel as the seat of ligature.

#### OPERATION.

The subject being prone and the leg extended, make a vertical incision from three to four inches in length along the centre of the popliteal space, two-thirds of the incision being above and one-third below the line of the articulation between the femur and tibia. Divide the integuments cautiously, so as not to wound the external saphena vein, slit up the deep fascia on a director, and then seek the internal popliteal nerve, the most superficial of the

three organs above mentioned ; flex the leg partially upon the thigh, so as to relax the parts, and let an assistant hold aside the above nerve ; now seek the vein, which is still deeper than and internal to the nerve, and having found this vessel, seek the artery still deeper than and internal to the vein, and pass the aneurism needle from without to within. The various organs occupying this space are so bound together by the deep fascia, and the space thereby rendered so deep, that the artery cannot be readily reached unless a free incision be made.

*Posterior Tibial Artery.*—This vessel extends along the centre of the back of the leg between the two layers of muscles occupying that region, from the termination of the popliteal artery to a mid-point between the internal malleolus and the insertion of the tendo-achillis.

The artery is attended by venæ comites, and by the posterior tibial nerve, which in the upper fourth is internal to the artery, but in the lower three-fourths is external to that vessel.

#### OPERATION.

This vessel may be ligatured at any point of its course, and with comparative ease in the lower third of the leg, where it is not covered by muscle.

*Ligature at the middle third of the Leg.*—The surgeon should first ascertain the position of the internal saphena vein ascending along the inner side

of the leg, and, having done so, make an incision (Fig. 45) three or four inches in length, parallel to the inner margin of the tibia and a finger's breadth behind it, dividing the integument and deep fascia. He will now probably see the free margin of the gastrocnemius muscle lying upon the soleus, which former should be held aside while the fibres of the soleus muscle (*a*) are cautiously divided to a similar extent as the integument, until a whitish fibrous membrane be reached. (I beg to draw especial attention to this "whitish fibrous membrane," because it is




FIG. 45.

the tendinous origin of the soleus muscle from the tibia, and not, as I have known students suppose, the aponeurosis separating the superficial from the deeper layer of muscles.) Slit up this tibial origin of the soleus on a director and seek for the pearly-looking intermuscular septum, the transverse fibres of which are sometimes distinctly seen, separating the two layers of muscles and binding the artery upon the tibialis posticus muscle (or rather upon the posterior tibial aponeurosis). Divide this inter-

muscular septum on a director also, and seek the artery (*c*), external to the outer border of the tibia attended by venæ comites (*b*) and the posterior tibial nerve, the latter to its outer side. Pass the aneurism needle from without inwards.

Caution.—Some authorities advise that the soleus muscle should be detached close to the tibia; but it should be remembered that the flexor longus digitorum muscle also arises from the tibia, just external to the linear origin of the soleus, and would almost surely be detached with the soleus; and if so, the operator would get into the substance of the flexor muscle and anterior to the artery instead of being behind it, as is desired. Any muscular branch of artery which bleeds should be immediately ligatured or twisted.

*Another method* consists in making a vertical incision along the middle of the back of the leg through the superficial muscles. This is not so convenient as the former, because the artery is further from the surface, and more injury is inflicted on the various organs interested.

*Ligature at the lower third of the Leg.*—In this position the vessel lies about midway between the tendo-achillis and the inner border of the tibia, is attended by venæ comites and by the posterior tibial nerve lying to its outer side; internal to the artery are the tendons of the tibialis posticus and flexor longus digitorum muscles.

The vessel may be readily reached in this locality

by an incision (Fig. 46) two inches in length parallel to the inner edge of the tibia, and a finger's breadth posterior to it. By this method the artery will be ligatured about one inch above the inner malleolus, and the parts to be divided are, the in-




FIG. 46.

teguments and the deep fascia (*a*) on a director. Some fat will now be seen, and in it the sheath with the artery (*d*) and venæ comites (*c*). The posterior tibial nerve (*b*) is external to the artery. When performing this operation, the surgeon should be careful not to open the sheath of the tendons lying on the posterior surface of the tibia. Also, both in this and the former operation, the limb is resting on its outer surface; and the incision in both cases, although parallel to the artery, is not immediately



over it, but rather on a plane posterior to the vessel. The artery in both instances must therefore be looked for anterior to the direction given to the scalpel in effecting the integumental incision.

*Anterior Tibial Artery.*—On the surface, a line drawn from the inner side of the head of the fibula to a mid-point in front between the internal and external malleoli, will mark the course of the artery. In the upper three-fourths of the leg the artery rests upon the inter-osseous membrane; in the lower fourth, upon the tibia. It is more superficial below than above, in consequence of the diminution of the size of the tibia and muscles. On the outer side the vessel is bounded in the upper third by the extensor longus digitorum muscle, in the middle third by the extensor proprius pollicis, in the lower third by the extensor longus digitorum.

On the inner side the artery is bounded throughout by the tibialis anticus muscle, the outer border of which marks the course of the artery, and can be felt with tolerable facility when the muscle is in action. In front, in the upper two-thirds, the artery is concealed by the apposition of muscles above mentioned, deep fascia, and integument; in the lower third, besides integument and deep fascia, the vessel is crossed from without inwards by the extensor proprius pollicis muscle. Venæ comites accompany the artery, also the anterior tibial nerve, with uncertain position.

## OPERATION.

This vessel may be ligatured at any point, but with more ease towards the lower than upper extremity of the leg. In the upper third the vessel is very deeply seated; and as the muscles arise partly from the deep fascia covering them, the muscular space between the tibialis anticus on the inside and the extensor longus digitorum on the outside, cannot be readily found, although sometimes a whitish line will mark the position of the intermuscular septum.

*Ligature in the middle third of the Leg.*—Make an incision (Fig. 47) three inches or more in length, over and parallel to the course of the artery, dividing the integument only. Seek now a white line in the deep fascia, marking the septum between the tibialis anticus on the inside and the extensor longus digitorum on the outside.

Divide this white line of deep fascia longitudinally, and nick it transversely also at one or two points, if it prevent ready separation of the edges of the wound.

Flex the foot upon the leg so as to relax muscles, and (*caution*) not forgetting that in the middle third of the leg the extensor proprius pollicis muscle lies to the outer side of the artery, and concealed from view by the apposition of the tibialis anticus and extensor longus digitorum, separate the edges of the wound by drawing the tibialis anticus muscle (*b*) to the inside, and the extensor proprius and extensor longus digi-

torum (*a*) to the outside. The nerve will probably be seen first, somewhat anterior to the artery (*d*), the latter being attended by venæ comites (*c*). Pass the ligature according to rule.

The anterior and posterior tibial arteries may be readily compressed just above the ankle joint against the tibia during the performance of operations on the foot.




FIG. 47.

*The Dorsalis Pedis Artery.*—On the surface, a line drawn from a mid-point between the malleoli to the base of the first metatarsal space, will mark the course of the artery. The tendon of the extensor proprius pollicis muscle lies to the inner side of the artery, and can be readily felt by manipulating the great toe, or bringing the muscle into action.

The tendons of the extensor communis digitorum muscle are external to the artery, and the innermost tendon of the extensor brevis digitorum crosses the vessel from without inwards, just before the latter dips into the sole of the foot.

## OPERATION.

Commence an incision about one finger's breadth below the ankle joint, and carry it along the dorsum of the foot to the extent of one-and-a-half or two inches. Let the incision (Fig. 48) be external to and parallel to the tendon of the extensor proprius pollicis muscle (*c*). Divide the integument carefully, then the deep fascia on a director, when the artery (*d*) will probably be seen attended by venæ comites (*b*), and crossed obliquely by the inner tendon of the extensor brevis digitorum muscle (*a*): the nerve is usually outside the artery.




FIG. 48.

After ligature of an artery the patient should be instructed to abstain from all muscular exertion, while the part below the ligature is kept warm with either cotton wool or a flannel bandage or both.

## CHAPTER VI.

### OPERATIONS ON THE BONES.

#### EXCISION OF JOINTS, BONES, AND PORTIONS OF BONES.

EXCISION has for its object the removal of the articular ends of bones, a portion of the shaft, or the whole of certain comparatively unimportant bones, with a view to the preservation of the rest of the limb or adjacent structures to the use of the patient.

It has certain advantages over amputation, inasmuch as it implies the removal of a smaller portion of the frame, and, if successful, leaves the patient with a mutilated but more or less useful limb.

*Excision of the Upper Jaw.*—The face is to be disfigured as little as possible, and sound structures, both soft and hard, are to be carefully husbanded. By a free separation of the lips and cheek, and without section of either, portions of both jaws may be removed.

A large portion of the upper jaw may be taken away after it has been exposed by a division of the upper lip into the nostril of the condemned side, aided by a separation of the ala of the nose from its



bony attachment, and free dissection of the cheek from off the superior maxillary bone. The operation finished, the only external wound will be that of the upper lip, and this must be closed by suture.

The floor of the orbit is to be preserved, if not diseased, when the rest of the bone is removed, by a transverse section of the jaw below the margin of the orbital cavity. So also, if sound, are the alveolus and roof of the mouth to be retained, and separated from the body of the bone by an appropriate use of the saw or forceps.

The sutures which materially retain the upper jaw in position after division of the soft parts, and so prevent easy removal of it, are, one, between the ascending process and the nasal and frontal bones, a second, between the malar process and malar bone, and a third, the mesial articulation with the corresponding bone on the other side.

*One method.*—The patient being seated in a chair, at a convenient height, his face turned towards the operator, and having his head supported by an assistant behind, the surgeon should stand somewhat in front, but on the side of the patient opposite to that on which he is about to operate. The operator proposes to divide the cheek from the angle of the mouth of the affected side to a point opposite to the centre of the malar bone of the same side, and effects his object either by puncturing the cheek from within the mouth (the former being made tense by the left forefinger and thumb of the operator, pulling

upon the cheek on one side of the angle of the mouth, while an assistant pulls gently on the other side of the angle) opposite to the malar bone, and carrying it downwards, so as to divide the commissure of the lips; or, if the cheek be stretched over a tumour, the former may be divided from below upwards and outwards. The cheek must now be dissected upwards to the margin of the orbit, and the nasal cartilage of the affected side be separated from its attachment to the superior maxillary bone; branches of the superior maxillary nerve will of course have been cut across, as they emerge upon the cheek. Protecting the eye, divide with bone forceps the nasal process of the superior maxillary bone, opposite to the upper opening of the nasal duct. Take now one end of a "chain saw" (Fig. 49),



FIG. 49.

temporarily detached from its handle, and by means of a thread attached to it arm an aneurism needle with the saw, and pass the needle thus armed, from above through the speno-maxillary fissure, bringing it out below the malar bone in front of the origin of the masseter muscle. The thread should be now seized and held, while the needle is withdrawn as it came. The saw being now adjusted and the eye protected, the malar bone will be readily divided by a few strokes of the former. Extract one or two

incisor teeth from the condemned jaw, separate the velum palati by a transverse incision, from opposite its attachment to the posterior nasal spine outwards to a point just behind the last molar tooth; also incise the soft palate along the line of the median articulation between the palate processes of the palate and superior maxillary bones. Again arm an aneurism needle with the chain saw, and pass it back along the floor of the nostril of the diseased side, making it reappear in the opening caused by the transverse incision in the velum palati. With a forceps seize the thread and bring it and one end of the saw out at the mouth, at the same time removing the aneurism needle by the nostril. Re-adjust the handle of the saw, and make it cut its way forward through the hard palate. The chief osseous connections of the superior maxillary bone are now severed, and having introduced an elevator between the maxillary bones in front, slight force applied by means of the elevator used as a lever, while the sound maxillary bone serves as a fulcrum, will break down the still existing unimportant bony adhesions. A small straight saw or cutting bone forceps may be substituted for the chain saw.

With a pair of "lion" forceps holding the alveolar process, pull upon the loosened bone in a direction downwards and outwards, twisting it as it yields, so as to break down slight adhesions and to tear small vessels, using the knife sparingly, but to divide perhaps the superior maxillary nerve. Any

vessel bleeding should be ligatured if it can be reached, otherwise be touched with the actual cautery.

Bleeding having ceased, the wound is to be carefully closed and sutured with the ends of ligatures projecting into the cavity of the mouth rather than lying on the cheek. After recovery the patient may be handed over to the dentist.

Any vessel bleeding during the operation may be ligatured at once.

On examining the bone thus extracted, it will be found that, besides portions of the palate, malar and other bones, usually a greater or lesser portion of the pterygoid process comes away also.

*Another and better method.*—To effect removal of the upper jaw many surgeons prefer to incise the upper lip in the median line, and then to carry the incision outwards in front of the nostril to the ala of the affected side, continuing it up along the side of the nose to within half an inch of the inner angle of the eye. This incision occupies the site of natural furrows for the most part, and after recovery is not so unsightly as that described above. It will suffice if there be not much distortion of the features, and also if only a portion of the bone requires removal. Under circumstances of great enlargement, both of these incisions may be necessary to facilitate the operation, but it will be readily understood that the form and position of the incision must in some respects depend upon the seat and extent of disease.

With a view both to avoid injury to the facial nerve and artery, and to gain more room, the proposed incision across the cheek may be substituted by prolonging that which has already reached the inner canthus, directly outwards below the eye to the malar bone or zygoma (Fig. 50).



FIG. 50.

The bone forceps, straight and angular, also small saws, straight, semicircular, or with rounded angles, should be at hand in case of need; indeed, some prefer using a small saw and bone forceps to divide the hard palate and other bones, to the chain saw. Portions of the alveolar border of either jaw may be removed by the bone forceps and without incising the cheek.



Prior to removal of the upper jaw for enlargement of a doubtful nature connected with bulging of the antrum, the contents of the cavity may be tested by puncturing the same with a strong trocar, either through the socket of a decayed molar tooth extracted for that purpose, or through the anterior wall of the antrum.

*Another method.*—With the object of diminishing the gravity of the operation and to economize sound structures, Fergusson proposes to cut *into* the disease, rather than *around* it as already described, and then to cut away from the centre to the circumference as it were, until healthy tissues are reached. This plan may be resorted to in the case of tumour of both lower and upper jaws; and possibly the inner wall of the lower jaw may occasionally be preserved. Small saws, cutting forceps of various shapes, the gouge and trephine, will be wanted.

*Excision of the Lower Jaw.*—In operations performed for removal of portions of the lower jaw, as much of the periosteum as is possible should be preserved.

The whole of this bone has been removed by one operation, but such proceeding would be much facilitated by a previous section of the symphysis. Excision of one-half of the lower jaw may be performed as follows:—The patient being seated, and well supported behind, or semi-recumbent, and with his face turned towards the surgeon, who stands somewhat in front, but in either case on the patient's

right, the operator makes a curved incision, the convexity looking downwards and backwards, commencing on the cheek at a point, if possible, not higher than the junction of the lobule of the ear with the face, and carrying it along the margin of the bone a little beyond the symphysis. At either or both ends of this cut he may let fall a short incision at a right angle, the one over the symphysis being short of dividing the free margin of the lip. One or both ends of the facial artery should be ligatured at once. The flap of integument and muscles may now be dissected close off the bone, a tooth extracted, if need be, and a small saw used to cut a groove in the outer surface of this naturally dense bone, if possible, external to the symphysis, so as not to disturb the mesial attachments of the tongue. With the bone forceps complete the section of the bone begun with the saw. Keeping the knife close to the bone, detach muscles and mucous membrane from the inner surface as high as and including the internal pterygoid muscle. Seize now the freed portion of the jaw with the left hand, and press upon it in a downward and backward direction, so as to bring down the coronoid process and tendon of the temporal muscle as much as possible. The position of the apex of this process known, use the knife cautiously, nicking the tendon of the temporal muscle till the attachment to the apex of the coronoid process be severed. Still pulling upon the loosened bone, twist it forcibly outwards, so as to tear the capsular liga-

ment and the fleshy external pterygoid muscle; then incise the external lateral ligament and minor attachments close to the bone till it comes away. Bleeding having ceased, close the wound accurately. The ends of ligatures should be allowed to hang in the mouth or be cut short rather than be brought out through the edges of the wound.

Happily, in many instances, portions only of the lower jaw demand removal—as the symphysis, the part between the symphysis and angle, or between the angle and the articulation.

*Excision of the Symphysis.*—The dimensions of an incision to expose a portion of the jaw must depend in great measure upon the impediment consequent on the size of the body to be removed.

The bone may be laid bare by a vertical incision in the mesian line, dividing the integuments from the margin of the lower lip to the hyoid bone. Two flaps are formed, and turned aside so as to expose the symphysis, and enable the operator, after extracting a tooth on either side, to separate the diseased portion by means of a saw and bone forceps.

To prevent retraction of the tongue, and probable suffocation, a ligature should be passed through the tip of this organ, and be held firmly by an assistant, while the knife separates the fragment of bone from its attachments behind. The operation completed, the wound is to be closed by the twisted suture, and the ligature holding the

tongue should be brought out in front between the edges of the wound, and be fixed to one of the needles forming the suture, and be there maintained until the tongue shall have contracted adhesions. Any falling together of the remaining lateral portions of the lower jaw, and consequent diminution in the area of the floor of the mouth, may be obviated by some dental apparatus, having for its object the maintenance of the teeth in one jaw opposite those in the other, until repair and consolidation have taken place.

In all operations about the face, the red margin of the lips should, if possible, be left intact.

*Excision of portion of Jaw from symphysis to angle.*  
—The operation by lateral flap is effected by two incisions, one horizontal along the base of the jaw from the angle to the symphysis, the other vertical through the lower lip, meeting the end of the first at a right angle. The flap is to be dissected up, exposing the tumour to be removed. An incisor tooth having been extracted, the bone is partially divided near the symphysis with a small saw, and the section completed by the bone forceps; the angle is to be cut across in a similar manner, or by the chain saw introduced between it and the soft parts, as before directed, on an aneurism or other needle. The bone thus partially detached will be liberated altogether by a careful application of the knife to its inner surface. The facial artery, either one or both ends, should be ligatured as soon as divided.

The edges of the wound are to be carefully adapted by suture, due attention being paid to the exact apposition of the edges at the red border of the lip. A notch, which sometimes follows division of the red border of a lip, may be prevented generally by a fine suture introduced at the very margin.

N.B.—The flap methods as above mentioned will rarely be adopted, on account of the extensive scar that must result. A great deal can be accomplished by a linear or curvilinear incision along the base of the jaw, and where a scar would be greatly concealed. It is also quite possible that both operations can be performed within the mouth, and without any external wound whatever.

*Excision of portion of Jaw from angle to articulation.*  
—The patient in this case may be recumbent, as the cavity of the mouth is not to be opened. With the side of the face to be operated upon uppermost, the surgeon divides the soft parts along the posterior margin of the ramus from the zygoma to the angle of the jaw, carrying the incision along the base of the same to a small extent. If the facial artery be divided, it should be ligatured at once. The flap, including the masseter muscle, is to be dissected off, and the bone severed by the saw and forceps at the angle above the attachment of the buccinator muscle. The insertion of the internal pterygoid muscle is to be carefully detached, if possible, by tearing it with the finger from above downwards. The lower end of the ramus thus freed is to be seized and pulled



downwards and backwards, so as to depress the coronoid process. An assistant holding open the upper part of the wound, the operator divides the attachment of the temporal muscle to that process, and forcibly twisting the ramus outwards, tears through the attachments of the fleshy external pterygoid muscle and capsular ligament, and with a few cautious touches of the knife divides the remaining external lateral ligament and other minor attachments, and so completes the separation. Large branches of the facial nerve are severed by the above incision, and paralysis of the muscles by them supplied must be anticipated; also Steno's duct is severed. Bleeding having ceased, the edges of the wound should be most carefully adjusted, with the hope that the divided nerves and duct may reunite.

*Excision without wound of Cheek.*—In all operations on the face and neck it is of second importance to avoid deformity, the surgeon's first duty being to secure the safety of the patient. It is possible to combine both desiderata. Quite recently (March, 1870), the author removed a large piece of the lower jaw, including a myeloid tumour the size of a hen's egg, from a child ten years of age, through the mouth, preserving a good share of the periosteum, without cutting skin at all, and without wound of either facial vessels or nerve.

## OPERATION.

Exploration determined that the portion of bone included between the position of the canine tooth on the right side and the middle of the ascending ramus on the left side should be removed. Chloroform having been administered, the gum and mucous membrane, the periosteum and muscular attachments were separated from all parts of the condemned bone partly by a knife and partly by a raspatory. The integument of the chin was then turned down off the bone, and the right canine tooth having been extracted, the maxilla was cut through by the saw and cutting forceps at this point. The ascending ramus was severed by cutting forceps brought to bear upon it through the mouth. During the latter part of the operation, the tongue was held forwards, and was afterwards fixed to the integument of the chin by a hare-lip pin for a period of three days. The patient made a rapid recovery.

The woodcut (Fig. 51) is from a photograph taken twenty months subsequent to operation. Of course, no scar whatever exists.

*Excision of the Clavicle.*—The large vessels in relation with this bone posteriorly and inferiorly render its removal a matter of danger and difficulty. Such proceeding may be effected by an incision along the bone from one extremity to the other; and, if necessary, this may be added to by one or two short right angular cuts made at the required spot. The

bone having been bared, and its muscular attachments above and in front carefully divided, the "excision director" may be passed under the centre of the bone to protect the soft parts while the bone is sawn in two. Each half of the bone is now to be separately seized near the sawn end by a strong



FIG. 51.

forceps, and forcibly raised, while the operator cautiously divides the inferior muscular attachments as well as the ligaments of the articulation, cutting always upon the bone to be removed. The bone removed, the flaps may be readjusted, and the wound closed. Mr. Couper has removed the whole clavicle by a single incision.

*Excision of the Scapula.*—The whole of this bone has been removed, both primarily and secondarily ;

in the first case, leaving the arm to the use of the patient; in the second instance, after the arm had been previously removed at the shoulder-joint. The incisions requisite must depend altogether upon the condition of the soft parts and the magnitude of the mass demanding removal, and must be determined by the surgeon in each particular case. In a general sense, it will be necessary to make at least two incisions—one from the tip of the acromion process along the axillary border of the scapula to the inferior angle of the same; the second running the whole length of the scapular spine to join the first, either at an angle or some convenient curve. The flaps thus marked out are to be rapidly dissected up, so as to expose the muscular attachments along the base and superior border of the bone. These having been cut, the mass can be lifted off the chest, and then follows section of the serratus magnus and subscapular muscles; muscles taking origin from the coracoid process, coraco-clavicular and articular ligaments. The deltoid, capsular muscles, and remnant of capsule and muscles taking origin from the axillary border of the scapula, together with the subscapular vessels, are to be divided last. The operator must be aided by trustworthy assistants, who will either compress, ligature, or twist vessels as soon as they are divided. The patient will have a useful arm.

*Excision of the head of the Humerus.*—The patient either seated in a chair or semi-recumbent, the

surgeon should stand on the side of the subject corresponding with that of the arm on which he is about to operate, and somewhat in front. With the arm hanging naturally by the side, let the operator ascertain the position of the extremity of the acromion process, the coracoid process, and the portion of clavicle between these two. Slight rotation will prove that a portion of the head of the humerus underlies the space thus inclosed. From this point the tissues are to be divided down to the bone in a direction parallel with the long axis of the humerus as far down the arm as the point of union with the anterior fold of the axilla.

The edges of the wound are to be retracted by assistants, and the long tendon of the biceps muscle looked for; its sheath is to be slit up, as also the capsular ligament, when, if not already destroyed, the long tendon of the biceps should be slipped on one side. The muscular attachments to the tuberosities are now to be divided, if possible by a semi-circular sweep of the knife beginning with the heel of the same. To do this the wound must be well opened by retractors, while the surgeon, holding the shaft of the humerus in his left hand, rotates it first inwards, supposing him to be operating on the right shoulder, in order to divide the attachment of muscles to the greater tuberosity; then gradually rotating outwards, he divides the capsule over the head of the bone and subscapularis muscle attached to the lesser tuberosity. One or two touches of the knife permit



the head of the bone to appear through the wound, when the diseased portion can be readily removed with either a common or bow saw. Should the glenoid cavity be also the seat of disease, its surface may be removed with a gouge or forceps. The upper part of the wound should be closed by suture, and the elbow be raised and fixed to the side.

The efficiency of the limb will greatly depend upon the amount of bone removed; the longer the portion excised, the greater the difficulty of adaptation to the glenoid cavity. Moderately firm adhesions to subjacent structures forming a pivot, or false joint, on which the bone may move on its own axis, but from which it cannot be removed, will also add to the utility of the limb.

*Another method.*—The head of the bone is exposed by making a triangular flap of the deltoid muscle, base uppermost; this turned up, the operation should be completed as described above. In removing the diseased head of the humerus, it is customary to saw transversely. In this way the new surface looks upwards only; but in order that it may look towards the glenoid cavity, in accordance with the original direction of the normal articular surface, I propose to saw off the disease in a direction from below upwards and outwards, thus giving to the new surface a direction upwards and inwards. By this means I presume that the two surfaces could be better adapted. In examining the

amount of disease present, care must be had not to confuse new bony excrescences with caries. After excision a most useful limb will be preserved. In the living subject convalescence will be accelerated if a ready means of escape to expected secretions in the wound be at once provided for by making a dependent opening through the soft parts covering the back of the joint. In the case of a female sixty years of age, operated upon by the author, this was done by the insertion of a drainage tube. In less than a month the operation wound had healed, and the patient was using the extremity.\*

*Excision in the continuity of the Humerus.*—Operations which, if performed upon the lower extremity, would probably prove fatal, may be attempted upon the corresponding bone of the upper limb with every chance of success.

In cases of *ununited* fracture of the humerus, after less formidable means have failed, the surgeon need not hesitate to cut down upon the seat of fracture in some convenient position, say the outer side of the arm, due respect being paid to the course of large vessels and nerves ; and, having divided the fibrous tissues connecting the bony fragments, turn them out separately, and remove their extremity with the saw.

Care should be taken to remove the whole of the uneven surface of each fragment, so as to

\* See Trans. of Clinical Soc. of London. Article 1, vol. i.

leave two clean surfaces of bone in apposition after the completion of the operation. The case must henceforth be treated as one of compound fracture.

*Excision of the Elbow-joint.*—Experience in excision of joints has shown that the operation has been peculiarly successful in the case of the elbow-joint. Not only is the limb saved, but rendered most useful to the patient, who in a very large majority of cases acquires in great measure all those movements of which the healthy joint is capable. The joint being comparatively superficial behind, the posterior surface is selected for the first

incisions by which the bones may be exposed.




FIG. 52.

Previous to the operation the surgeon should ascertain the relative position of the point of the olecranon to the internal and external condyles of the humerus, recollecting also that the ulnar nerve lies in the hollow between the internal condyle and the olecranon, and which nerve in a healthy state of parts can be readily felt and rolled under the point of the thumb. The bra-

chial artery and median nerve are separated from

the joint in front by the brachialis anticus muscle.

The extent of incision necessary to this operation will depend upon the state of the soft parts around. If the integument has been long subjected to inflammation it will be thickened, swelled, and tough, having lost its elasticity, and then, according to some authorities, free incisions will be necessary, such as the +, or H, Fig. 52.

*Operation.* — Should the soft parts be little altered one longitudinal incision will suffice, as follows :—

To operate on either arm the surgeon should stand on the left hand side of his patient, who is recumbent. The arm of the patient should be flexed and carried across the front of the chest, the forearm being firmly held and supported by an assistant standing opposite to the operator, if the left elbow be the seat of disease, while the arm must be similarly held if the right elbow is to be removed. The ulnar nerve is to be felt for and pressed towards the internal condyle, and be there maintained and guarded from the knife by the point of the left thumb during the reflexion of the integument and muscles on the inner side. A longitudinal incision is to be made along the middle of the posterior surface of the arm, to the extent of three fingers' breadth both above and below the point of the olecranon, dividing the soft parts down to the bone. Above the olecranon the triceps will be divided into

two portions ; each half is to be separated from the bone, likewise the integument and muscles from the internal and external condyles of the humerus and upper ends of the radius and ulna, the edge of the knife being always directed towards and cutting upon the bone. As soon as convenient the ulnar nerve should be slipped over the internal condyle, and be there maintained. The olecranon will be exposed first, and should be removed either with a bone forceps or saw, thus exposing the interior of the joint, and allowing the operator to determine the amount of disease present and the extent of bone demanding removal. By forcibly flexing the arm and dividing ligamentous or muscular fibres still uncut, the extremities of the humerus, and of the radius and ulna united, may separately be made prominent, and be removed with a saw. Usually no vessel requires to be ligatured, and the wound being closed and dressed, the limb is to be placed straight, on a long pillow. No splint is requisite, except in the case of restless children. If the case do well, "passive motion" should be commenced from ten to twenty days after the operation, to prevent bony ankylosis. *a, b, c* (see Fig. 52), show respectively portions of humerus, ulna, and radius after removal. It is rarely necessary to remove so large a portion of either bone.

*Author's method*—in order to preserve extension of the forearm.

"Of the major operations, probably no one is



more successful in saving life and securing an useful limb than excision of the elbow-joint. The articulation is reached, and the ends of the bones are exposed and removed with comparative ease, by a posterior longitudinal incision, with or without the addition of a short transverse cut, the latter through the *skin only*. By complying with the general principles of surgery applicable to resections, few important structures are injured by the knife, and as a result we have a most useful limb—one, it is said, generally capable of performing to a large extent *all* the functions and movements of the healthy member.

“It is from the latter statement that I venture to differ. Flexion shall be good, supination and pronation tolerably good; but *extension* of the forearm is generally impossible. For the latter defect, the mode of operating is responsible; but the remedy is easy, and our knowledge of anatomy will supply it. Although probably the majority of surgeons now employ the longitudinal incision, yet a certain structure to be alluded to is often severed to facilitate the operation, because its value is unknown. It is possible that the reader will be surprised when I say that the power of extension is rarely preserved; and when it is, the means is probably not understood. On testing the movements retained by the forearm of a patient who has undergone excision of the elbow, extension appears perfect, while in reality it may be, and often is, altogether absent. A patient

is desired to bend and then to straighten the forearm. He complies with the former request ; but when the limb becomes again straight, it is purely by the force of gravity ; the hand and forearm fall, but are in no way extended by the triceps. The triceps muscle has no longer an attachment to the forearm. It will be remembered that the triceps muscle, while being firmly attached to the olecranon, also sends some of its tendinous fibres beyond that process to blend with the fascia of the forearm, especially with that portion of the fascia overlying the anconeus muscle ; and by these fibres it is that extension may be *always* secured after excision. It is, however, probable that in exceptional instances the cut triceps acquires attachment to the end of the ulna, through the medium of fibrous tissue formed during repair. By this means, some amount of extension is secured ; but it is accidental, and cannot be foretold in an individual case.

*Operation.*—"In speaking of this operation, I must be understood to refer to that method by which the articular ends of the bones are cut away to the extent to which they are normally covered by cartilage—the one now generally adopted. I commence by a longitudinal incision at the back of the limb, in length three or four fingers' breadth both above and below and crossing the point of the olecranon. Then, if there be a wound in the adjacent integument, conveniently situated, I generally lay it open into the longitudinal incision, and am able to expose

the bone-ends with greater facility. I next let the knife sink into the triceps muscle, and divide it longitudinally into two portions, the inner one of which is the more firmly attached to the ulna, while the outer portion is continuous with the anconeus muscle, and sends some tendinous fibres to blend with the fascia of the forearm. It is these latter fibres that are to be scrupulously preserved. Thus, in concluding the early steps of the operation, two chief points have to be remembered, instead of one (care for the ulna nerve) as hitherto advised. The ulna nerve, often unseen, must be lifted from its bed and be carried over the internal condyle to a safe place; and then the outer portion of the triceps muscle, with its tendinous prolongation, the fascia of the forearm and the anconeus muscle, must be dissected up, as it were, in one piece, sufficiently to allow of its being temporarily carried out over the external condyle of the humerus. This done, the operator may proceed in the usual way; but it is not my intention to follow him further in this paper. I will add that I have exhibited at meetings of the Hunterian and Medical Societies of London three patients, adult males, who had undergone excision of the elbow-joint, and all who saw them were surprised by the degree of active extension of the forearm by the triceps muscle which each possessed."

"The drawing (Fig. 53) shows the state of parts after primary excision has been performed, by the

usual longitudinal incision, upon a left extremity. The tenaculum sustains the band of fibres which is to be preserved uncut.”\*




FIG. 53.

Fig. 54 represents the arm of one of the gentlemen above referred to. The forearm is in the position of active extension by the triceps. This patient can play billiards, quoits, and use “the gloves” with facility. The operation was performed three years ago.

*Dressing the Wound.*—After injuries of or opera-

\* *British Medical Journal*, July 29, 1871.

tions upon joints, and in cases in which the continuity of a bone has been destroyed, it will be well to disturb the limb as little as possible when the wound is cleansed and dressed. When the limb



FIG. 54.

is *put up*, and it is necessary to invest its circumference with some dressing, such as strips of wet lint, which requires to be changed daily, this change



may be effected without moving the limb, by pinning strips of lint similar to those first used, each to one end of an original piece; then drawing gently upon the other end of the strip to be removed, the fresh piece will follow under the limb and replace the dirty portion.

*Excision of the Radius, and of the Ulna.*—Portions of either of these bones may be excised with the necessary precautions, especially the lower end of the ulna, where it is comparatively superficial, and, although close to the wrist-joint, may be removed without opening this articulation. In removing portions of these bones, care must be had not to interfere unnecessarily with tendons, and to leave important vessels and nerves intact; and to do this the edge of the knife should be studiously kept close to the bone in progress of removal.

*Operation.*—To excise the lower portion of the ulna make an incision along its inner border of the requisite extent, beginning at the styloid process of the same. Detach carefully the extensor carpi ulnaris from behind, and the pronator quadratus and other muscular fibres in front, cutting close upon the bone to avoid injuring the ulnar vessels and nerve. Take now the “excision director,” and introduce the point on one side between the radius and ulna, thus traversing the inter-osseous membrane and bringing out the point on the other side of the ulna. Thus the bone is isolated; and the groove in the director having been turned uppermost, the saw may be

applied without the risk of lacerating the soft parts. Seize now the upper end of the portion of ulna to be removed with a pair of forceps, dragging upon the same, and dividing all remaining attachments short of the articular fibro-cartilage and external lateral ligament of the wrist-joint. By these means the fragment of bone will hang out of the wound, when the application of the bone forceps to the root of the styloid process will complete the separation without opening the wrist-joint. The triangular fibro-cartilage being attached to the base of the styloid process, the non-removal of the latter secures the integrity of the wrist-joint. The wound may be closed in the usual manner.

*Excision of the Wrist-joint, &c.*—This articulation may be removed with a view to saving the hand, by various incisions; as a *curved* incision with convexity downwards across the back of the wrist from one styloid process to the other, dividing tendons as well as integuments. The semi-lunar flap is dissected up; and the joint having been opened, the diseased portions of bone can be readily removed, but at the expense of the extensors of the fingers.

It is desirable to maintain the extensors of the thumb and fingers uncut; and with that view the articulation may be removed by two *lateral* incisions, one along the inner border of the ulna, as already described, and a similar one along the border of the radius, to one or both of which

perpendicular cuts a short transverse incision may, if deemed necessary, be added opposite to the joint, so as to form a small flap; the required portions of the radius and ulna are to be removed, after the manner indicated in excision of the lower end of the ulna, due care being paid to preserve the extensors of the thumb and fingers, and also the parts in front of the joint, from injury. The extensors of the wrist need not be studiously preserved intact. The ends of the radius and ulna having been removed, the carpal bones may be made to protrude on either side through the wound, and can be readily disposed of.

*Another method* consists in making one incision only, and that along the inner side of the ulna and hand to the extent of two or three inches above, and the same below, the articulation. The soft parts in front and behind are to be carefully dissected off the bones: ligamentous fibres must be severed or torn through, when by forcible abduction the carpal bones may be made to protrude at the wound; these removed, the radius and ulna may be similarly treated. Should either the radial or ulnar arteries be accidentally or intentionally divided, both ends must be ligatured. The limb should be placed on a splint, with the hand prone, and after the lapse of some days, when the parts are beginning to solidify, passive motion should be attempted; the fingers, too, must be exercised from day to day soon after the operation.

*Lister's method* (almost in his own words).—In the living, any adhesions of tendons are to be broken down by freely moving all the articulations of the hand, and a tourniquet should be used to prevent oozing. A radial incision, L. L. (Fig. 55), is planned, so




FIG. 55.

as to avoid the radial artery A, and also the tendons of the extensor secundi internodii pollicis B and indicator C. It commences above at the middle of the

dorsal aspect of the radius on a level with the styloid process. Thence it is at first directed towards the inner side of the metacarpo-phalangeal articulation of the thumb, running parallel in this course to the extensor secundi internodii; but on reaching the line of the radial border of the second metacarpal bone, it is carried downwards longitudinally for half the length of the bone, the radial artery being thus avoided, as it lies somewhat further to the outer side of the limb. The soft parts at the radial side of the incision are next detached from the bones with the knife guided by the thumb-nail, so as to divide the tendon of the extensor carpi radialis longior  $\pi$  at its insertion into the base of the second metacarpal bone, and raise it, along with that of the extensor carpi radialis brevior  $\iota$  previously cut across, and the extensor secundi internodii; while the radial artery is somewhat outwards. This prepares the way for the next step, which is the separation of the trapezium from the rest of the carpus, by means of cutting forceps applied in a line with the longitudinal part of the incision—a procedure which, as experience shows, does not endanger the radial artery. The removal of the trapezium is reserved till the rest of the carpus has been taken away, when it can be dissected out without any considerable difficulty. The soft parts on the ulnar side of the incision are now dissected up from the carpus as far as is convenient, the hand being bent back to relax the extensor tendons of the fingers. The separation of



this is, however, best effected from the ulnar incision, as follows:—The knife is entered at least two inches above the end of the ulna, immediately anterior to the bone, and is carried downwards between it and the flexor carpi ulnaris, and on in a straight line as far as to the middle of the fifth metacarpal bone at its palmar aspect. The dorsal lip of this incision is then raised, and the tendon of the extensor carpi ulnaris is cut at its insertion into the fifth metacarpal bone, and is dissected up from its groove in the ulna, care being taken to avoid isolating it from the integuments, which would endanger its vitality. The extensors of the fingers are then readily separated from the carpus, and the dorsal and internal lateral ligaments of the wrist-joint are divided; but the connections of the tendons with the radius are purposely left undisturbed. The anterior surface of the ulna is now to be cleared by cutting towards the bone, so as to avoid the artery and nerve; the articulation of the pisiform bone is opened, if that has not been already done in making the incision, and the flexor tendons are separated from the carpus, the hand being depressed to relax them. While this is being done, the knife is arrested by the process of the ulnar bone, which is clipped through at its base with pliers. Care is taken to avoid carrying the knife further down the hand than the bases of the metacarpal bones; for this, besides inflicting unnecessary injury, would involve risk of cutting the deep

palmar arch. The anterior ligament of the wrist-joint is also divided, after which the junction between the carpus and metacarpus is severed with cutting pliers, and the carpus is extracted by seizing it from the ulnar incision with a pair of sequestrum forceps, and touching with the knife any ligamentous connections that may remain undivided. The hand being now forcibly everted, the articular ends of the radius and ulna will protrude at the ulnar incision, and are carefully examined and treated according to their condition. If they appear sound or very superficially affected, the articular surfaces only are removed. The ulna is divided obliquely with a small saw, so as to take away the cartilage-covered rounded part over which the radius sweeps, while the base of the styloid process is retained. The end of the radius is then cleared sufficiently to permit a thin slice to be sawn off parallel to the general direction of the inferior articular surface. For this purpose it is scarcely needful to disturb the tendons in their grooves on the back of the bone, the bevelled ungrooved part being enough to remove, and thus the extensor secundi internodii pollicis may never appear at all. The articular facet on the ulnar side of the bone is then clipped away with bone forceps applied longitudinally.

The metacarpal bones are next dealt with on the same principle, the second and third being most readily reached from the radial side, the fourth and fifth from the ulnar side. The trapezium is next

seized with a strong pair of forceps, and dissected out, so as to avoid cutting the tendon of the flexor carpi radialis, which is firmly bound into the groove on its palmar aspect, the knife being also kept close to the bone elsewhere to preserve the radial artery. The thumb being then pushed up longitudinally by an assistant, the articular end of its metacarpal bone is cleared and removed.

Lastly, the articular surface of the pisiform is clipped off, the rest of the bone being left, if sound, as it gives insertion to the flexor carpi ulnaris, and affords attachment to the anterior annular ligament. The same applies to the process of the unciform. The wounds are now to be closed more or less, and the limb placed on a suitable splint. The after-treatment requires much care. The principal objects to be kept in view are to maintain flexibility of the fingers by commencing passive movement of them on the second day, and at the same time to procure firmness of the wrist by securely fixing it during the process of consolidation.\*

*Exeision of the metacarpal bone of the Thumb.*—This bone has been removed, leaving to the patient a comparatively useful, although short member. The fleshy ball of the thumb forms a cushion, upon which the first phalanx rests, in such a manner as to offer a very fair amount of antagonism to the fingers.

\* See *Lancet*, April 1, 1865, p. 335.

## OPERATION.

Make an incision along the outer border of the bone, beginning the third of an inch above the superior articulation, and terminating the same distance beyond the metacarpo-phalangeal articulation. At each extremity of this cut, two short transverse incisions may be made, running outwards, so as to allow of the formation of a flap, as in Fig. 56. This flap, containing the extensors primi




FIG. 56.

and secundi internodii (*b, c*), uncut, is to be dissected up, and the soft parts on the palmar surface are also to be carefully shaved off close to the bone, without injuring the tendon of the flexor longus pollicis muscle. An assistant holding aside the above-mentioned extensors, the surgeon opens the distal articulation on the dorsal surface, enters the joint, and divides all ligamentous attachments. This done, the head of the bone (*a*) may be seized with the finger and thumb, and be made to protrude, while the knife divides the muscular attachments to

the inner side, but with due attention to the proximity of the radial artery. Open now the proximal articulation on the dorsal surface, dividing the insertion also of the extensor ossis metacarpi pollicis and other attachments, till the bone be freed. Close the wound in the usual manner. Should the radial artery or either of its terminal branches be wounded, both ends must be tied.

Excision of either of the remaining four metacarpal bones is unnecessary, and perhaps unjustifiable by reason of their complicated carpal articulations; the probable injury which may be inflicted on the palm of the hand, and when accomplished, leaves the finger ill-supported, and perhaps even an obstacle to the general utility of the hand.

*Excision of a phalangeal Articulation.*—Such operation should be resorted to in cases in which the thumb or forefinger is the seat of disease or injury; these two members, and especially the thumb, being more valuable and useful to the patient, even in a mutilated condition, than any three fingers conjointly.

The operation is performed by making a longitudinal incision on one or both sides of the articulation, dissecting the soft parts, opening the joint by severing the ligaments, and then causing the ends of the bones to protrude separately; they may be removed by the saw or bone forceps. Passive motion may be attempted after some days, or ankylosis be encouraged at an obtuse angle.

*Excision of the Hip-joint.*—This operation should



never be resorted to until rest, time, fresh air, and good diet have failed to arrest the disease. At length, when prophylactic measures have been proved to be of no avail, and the patient appears to be gradually growing worse, being worn out, either by excessive pain, or by the disease involving the pelvic bones, or as it were dying of inanition consequent on profuse suppuration, the operation may be performed.

The subject lying on the sound side, the position of the great trochanter should be ascertained, and the head of the bone may then be best exposed by making a semi-lunar incision (Fig. 57) skirting three sides of the trochanter, the convexity being directed upwards. The flap thus marked out should be thrown down, and, cutting close to the bone, the muscular attachments to the great trochanter should be completely severed. The limb being rotated by an assistant, the position of the head of the bone may be ascertained by the



FIG. 57.

finger of the operator. The capsular ligament may be divided posteriorly and superiorly close to the acetabulum; and, this done, forcible adduction and rotation inwards will cause the head of the bone to protrude, and even rupture the round ligament if it

be not already destroyed. The extent of disease being recognised, the chain or other saw may be adapted, and the portion of bone removed.

The extent of bone requiring removal cannot be previously determined upon. The articular surfaces having been carefully examined, as well as the adjacent bone, the judgment of the surgeon will decide upon the necessary ablation. As a rule it is desirable to remove the great trochanter with the head and neck of the bone, and also loose fragments of the os innominatum if there be such. The gouge and raspatory are often needed.

*Another method.*—In cases in which the joint is more or less disorganised by disease and the head of the bone somewhat displaced, either a simple longitudinal incision over this latter or the enlargement of an already existing wound will suffice.

Under the latter circumstances, excision of the head of the femur is an easy operation compared with its performance on the dead but healthy subject in which muscles and ligaments offer a formidable obstacle to excision. In most cases the acetabulum will be likewise in a state of caries, and if so, the whole of the disease should be removed either by the curved bone forceps or the gouge. Should pelvic abscess exist, the acetabulum may be perforated by the trephine.

The operation completed, the edges of the wound may be adapted to some extent; and, during repair, gentle extension should be kept up in order to prevent retraction of the limb towards the dorsum ilii.

Whatever incision may be preferred, the position of the sciatic nerve behind, and of the anterior crural nerve and femoral artery in front of the articulation, must be borne in mind.

*Excision in the continuity of the Femur.*—Portions of the femur have been cut down upon and removed, in cases of angular union after fracture and of ununited fracture. This is a formidable operation; but if resolved upon, the operator must select for his incision a point at which the bone is nearest the surface, and at a distance if possible from all important vessels and nerves. After the operation the case must be treated as one of compound fracture of the thigh.

In Paris, I have seen five inches of the middle of the shaft of the femur (the seat of a malignant tumour) of a lad removed. Such practice is frightfully hazardous, and quite unworthy to be ranked as an operation of conservative surgery.

*Excision of the Knee-joint.*—Excepting some cases of angular ankylosis, rendering the limb not only useless but an incumbrance to the proprietor, and for which excision of the parts corresponding to the original joint may be performed, after that the patient has been made aware of the risk, the same observations will apply to this as to the hip-joint, in reference to the selection of cases for operation, because time and experience are yet wanting to determine the value of this operation over that of amputation of the thigh.

*Operation.*—If determined upon, the articulation

will be best exposed by a semi-lunar incision. The patient being recumbent, and the limb supported by two assistants, one taking charge of the thigh and the other of the leg, the surgeon ascertains the position of the internal saphena vein by making pressure upon the inner side of the thigh, and so obstructing the flow of blood and causing the vein to swell. Standing on the outside to operate upon the right limb, and on the inside to operate on the left knee, he ascertains the point of attachment to the inner condyle of the femur of the tendon of the adductor magnus muscle, on the outside the point of attachment of a strong process of the fascia lata to the external condyle, also the attachment of the ligamentum patellæ to the tibia. These landmarks recognised, the semi-lunar incision is to be commenced over one condyle and carried down, and then across the limb, opposite to the upper end of the tubercle of the tibia, thence turning upwards, and terminated at the point delineated on the other condyle. This incision will inclose a well-rounded flap, base upwards, which may be readily turned up, so as to expose the patella and its connections (Fig. 58). This bone may be removed by a circular sweep round it, and the interior of the joint will be exposed. The leg should now be flexed by the assistant while the operator divides the external and internal lateral and the crucial ligaments, the latter with caution, remembering the position of the popliteal artery behind.

This done, the eondyles of the femur will protrude, and may be removed with the common saw after the knife has been earried round to divide the soft parts, and form a passage for the former instrument. The required extent of tibia is to be isolated in a similar manner by the knife, and then removed by the saw. In performing exeisions, the bow saw, with the teeth reversed, will be found of great service.




FIG. 58.

To assist in maintaining the eut surfaces of the femur and tibia in eontact, they may be fastened together by a wire suture in front. To diminish suppuration and prevent the formation of troublesome sinuses, the surgeon should eut away, as much as possible, diseased synovial membrane. When operating on a young subject, as little as possible of the epiphysis of the femur is to be removed. The



saw must leave a flat surface of bone to be brought into contact with the tibia, and the remnant of articular cartilage may be cut away with a scalpel.

The operation completed, two or three sutures may be used, and then the limb should be placed upon a long back splint, with foot-piece, two interrupted side splints, and to prevent rotation of the thigh outwards a fourth splint may with advantage be adapted to the anterior surface of the thigh. These carefully adjusted, while the patient is under the influence of chloroform, will favour success. Bony ankylosis is desired.

A very useful and inexpensive apparatus, after excision of the knee, is the plaster of Paris bandage strengthened by wire splints. The operation completed, the foot, leg, and thigh are to be covered with a flannel bandage, and outside this two interrupted wire splints, also covered with flannel, are to be adjusted to the limbs, and then the whole is to be encased by the plaster of Paris bandage. The bandage can be strengthened behind the knee by a short splint. Should the patient complain of undue pressure or the limb increase in bulk, the bandage can be cut up longitudinally and be still retained by one or two turns of a bandage. A patient operated on successfully by the author wore this apparatus for seven consecutive months.\*

*Excision of the Fibula.*—Portions of the fibula may be readily removed, in accordance with the plan laid

\* See "London Hospital Reports," vol. iv. p. 250.

down for operations of a similar kind on the upper extremity.

*Excision of the Ankle-joint.*—The bones forming this articulation are so intimately connected with important organs that the joint cannot but be removed with difficulty.

In cases of compound dislocation, the original wound must be conveniently enlarged, if this operation be determined upon.

Should the case be otherwise than traumatic, the operator may expose the inferior extremities of the tibia and fibula consecutively, by a longitudinal incision over each bone; that over the tibia being joined at its lower extremity just below the internal malleolus by a short semilunar incision, corresponding with the margin and breadth of the malleolus.




FIG. 59.

The integuments should be carefully dissected off the bones to the required extent, when either the "excision director" (Fig. 59) and common saw, or

the chain saw or cutting forceps, may be employed to sever the fibula.

Seizing now the upper end of the loosened fragment with a pair of forceps, the operator cautiously divides the inter-osseous and ligamentous attachments from above downwards, until the portion of



FIG. 60.

bone is detached. The fragment of fibula having been removed, it becomes necessary to treat the tibia similarly. This bone is comparatively massive, and in such close relation with important organs that its section cannot be so readily effected. The soft parts having been very carefully dissected off the tibia without injury to adjacent tendons, vessels, and

nerves, the internal lateral ligament must be severed, if not already destroyed by disease. The foot must now be forcibly dislocated outwards, and the lower end of the tibia being protruded at the wound, can be sawn off. The upper surface of the astragalus will be best removed by a narrow-bladed saw worked through the existing wounds. The operation completed by a partial closure of the incisions, the limb should be put up with the foot at a right angle to the leg. Although bony ankylosis should occur, a most useful member is secured to the patient.\*

*Excision of the metatarso-phalangeal Articulation.*  
—Excepting the joint of the great toe, no other metatarso-phalangeal articulation need be submitted to an operative proceeding short of amputation. The metatarso-phalangeal articulation may be best exposed by a free longitudinal incision along its inner side: this may be converted into an  $\times$  or  $<$  incision by a short cut opposite to the joint. The joint having been opened, the proximal end of the phalanx should be first protruded and be cut off with the bone forceps; this done, the head of the metatarsal bone may be treated in a similar manner. I have seen a patient walk perfectly well after this operation has been performed.

\* In 1864 the author excised the ankle-joint in a lad fourteen years of age. After a time he became a collector of money, and has been able ever since to walk for many hours daily without the least discomfort.—("London Hospital Reports," 1865.) Fig. 60 shows the appearance of this patient's limb eight years subsequent to operation.

A narrow-bladed knife should be used in operations about the joints of the toes and fingers.

*Subperiosteal Excision.*—With a hope that bones and portions of bone might be restored if their periosteal covering were retained, various operations were undertaken with that view, and with a most gratifying result—bone was richly reproduced. This plan is applicable to the excision of joints. The instruments specially requisite are, various raspatories or *detache-tendon*, both sharp and blunt, a chain saw, and an excision director (Fig. 59). The soft parts covering the bone or portion of bones to be removed are divided longitudinally, or as they would be by the method commonly adopted, with due regard to all important structures. The periosteum is to be similarly treated, and then is to be carefully separated from the subjacent bone by the raspatories, on its exposed surface first. The excision director, or a grooved raspatory, must now be cautiously insinuated between the bone and periosteum, still adherent on its other face, so as to admit of the placing *in situ* the chain saw with which the bone thus isolated is to be sawn across. The fragment being now seized with forceps, can be removed by a few more careful touches with a raspatory. Thus the normal relation of parts superficial to the periosteum is little altered, and muscles are left adherent to the periosteum. This operation is not to be hurried lest the periosteum be much torn, and if necessary to facilitate the procedure, a short trans-



verse incision may be made at right angles to the longitudinal cut in it.

*Bifid Fingers and Toes.*—This deformity may be remedied by amputation of the supplementary member. Examine carefully the comparative merits of the two members, and remove the one which appears to be the less useful and most unlike the natural organ. One synovial membrane usually lines both bones as well as that upon which they rest. The supplementary member should therefore be removed in its continuity by dividing the bone obliquely with saw or cutting forceps, leaving as small a portion of bone as possible, short of opening the joint.

*Excision of Tarsal Bones.*—The *astragalus* is sometimes dislocated, and, unless immediately removed, gives rise to violent inflammation, which in many cases has proved fatal without even giving the patient a chance of life by amputation. The prominently displaced bone should be cut down upon and removed, with due regard to adjacent tendons, vessels, and nerves.

The foot after the operation should be kept at a right angle to the leg.

The *os calcis* may be excised, leaving a very serviceable foot. The heel bone is to be laid bare by making a flap of the integument covering it, by a horse-shoe shaped incision, the inner arm of the shoe being shorter than the external, and terminating on the inner side of the foot under the internal

malleolus, so as to avoid injury to the vessels, nerves, and tendons of the region. The arc of the shoe will be represented by prolonging the incision in the skin of the heel on a level with the insertion of the tendo-achillis, and the long arm traversing the outer border of the foot beneath the external malleolus should terminate just beyond the calcaneo-euboid articulation. The tendon of the peroneus longus muscle is not to be injured. Throughout the operation the knife must be kept close to the bone, especially on its under and inner aspects, and the ligaments uniting the os calcis and astragalus should be attacked on the outside as soon as the insertion of the tendo-achillis has been severed.

*Another method*, requiring the expenditure of a little more time.—If the long arm of the horse-shoe incision be carried on a little beyond the calcaneo-euboid joint, the short arm need not be cut at all, but instead of this latter a short perpendicular cut towards the sole should join the transverse incision at a right angle over the centre of the heel. Thus an external flap is formed, and can be turned down so as to admit of removal of the bone. The important structures on the inner side of the os calcis must be carefully preserved.

*Ununited Fracture*.—Excision of the ends of the fragments has been already referred to. As a less severe and often successful measure, fastening the ends of the bones together by means of ivory pegs

driven into them may be adopted. The relation of one fragment to the other having been made out by careful manipulation, the surgeon punctures the integuments down to the bone at the point at which a peg is to be introduced, and bores a hole with a drill in the requisite direction, so as to include both fragments. The drill removed, an ivory peg of the required length and thickness, say one-and-a-half inches in length and the sixth of an inch in diameter at the largest extremity, may be driven in so as to unite the fragments, with a wooden mallet. In the case of the tibia two pegs will suffice, a small portion of each being allowed to project at the wound, in order that it may be seized with a forceps and removed at pleasure. Should the case do well, the pegs may be left in for a month, with the leg perfectly at rest. At the expiration of this time, the pegs having been removed, the limb should be carefully put up in a plaster of Paris bandage, and so be kept for another month or six weeks.

*Compound Fracture.*—In certain cases of compound fracture, one fragment protrudes and cannot be readily replaced. To favour reduction, besides a position favourable to muscular relaxation followed by extension, either tenotomy may be useful, such as division of the tendo-achillis; or free incision of the soft parts parallel to the long axis of the protruded bone, apparently offering mechanical obstruction to reduction; or removal by the saw of the end of the projecting fragment; or, as in compound

dislocation, removal of the protruded head of the bone.

*Compound comminuted Fracture.*—Small detached fragments of bone should be removed at once, if they can be reached without adding to the magnitude of the existing injury. The wound should be thoroughly cleansed of all foreign bodies also.

*Exostoses.*—Outgrowths of bone, if in any way troublesome, and not too near a joint, may be removed by cutting down upon them, due regard being paid to adjacent tendons, vessels, and nerves, and be removed by the saw, forceps, or chisel.

*Abscess in Bone.*—A crucial, or other convenient form of incision, should be made over the expected seat of matter and the flaps dissected up, when the trephine may be applied to open the cavity. Pus will be recognised by its oozing by the side of the trephine, or the cavity will be known to be opened by a diminution in the resistance offered to the working of the trephine.

*Necrosis and Caries.*—Certain operations are often resorted to, both to check the progress of caries and to assist Nature in the ejection of dead bone.

*Necrosis and Exfoliating Bone* are usually seated within and upon the shaft of bones, while the seat of caries is generally the cancellous extremities of long bones and the small irregular bones. During the progress of a case of necrosis, in which more or less of the shaft of a bone dies, while, at the same time, new bone is developed around to maintain the

natural conformation of the limb and give attachment to muscles, Nature, by progressive absorption, establishes at different points fistulous openings or cloacæ, which communicate through the shell of new bone with the external world, and the sequestrum of bone within.

In process of time Nature in some few cases effects a cure, by ejecting the dead bone through these cloacæ; but this is an exception to the rule, and since dead bone is not absorbed, and therefore can never become smaller with a view to its expulsion, and since also it lies probably at a right angle to these cloacæ, and a mechanical impediment is also offered to its ejection by the surrounding shell of new bone, Art may with advantage be called in to assist Nature. To detect dead bone a probe is usually introduced through the fistulous opening, and the sensation communicated need only be felt once to be never forgotten. By fixing the probe firmly upon the dead bone, and moving it laterally, the sequestrum may be felt to yield, and, if so, the sooner it be removed the better. To do this, it may be necessary only to introduce a pair of forceps through the fistula, seize the sequestrum and withdraw it; or it may be needful to enlarge the fistula by incising the integuments, and to remove a portion of new bone with cutting forceps, trephine, or chisel, in order to admit the entrance of the forceps. Again, a sequestrum may be so large and long as to require division before it can be removed; this step will



require a more extensive division of integuments, say the interval of two cloacæ, then the application of the trephine to remove a portion of the new shell, and admit the cutting forceps to divide the sequestrum; this done, each half of the dead bone can perhaps be removed with the forceps.

*Death of the ungual phalanx* is a frequent consequence of acute inflammation. It is usually detached from one to two months after the commencement of the disease, and should be removed either through an existing opening, or by incision, leaving the nail and extremity of the finger to the use of the patient, as an organ of touch.

*Exfoliation*.—When a portion of bone has been deprived of its periosteum, it frequently dies, and is either thrown off by Nature, or may be removed when loose by the surgeon.

This is a comparatively simple operation, being done by introducing a pair of forceps through the existing wound, seizing the dead portion of bone, and removing it with the same. Should the exfoliation be partially overlapped by the surrounding soft parts, suitable incisions will facilitate extraction. In cases of loss of pericranium, the surgeon should not too hastily condemn bone because it has lost its investing membrane: granulations will often spring up where they are little expected.

*Caries*.—This inveterate disease may sometimes be checked by gouging away the surface of bone on which it is seated, but more certainly, when prac-

licable, by excising the whole of the affected bone; as for instance the os calcis. The surgeon must make choice of his incision according to the extent and position of the disease, due attention being paid to the locality of important tendons, vessels, and nerves, especially those on the inner side of the foot.

Strong nitric acid or the actual cautery may be employed to destroy caries.

Excision of joints for caries has been referred to.

*The Trephine* (Fig. 61).—This instrument is




FIG. 61.

essentially a circular saw, with a pin in the centre to fix it on the required spot. It is used to open bony cavities, especially that of the head, in cases of fracture, or to favour the discharge of certain injurious contents, as pus and extravasated blood. In either case a + or otherwise convenient incision

is made, or an existing wound may be enlarged, so as to allow of the application of the instrument to the bone, the pericranium being preserved if possible. Having been fixed with the central pin, the instrument is worked by alternating supination and pronation, the pressure being lessened as the section is nearly completed, lest the contents of the head be injured. The progress of the operation must be tested at intervals by the removal of the trephine, and the introduction of a probe or toothpick to ascertain the depth of the incision; also, as soon as a groove has been made for the trephine to work in, the pin should be elevated lest it perforate the skull. It will be known when the diploe is reached, either by an oozing of blood or by diminution of resistance offered. The section completed, an elevator may be used to remove the loosened fragment. In the instance of fracture, whether simple or compound, with depressed bone, a segment only of the sound adjacent skull should be removed, sufficiently large to admit of the introduction of an elevator. In some cases a Hey's saw (Fig. 62) may be substituted for the trephine. In all cases as small a portion as possible of the skull should be removed, because the loss is rarely thoroughly made good by development of new bone.

*Anchylosis* may be false or true. *False*, as a result of the maintenance of a limb in one position for a length of time, thus allowing the muscles to become wasted, inactive, contracted, and unable to

accommodate themselves to any other position; or the bones forming an articulation, may be united by the intervention of fibrous tissue. This variety




FIG. 62.

must be treated by forcible movement of the limb, and in many cases by forcible extension of the joint after division of tendons, the extension being kept up and increased by suitable apparatus.

*True*, as in cases of union of bones originally forming a joint, by bone. In some instances of this kind, it may be justifiable to break down, either by force or by chisel and mallet or by saw subcutaneously, the bony adhesions, with a view to restore the utility of a distorted member.

In selected cases of ankylosis at the hip-joint, W. Adams and others have severed subcutaneously, with a saw, the neck of the femur.

L. Stromeyer Little has severed subcutaneously, with chisel and mallet, a bony ankylosis of a knee-joint.

The comparative facility with which excision of joints is performed on the living and dead subject varies. In the case of long-standing disease in the

living, the relative anatomy of the part is altered, the soft parts are agglutinated, have lost their elasticity, and become unyielding and adherent to adjacent structures, rendering their separation from the bones, and exposure of the diseased extremities, difficult. The bone, too, which is the seat of disease, becomes softened, and cannot, without the risk of fracturing the diseased portion, be used as a lever to assist the surgeon in exposing its extremity.

On the other hand, inflammation and non-use have so altered the character of the tissues in which the former is seated, that adjacent muscles are wasted, while ligamentous structures are either so softened or destroyed as to offer very little impediment to the performance of the operation. In the dead subject, however, while the surgeon can employ the sound bone as a lever to assist in disarticulation, and can readily dissect the soft parts from off the bones, still the healthy ligaments offer a great obstacle to the performance of the operation. On the whole, however, I should say that excision of a joint may be performed more readily when the structures are healthy than when the seat of disease.

Fig. 63 shows the *bow* saw, the blade of which can be reversed at pleasure.






FIG. 63.

## CHAPTER VII.

### OPERATIONS ON THE SURFACE OF THE BODY.

*Abscess, acute and chronic.*—To evacuate an acute abscess, seek the spot at which the integuments are comparatively thin, and apparently about to give way by progressive absorption. This position may often be recognised by the finger detecting a softer and circumscribed spot, at which perhaps the cuticle is about to fall off. Select also the most depending point, so as to favour the discharge of pus; and incise the part parallel to the natural folds of skin, that the cicatrix may not be readily seen afterwards. Also, in important regions open the abscess, holding the knife parallel to large vessels and nerves; and if the pus be deep, first divide the integument with a knife, and then through the wound thus made plunge a pair of dressing forceps into the sac of the abscess, separating the blades as soon as entered, in order to favour the discharge by enlarging the opening. In the neck, especially of a female, abscess should be opened as soon as possible, and with a small knife, to avoid an ugly scar. In the breast

abscess should be opened as soon as fluctuation can be detected, lest the pus burrow in different directions through the organ.

*Chronic Abscess.*—If it be decided to open a chronic abscess, it may be thought advisable to do so with a view to favour gradual contraction of the sac and prevent at the same time the entrance of air. To do this either a trocar and canula may be used, or a knife. To avoid entrance of air the skin should be punctured, either by making use of the natural elasticity of the same, by drawing it on one side of the intended point of puncture and at the same time plunging the instrument through the integument and sac of the abscess, which latter being evacuated to the required extent, the skin may be allowed to return to its natural position, when the wound in the latter and in the sac of the abscess will no longer correspond; or, by passing the knife obliquely under the skin for some little distance, and then entering the sac of the abscess, by this means a valvular opening is made. In both instances a compress of lint and bandage, with more or less pressure, should be employed to favour contraction of the sac of the abscess. When opening large abscesses, the pus is shot out to a great distance sometimes, thus soiling the bed, the operator and his assistants. To avoid this accident, a temporary shield of paper or of gutta serena sheeting, three or four inches square, may be readily adjusted to the knife at the junction of its handle and blade. Should abscess be situated be-

neath fasciæ, and the opening made to be permanent, a strip of oiled lint must be introduced and kept between the edges of the external wound for twenty-four hours, lest union take place before it is desirable.

*Acupuncture.*—This operation, as its name expresses, consists in the introduction of a sharp and long needle into the soft parts. It should be made to penetrate by a twisting motion.

*Caustics, fluid and solid.*—Fluid, such as the mineral acids, are best applied with a glass rod or glass brush. If to the skin, the surrounding part should be previously protected by the application of a piece or pieces of adhesive plaster, a hole of the requisite dimensions having been cut out of the centre. If to a wound, the surface having been previously dried, the margins of the same will perhaps determine the extent of the application.

*Solid, in powder or stick.*—If the skin be entire, the required extent of surface may be destroyed by isolating it as above described, and then by applying and leaving a certain portion of the caustic in contact with the same till the tissue is destroyed and the slough thrown off by ulceration, when continued applications may be made to destroy the deeper structures, as in treating malignant disease of the breast by escharotic.

*The actual cautery.*—The red-hot iron applied to the surface is a powerful counter-irritant, and is attended in its use by comparatively little suffering.

The shape of the portion of iron employed must depend upon the conformation of the part and the extent of surface to which it is to be applied. Its application is effected more rapidly than that of the "moxa," is equally efficacious, and may replace it with advantage.

A *galvanic* cautery is now employed.

*Exploration.*—When tumours of a doubtful nature are presented to the surgeon, exploration of the same to clear up the doubt and determine their nature is often resorted to. Instruments used are either a trocar and canula, or grooved needle. The grooved needle is preferable, and should consist of a cylinder, *one quarter only* of the circumference of which has been cut away. Should the needle be *semicircular*, as very many in use are, the groove when the instrument enters the soft parts becomes occupied by a portion of integument which prevents the exit of contained fluid. Thick fluids will not readily flow through a small canula. Under such circumstances, a bristle or probe may be passed along the canula to encourage their egress. The exploration effected, the wound may be closed by a compress of lint and strapping.

*Issue.*—An issue is made either by incising the skin and introducing a foreign body, such as a pea, or rubbing in a caustic to keep up irritation, or by the application of some caustic to the surface.

*Seton* is made by introducing and maintaining a foreign body, such as a skein of thread, under a



portion of integument. Its introduction is effected (Fig. 64) by raising a fold of integument and carry-




FIG. 64.

ing a knife, or better, a double-edged seton-needle (Fig. 65), armed with the thread, through the base



FIG. 65.

of it: the needle withdrawn, one end of the thread will project on either side of the wound, when to prevent accidental removal they may be tied loosely together.

The threads may be smeared with any irritant, if necessary, and thus armed, be drawn through the wound at pleasure.

*Vaccination* is best practised with a fine-grooved needle. Some of the contents of a well-developed vesicle, say on the eighth day, should be received upon the needle, the point of which is to be intro-

duced thus armed, at usually three points, under the cuticle. Or, while the skin is made tense with the finger and thumb of the left hand, scratches may be made with a lancet, and *points* conveying the lymph may be introduced and rubbed one into each scratch.

## CHAPTER VIII.

### AMPUTATION.

AMPUTATION is the term applied to the operation by which the whole or portion of a member is removed from the body, and has for its object the separation of that whole or portion of member which is deemed to be either congenitally, idiopathically, or traumatically useless or even injurious to its owner ; in order either, as a necessity to prolong life by substituting a lesser injury for a greater, and so to tax the reparative powers of nature as little as possible, or, as a means of affording relief and comfort.

The laws which are to guide the surgeon in his selection of cases for amputation cannot be precisely defined on paper. His decision must be formed by a reference to *experience* ; by a careful examination of the general condition of the patient as well as of the local abnormality ; his age, habits, occupation, social position, and the probable consequences, whether amputation be or be not performed, must have their due share in determining his line of

action. In the case of congenital or other malformation, time when for amputation may perhaps be arranged at leisure; in the instance of disease, its ravages, both general and local, will guide the surgeon; and in the case of injury, amputation cannot be performed too early, provided that the patient be not in a state of collapse. Should there be in the mind of the surgeon a doubt as to the necessity for immediate amputation, let him give the patient the benefit of that doubt, and delay the operation.

Amputation having been determined upon, the surgeon must not forget one important rule, *to remove as small a portion of the body as possible*, with a view to mutilate the patient as little as need be, and also to occasion the least degree of shock to the system. This rule may, however, be occasionally deviated from, and some exceptions will be mentioned hereafter. Bearing in mind the above rule and its exceptions, one of two points at which the member may be separated from the body should be chosen by the operator, and these are termed respectively *point of necessity* and *point of election*, meaning that the operator would prefer the point of election to the point of necessity, if he were convinced that the after comfort gained to the patient, should he survive the operation at the point of election, would be more than equivalent to the risk incurred. Again, the social position, occupation, and prospects in life of the patient must be taken into consideration, because

the man who has to earn his daily bread by physical exertion must be provided with a stump as serviceable as possible, while his more fortunate and wealthy co-sufferer, who is in a position to obtain a costly mechanical substitute, is perhaps content with a shapely rather than useful limb.

Amputation is affected by various methods, as by *flap*; by *circular incision*; by *oval incision*; these again are modified according to the fancy of the operator.

Amputation, to be conveniently performed, requires the aid of certain assistants and the use of certain instruments, and, to avoid repetition, I will detail an amputation, *according to rule*, at the middle of the thigh, by—

*Double-flap*.—The patient being recumbent, and at a height which shall allow the surgeon to perform his manipulations with ease, one or two assistants should take charge of the head and trunk of the subject; a third should be responsible for the main artery of the limb; a fourth must be in readiness to support the thigh above the intended point of section, and also the flaps when cut; a fifth sustains the distal portion of the limb, and is prepared to ligature the vessels, &c., &c. Instruments and appliances may either be placed near to the surgeon or may be handed to him as required. They consist in an appropriate tourniquet, knife, saw, scalpel, bone forceps, artery forceps, tenaculum, acupressure needles, ligatures, sutures, strapping and scissors.



lint, bandages, sponges, and brandy. The assistants being in position, the operator recognises the course of the main artery by its pulsation, and applies the tourniquet in readiness to compress the vessel against some portion of bone, the upper part of the shaft of the femur for example, the satisfactory application of which may be tested by ascertaining that there is no pulsation in the arteries below the point of compression. This done, assistants draw the patient towards the edge of the table and fix the sound limb with a bandage to a leg of the latter that it may not in any way interfere with the operation. The limb to be removed must be held horizontally. The operator, armed with a sharp-pointed knife, the blade of which should be from two to three inches longer than the diameter of the limb at the intended point of section, stands according to his fancy, either on the outside or on the inside, say outside in this instance, and grasping with his left hand the soft parts in front of the bone, raises them so as to have as much integument as possible in the anterior flap, and at the same moment enters the point of his knife on the outside and middle of the limb, and carries it across the thigh in front of the bone (slightly depressing the handle so as not to break the point) to a corresponding spot on the inside, at which the point make its exit. If now the operator can, by cutting towards the knee, and at the same time from heel to point of the knife, withdraw it and form a flap, the anterior flap is made, as in Fig. 66, where it is turned back ;

the posterior flap is made in a similar manner, the knife being passed behind, but not quite close to the bone, lest the main vessels likewise be pierced. If he cannot perform the above manœuvre, the flaps




FIG. 66.

must be cut by a to-and-fro movement, as in using a saw. One or two sweeps of the knife around the bone close to the bases of the flaps, held aside by an assistant, sever the remaining attachments and the periosteum, and prepare the way for the

*Saw.*—To use this instrument, place first the heel of it upon the bone, and draw it with firm pressure across the latter, from *heel to point*, so as to form a groove in which it is to be worked to and fro, but now from *point to heel*, and with moderate pressure, only when carried forward, from the hand of the surgeon. An English hand-saw cuts only when

carried forwards from point to heel, allowing an interval of repose between each stroke. The saw should be held perpendicularly (when only one bone is interested), the point being towards the ground, in order that splintering of the bone may be avoided by opposing to the weight of the limb below the saw up to the moment of separation, a gradually diminishing segment of bone, the chord of the arc of which is directed from above downwards.

The saw should be tolerably heavy, requiring to be guided with *moderate pressure only* by the operator, and should be worked steadily from point to heel, rather than by short and irregular strokes. The ready application of the saw by a surgeon performing amputation, depends greatly upon the aid given by the assistants who hold the limb. The bone to be severed should be held horizontally lest it be cut obliquely, and firmly and steadily at two points, one above, the other below, the point of section. Thus, if it be the thigh bone, it will not be sufficient for the assistant to hold the leg below the knee, the condyles of the femur must be grasped by him, and be neither depressed nor elevated during the working of the saw. If there be two bones, both must be held firmly and separately; otherwise, should both be grasped by one hand, they will probably become approximated, and interfere with the action of the saw, if, as is usual, one be divided before the other.

When two bones are to be severed—as tibia and

fibula, or radius and ulna, for example—the saw should be first applied to the thickest and most firmly fixed ; therefore to tibia and ulna respectively, including and completing the section of the fibula and of the radius, and terminating with the tibia and ulna. The section completed, as in Fig. 67, showing the two flaps, end of bone, and the main




FIG. 67.

artery and vein, the assistant raises the stump to a convenient height, and supports the flaps while the vessels are being ligatured. This step effected, the surface of the flaps should be freed from coagula with a soft sponge, be brought into apposition and their edges be adjusted, and be so maintained by suture, by strips of adhesive plaster passed between the sutures, by a thick pad of lint placed upon the cutaneous surface of either flap, and by a bandage

lightly applied from above downwards, leaving the face of the stump exposed so as not to prevent the escape of secretions, or only protected by a piece of lint placed lightly upon it. The patient being returned to bed, the stump should be raised to a convenient height on a pillow, and if jactitation arise may be bandaged to the cushion on which it rests.

*After-treatment* of a healthy stump consists in the maintenance of rest ; in cleanliness ; in allowing free escape of all secretions ; in avoiding constriction or tension at any point where swelling consequent on reaction comes on by removing the cause, whether it be bandage, plaster, or suture ; in good support with the palms of the hands during dressing, with a view to disturb the relation of the flaps to each other as little as possible.

Delay the first dressing of a healthy stump as long as is consistent with cleanliness.

*Length of Flaps.*—It is of importance to decide upon the requisite length of flaps, and as a rule each flap should be equal in length to rather less than one-third of the circumference of the limb, at the intended point of section of the bone ; or, flaps of unequal length should be, together, equivalent to two-thirds of the circumference of the limb. Let the flaps be too long rather than too short ; and to insure accuracy, the operator may, if he please, measure the circumference of the limb and mark out the flaps on the surface with pen and ink. If, by



an error in judgment, the soft parts be not long enough to cover the wound, a portion of bone may be removed after that the muscular attachments have been carefully detached by the knife held parallel to the long axis of the bone. This manoeuvre will allow of retraction of the soft parts to the requisite extent, when the saw may be applied, and the protruded portion of bone be removed.

#### VARIETIES AND MODIFICATIONS.

Instead of making an anterior and posterior flap by transfixion, as above described, some surgeons cut the anterior flap from skin to bone and from below upwards (Fig. 68), and afterwards form the posterior by transfixion ; others, in any case, form the posterior flap first.

Again, in very muscular subjects, the knife may be made to traverse the limb at a distance from the bone, and so form two flaps, each being composed of *part only* of the *muscular* structure and the integuments: the muscular structures remaining attached and adjacent to the bone must be divided by a circular sweep of the knife. By this mode the main vessels are cut transversely and run no risk of being wounded above their point of section, an accident which may happen by the ordinary method of transfixion.

Flaps of integument only may be preferred, the deeper structures being cut circularly at the intended point of section of the bone.

The ordinary operation by double flap (antero-posterior) may be replaced by lateral flaps, the steps of both operations being similar.

There is one objection to cutting by transfixion either the posterior flap or the flap which is to contain the main vessels first, and for this reason: these




FIG. 68.

vessels, in certain regions, lie just behind the bone or bones, and as the operator generally endeavours to include a good share of integument in the first flap the knife is passed as near as possible to the bone or bones, and thus the vessels are often pierced as well

as cut obliquely ; but if the flap which is not to carry the main vessels be cut first, the operator can readily manœuvre to keep at a distance from the track of these organs when forming the second flap.

#### AMPUTATION BY CIRCULAR INCISION.

As the term expresses, this operation is performed by one or more sweeps of the knife round the limb till the soft parts are divided down to the bone, and the saw being applied, completes the separation. The success of this mode, as of the flap operation, will depend upon giving to the divided bone a sufficient covering of soft parts ; and to insure this desideratum, various manœuvres have been resorted to from time to time.

The number and position of assistants, and similar instruments and appliances, are equally requisite for this as for the flap operation. Also, the steps of the operation, excepting the use of the knife, being alike, need not to be again detailed. With few exceptions, the surgeon will choose to stand on the outside of the limb, although, in any case, some prefer to have the left hand towards the trunk. The position chosen, the operator plants the sole of his left foot firmly upon the ground, while the right knee either approaches or rests also upon the floor ; the left hand rests either upon the distal or proximal side of the limb, while the right hand holds the knife and is below the limb. The knife is usually *grasped* firmly

by the hand of the surgeon, but when so held, the completion of the circular incision without removing the instrument from the body is difficult, and though effected, is an inelegant manoeuvre. I do not wish to infer that it is necessary to the success of the operation to finish the circular incision by one sweep; a second cut completes the section very much to the convenience of the surgeon.

Another mode of holding the knife is as a pen, but with its point upwards and directed somewhat towards the face of the operator, the edge being towards the limb to be removed.

The student may practise with advantage the method of holding and sweeping the knife round a limb with a paper-knife, when he will learn to imagine what no description can teach, how firmly to hold the knife, and also to form some idea of the amount of pressure that may be requisite to divide the soft parts in making the circular incision. He will also observe that the knife is, as it were, on a pivot represented by the forefinger and thumb, and upon which it must be allowed to turn in such a manner that when the incision is completed, the knife will be on the side of the limb nearest to the operator with its point directed slightly downwards and towards him. The incision should be commenced with the heel of the knife placed upon the upper surface of the limb held horizontally, and be made partly by pressure and partly by drawing the knife slowly from the heel towards the point, as well

as by an almost imperceptible to-and-fro movement. The handle of the knife should be smooth, and the blade heavy, and if held as described above, the circular incision may be completed with one sweep. Perhaps, for the oblique section of muscles so as to form a cone with the bone at its apex, the handle of the knife should be *grasped* as usual.

Previous to the commencement of the operation, the appointed assistant embraces with both hands the proximal portion of the limb, and at the same time makes gentle but equable traction upon the integuments, so as to preserve as much skin as possible to cover the wound. (The assistant must avoid drawing up the skin *during* its section, otherwise its margin will be cut unevenly.)

The first incision should divide the integument, when traction from above and a few slight touches with the knife at the requisite points will perhaps allow it to be drawn up to a sufficient height; if this plan do not succeed, the integument must be dissected off the deep fascia as delineated in Fig. 69.

The first step completed, a second sweep round the limb as high as the retracted skin will permit, divides the muscles, vessels, and nerves; a third sweep divides the periosteum, and lastly, the saw completes the separation.

*Another Method.*—First step consists in division of skin and deep fascia followed by traction from above; secondly, a sweep of the knife should divide the superficial set of muscles close to the edge of



the retracted skin — again traction from above ;




FIG. 69.




FIG. 70.

thirdly, division of the remaining muscles, blood-vessels, &c., close to the retracted soft parts, Fig. 70; fourthly, division of periosteum, followed by the application of the saw.

In all amputations by circular incision, after the skin has been divided, the remaining soft parts should be cut obliquely from below upwards, the edge of the knife being, for this purpose, directed upwards and towards the bone throughout each circular sweep. By this

means when the operation is completed the end of the bone will be found to form the apex of a cone, the base of which is at the cut margin of the skin, as in Fig. 71; the bone will also be well covered, and superabundance of soft parts is avoided; apposition of the raw surfaces and a sufficiently thick covering for the end of the bone is insured; whereas, after the completion of the operation begun as in Fig. 69, skin alone serves to cover the end of the bone, and as its opposing surfaces cannot be readily approximated, a pouch in which secretions are liable to lodge is formed.




FIG. 71.

Fig. 70 shows the wrinkled condition of the skin as well as the obliquely cut muscles and exposed bone after repeated sweeps of the knife followed by traction.

#### COMPARATIVE MERITS OF AMPUTATION BY FLAP AND BY CIRCULAR INCISION.

Amputation by flap is performed rapidly and with comparative ease; a good covering of soft parts is preserved to the bone; flaps also afford mutual support, and their whole surfaces being readily approximated and easily maintained in apposition, oozing of blood is prevented and rapid union may be antici-

pated; a flap or flaps may be cut at any part of the circumference of a limb, under circumstances of disease or injury in which the circular mode could not be applied; on the other hand, a larger number of ligatures is requisite; vessels are liable to be wounded above the point of division when the flaps are cut by transfixion; these, as well as nerves and tendons, are often exposed, to some extent, on the surface of a flap, and must be dissected out and cut short, thus prolonging the operation. The flap operation, performed indiscriminately, will in some cases be followed by retraction, resulting in a conical stump.

Amputation by circular incision, as at Fig. 69, is tedious to the operator, and more injurious to the patient. On the other hand, vessels, nerves, and tendons being cut short, do not require to be trimmed; fewer ligatures are necessary; there is less liability to retraction of soft parts, and the formation of a conical stump.

Thus it appears that each mode of performing amputation has its advantages and disadvantages, and practically each, or a modification of each method, is applicable to certain localities, as will be hereafter indicated.

#### AMPUTATION BY OVAL INCISION.

This method, which may be considered a modification of the circular, will be described under the head of *special amputations*.

## AMPUTATION IN THE CONTIGUITY OF A LIMB.

Amputation in the contiguity of a limb, or through an articulation, is not so readily performed as may at first thought be supposed. In many instances, to be cleverly executed, it requires a thorough knowledge of the anatomy of the articulation in question ; as, the relation of points of bone to each other ; the position of ligaments which must be divided before disarticulation can be effected ; the most vulnerable part of the joint under certain conditions, whether of flexion, extension, or otherwise, &c. ; still, with all this knowledge to aid, the surgeon will sometimes be baffled in his first attempts to open a joint.

Previous to performing amputation through a joint, the operator should manipulate the part carefully, with a view to discover some sure landmark to guide him to the articulation, as soon as it may be necessary to open it. Should this be impossible from the nature of the disease or injury necessitating amputation, the soft parts must be divided, and the line of articulation be sought for at the proper time, by repeated manipulations, and by a steady and cautious use of the knife, cutting and cutting upon the bone to be removed until the joint be found. It is at this stage of the operation that the surgeon should be reconciled to lose a little time while searching for

the joint, if he has not hit upon it at first. By cautiously cutting and cutting upon the bone to be removed, as above advised, rather than upon the proximal side of the articulation, no permanent injury is inflicted.



## CHAPTER IX.

### SPECIAL AMPUTATIONS.

#### LOWER EXTREMITY.

*The Foot.*—The framework of the foot is so complex, the articulations so numerous, and the partial amputations which are performed upon it so worthy of attention and repetition, that a study of its skeleton, with a view to the relative position of certain bony prominences and corresponding depressions, will not be misplaced. Carrying the finger from before backwards along the inner border of the foot, the following landmarks will be recognised:— 1st, the large rounded head of the first metatarsal bone; 2nd, an ill-defined ridge or tubercle marking the base of the first metatarsal bone; 3rd, a projection of the internal cuneiform bone, a slight depression between these two latter indicating the position of their articulation; 4th, the tubercle of the scaphoid bone, between which and the internal cuneiform bone is a slight depression marking their articulation; behind the prominent scaphoid bone is the line of its articulation with the head of the

astragalus. Proceeding in a similar manner along the outer margin of the foot is the base of the fifth metatarsal bone, which articulates posteriorly with the cuboid bone, and one finger's breadth behind the base of the fifth metatarsal bone is the line of articulation of the cuboid bone with the calcaneum.

On the dorsal aspect, one finger's breadth in front of the ankle joint, a line drawn across the foot will correspond to the articulations between the astragalus and calcaneum behind, and the scaphoid and cuboid in front.

The postero-anterior arch of the foot, upon which the greater part of the weight of the body is received, has two principal points of support, the heel and the ball of the great toe. If, therefore, either of these be removed, the vault of the arch will be lowered, and its strength and utility be diminished in proportion.

These observations lead me to speak first of amputation of—

*The Toes.*—These members may be amputated *en masse* at the metatarso-phalangeal articulation, or be separated individually in either their continuity or contiguity; but since their functions as prehensile organs cannot be called into play so long as thick-soled boots are worn, the four lesser toes are rendered comparatively useless, and amputation of one or more should be performed either through the first phalange or at the metatarso-phalangeal articulation.

This observation does not apply to the great toe, the smallest portion of the first phalange of which should be carefully husbanded in order that it may assist in bearing its due share of the weight of the body thrown upon the ball of the great toe.

When performing partial amputation of the hand or foot, the blade of the scalpel or knife employed should be very *narrow*, in order that it may be passed readily between bones and through small articulations.

The main vessels may be compressed by the fingers and thumb of an assistant; in the case of the foot, just above the ankle joint, the fingers being employed to press the posterior tibial artery against the posterior surface of the tibia, while the thumb compresses the anterior tibial artery upon the lower end of the tibia in front.

During an operation for the removal of a toe, the adjacent toe or toes should be held aside by a loop of bandage cast over them.

If the plantar surface of the toes be examined, certain transverse markings will be observed; but since most adult toes are more or less deformed, these lines will not much assist in determining the point of articulation between the first and second phalanges, although the second line from before backwards will be often found opposite to the above articulation: in the case of the great toe no perceptible line exists.

On the dorsal surface, excepting the great toe, a small tubercle immediately in front of the articula-

tion, and appertaining to the second phalange when well developed, indicates the line of the articulation. Besides these anatomical aids, the operator should flex and extend the bone to be removed, and even pull upon it, so as if possible to separate the articulating surfaces, and discover with his finger the line of the joint. Excepting the metatarso-phalangeal joint of the great toe, the remaining four are placed deeply in the sole of the foot, a fact to be remembered by the operator, who otherwise will be puzzled to find the articulation; the transverse line on the plantar surface at the junction of a toe with the sole of the foot is much in advance of the articulation, and consequently cannot be taken as a guide to the latter.

For mode of performing partial amputation of toes, see Amputation of Fingers.

*Amputation of Great Toe* (metatarso-phalangeal).—The head of the metatarsal bone is very large, and requires a wide extent of integument to cover it. Not forgetting the above fact, and husbanding the skin accordingly, the operation is similar to that performed at the metatarso-phalangeal articulation of the other toes, either by oval incision or by flap.

By *oval incision*.—Hold the condemned toe with the finger and thumb of the left hand firmly, and commence the incision on the dorsal surface opposite to the joint and in the median line of the toe, carrying it downwards and forwards along one side of the toe to the point of junction of the web with the toe,

then through the transverse line, marking the junction of the toe with the sole, to a corresponding point on the other side, and terminate at the point of commencement of the incision. Divide the extensor tendon, and open the joint on the dorsal surface; sever the lateral ligaments consecutively and carefully with the point of the knife, and also the flexor tendon's sheath and remaining slight attachments.

In removing either the great or little toe, as above described, let the incision on either side of both toes be prolonged to an equal distance.

Avoid plunging the point of the knife into the sole of the foot.




FIG. 72.

The wound and parts exposed in a similar amputation of the second toe are seen in Fig. 72: *a*, the



extensor tendon ; *b*, the head of the metatarsal bone ; *c*, the flexor tendon. *b b*, Fig. 73, shows the linear cicatrix resulting when the edges of the wound have been kept in apposition by suture and by the approximation of the adjacent toes.




FIG. 73.

If sufficient integument cannot be found to cover the head of the metatarsal bone of the great toe, the exposed extremity must be removed either by saw or forceps ; the heads of the remaining four metatarsal bones, being deeply seated in the sole, should not be taken away.

By *flap*.—Hold the toe firmly with the left hand, and with a long narrow-bladed scalpel cut one flap by transfixing the soft parts on one side of the toe from below upwards and backwards, causing the point of the knife to appear on the dorsal surface opposite to the articulation and in the middle line of

the toe. By cutting forwards towards the extremity of the toe and as far as the junction of the web with the toe, taking care to include as much integument as possible, one flap will be formed; now divide the extensor tendon with the point of the knife, and open the joint; pass the knife, point uppermost, across the joint after dividing the lateral ligaments and flexor tendons, and then form the second flap by cutting forwards, as in completing the first flap.

*Toes en masse.*—The toes may be removed together by two incisions—one on the dorsal, the other on the plantar aspect of the foot. Preserve as much integument as possible, to cover the head of the metatarsal bone of the great toe.




FIG. 74.




FIG. 75.

Holding the toes in the left hand, commence and

terminate the dorsal incision either on the outer or inner border of the foot, as much in front of the metatarso-phalangeal articulation as is consistent with cutting a regular margin to the flap (as in Fig. 74, *d*) ; now mark out the flap on the plantar surface by carrying an incision between the points already determined by the dorsal incision, along the lines of junction of the toes with the sole ; divide the extensor tendons, traverse the joints severally and in order, and complete the operation by division of the flexor tendons. Fig. 75 shows the result of such an operation.

*Metatarsal Bone, partial or entire.*—Commence the incision on the dorsal surface at the intended point




FIG. 76.

of section, or of disarticulation of the bone (Fig. 76, *a*) ; carry it towards and about the toe (*b, c*), as

already described for the removal of the toe only, and terminate the incision at *a*. Holding the long narrow-bladed knife parallel to the long axis of the bone to be removed, carefully separate the muscular attachments, first on one side and then on the other side, and then, to complete the section of the flexor tendons, cautiously pass the point and part of the blade of the knife under the bone, and cause it to protrude on one side, while the remaining portion of the blade with the handle of the knife is on the other side, thus giving it an oblique direction; by cutting forward towards the toe, the division of soft parts may be readily completed. Use the condemned toe as a lever, whilst the ligaments of the tarso-metatarsal articulation are being divided. Should the operator intend only to remove the anterior portion of a metatarsal bone, the bone-forceps, applied on the dorsal surface, with a direction downwards and forwards, cutting the bone obliquely, will suffice. The wound thus made is shown in Fig. 72, and the parts exposed are, *d*, extensor tendon; *e*, fibres of flexor brevis digitorum; *f*, part of cuboid bone; *g*, the divided interossei muscles; *h*, the flexor tendons. A linear cicatrix (Fig. 73, *a*, *a*, *c*) is the result.

*Metatarsal Bone of Great Toe.*—Observe that the direction of the line of articulation of the first metatarsal bone with the internal cuneiform bone is from within, downwards and outwards towards the head of

the fifth metatarsal bone ; that the joint is in advance of that of the second metatarsal bone, and quite distinct from it ; that the dorsalis pedis artery dips into the sole of the foot close to the outer side of the joint. To remove this bone with the great toe, let an assistant draw the integument of the dorsum of the foot towards the ankle-joint ; the operator should then commence his incision on the dorsal surface, and opposite to the articulation, carrying it downwards and forwards to one side of the toe, as far as the web, *a*, around this former, as already described, and back to the point at which it was commenced ; thus a  $\Delta$ -shaped portion of integument is included (Fig. 77).



FIG. 77.

(Besides the above incision, a second may be made at the apex of the former and at a right angle to it, opposite to the metatarso-cuneiform joint, and extending down on the inside and towards the sole of the foot to the extent of an inch. By this means a flap is formed, and the above articulation is more readily exposed.) Carefully separate the soft parts from the metatarsal and sesamoid bones ; divide the



ligaments of the articulation without either carrying the knife up between the base of the second metatarsal bone and internal cuneiform bone, or wounding the adjacent dorsalis pedis artery; and amputa-




FIG. 78.

tion is accomplished. Fig. 78 shows the wound and parts interested: *a*, the extensor tendon; *b*, internal cuneiform bone; *c*, the dorsalis pedis artery, cut



FIG. 79.

across; *d*, *e*, *f*, *g*, *h*, mark certain muscles which have been necessarily divided. Fig. 79, *a a a*, shows a linear cicatrix resulting.

*Fifth Metatarsal Bone.*—This bone may be satisfactorily removed also by the oval incision, including an elongated triangular portion of integument with rounded corners. The tuberosity of this bone, to which is attached the tendon of the peroneus brevis muscle, the oblique direction of the line of articulation with the cuboid bone (from without, downwards and inwards towards the head of the first metatarsal bone), render it necessary to commence the incision a line or two above the articulation, in order that disarticulation may be readily effected. The



FIG. 80.

course and extent of incisions are indicated at Fig. 80, *a*, *b*, *c*. A linear cicatrix is the result, as in Fig. 79.

By this *oval* method or modification of it, as occasion requires, two or more metatarsal bones, with their corresponding toes, may be removed.

*Metatarsal Bones en masse.*—These bones may be amputated either in their continuity or in their contiguity.

*Tarso-metatarsal Amputation (Lisfranc).*—On the

inner side of the foot a linear depression between the base of the first metatarsal bone and the internal cuneiform bone marks the line of articulation between the two. On the outer side of the foot the tuberosity of the fifth metatarsal bone will indicate sufficiently well the position of the joint between this and the cuboid bone. The base of the second metatarsal bone is wedged between the internal cuneiform bone on the inside and the external cuneiform bone on the outside, its line of articulation with the middle cuneiform bone being about half an inch in the rear of the anterior articular surface of the internal cuneiform bone, and one quarter of an inch posterior to the anterior articular surface of the external cuneiform bone. (Fig. 81.) When performing the operation




FIG. 81.

about to be described, the points of commencement and of termination, and the direction of three lines

of articulation, must be borne in mind. On the outside, the line of articulation of the three external metatarsal bones with the cuboid and external cuneiform bones has a direction from behind forwards and inwards; on the inside, the line of articulation between the first metatarsal bone and the internal cuneiform bone has a direction from behind forwards and outwards; in the middle, the articulation of the second metatarsal bone with those adjacent forms three sides of a square, of which two are parallel and look forwards and backwards, and the third from side to side.

To operate on the *right* foot it will be convenient to hold the member with the left hand placed upon the dorsum of the foot, the point of the forefinger being placed upon the base of the fifth metatarsal bone, and the point of the thumb just in front of the articulation between the internal cuneiform bone and first metatarsal bone, and on the side of the base of the latter. Commence the incision on the outer border of the foot, just behind the point of the index finger; carry it across the dorsum, with a slight convexity forwards (see Fig. 74, *c*), and terminate it on the inner border of the foot, behind the point of the thumb. This first cut should divide integuments only, and when these are slightly retracted a second incision across the foot should divide all soft parts down to the bones and on a level with the edge of the divided and retracted skin. Search now for the external *line of articulation* already mentioned,

and having opened the joint of the fifth metatarsal bone with the cuboid bone, let the knife, almost *sponte*, follow the *line* to its termination on the outside of the second metatarsal bone ; open next, with the heel of the knife, the internal metatarso-cuneiform joint ; and lastly, grasping the handle of the knife (point directed downwards and backwards, Fig. 81), cautiously introduce the point between the first and second metatarsal bones, and then between the second and third metatarsal bones, and having fixed it on an imaginary fulcrum or pivot, carry the handle and blade backwards so as to divide the ligaments which unite the sides of the base of the second metatarsal bone to those adjacent ; now, by cutting with the point of the knife upon the dorsum of the second metatarsal bone, the remaining dorsal ligament uniting it to the middle cuneiform bone will be severed, and if the foot be used as a lever and be depressed by the hand of the surgeon, the articulations already opened will be freely exposed to view, and the most difficult part of the operation be effected. Without injuring the sole, divide the plantar ligaments and tendon of the peroneus longus muscle attached to the base of the first metatarsal bone.

When dividing the above parts it will be well, almost imperceptibly to commence cutting the flap by nicking the integument on the outside with the point of the knife, and on the inside with the heel of the knife. (It is difficult to describe this manœuvre on paper ; the object is to avoid an ugly



angle on either side by rounding off in a forward direction the original transverse cut on the dorsum.)

A flap is to be made from the sole, and to do this place the knife across the wound, and the blade flat on the raw surface, and cut forwards close to the under surface of the metatarsal bones, and as far as the roots of the toes, not forgetting the position of the sesamoid bones, which should also be removed; now measure the raw surface of the sole by bringing it up against the exposed cuneiform and cuboid bones, and having determined upon the requisite length of flap (allowing for retraction) which will cover the bones, grasp the condemned toes and metatarsal bones with the left hand, and holding the knife, point downwards and forwards, almost perpendicularly to the raw surface of the sole, cut away the toes and leave the flap. The flap should be longer on the inner than on the outer side of the foot, because the internal cuneiform bone is deeper than the cuboid; the angles of the flap should be slightly rounded at the same time that the toes are cut away, and its anterior margin be cut somewhat obliquely from above downwards and forwards.

To operate on the *left* foot it will be found convenient to take the sole of the foot into the palm of the hand, using the points of the finger and thumb as before directed. The steps of the operation should be performed in the above order, although one or more individual steps may be reversed. Fig. 82 shows the result of the operation on the left foot.

*Medio-tarsal Amputation* (Chopart).—In this operation the whole of the foot anterior to the astragalus and os calcis is removed. The landmarks are, on the outer side of the foot, a point one finger's breadth behind the base of the fifth metatarsal bone, marking the line of articulation between the cuboid bone and os calcis; on the inner side, a point immediately posterior to the tubercle of the scaphoid bone, indicating the line of articulation between the astragalus and scaphoid bone: on the dorsum of the foot, a line at




FIG. 82.

the distance of one finger's breadth in front of the ankle-joint will indicate the line of articulation which is to be traversed by the knife.

To operate on the *left* foot, hold the member with the sole in the palm of the left hand, and let the point of the forefinger rest upon the outer border of the foot just behind the base of the fifth metatarsal

bone, while the point of the thumb rests upon the tubercle of the scaphoid bone on the inner side of the foot; behind these two points or landmarks the first incision is to be begun and to be terminated. Commence the incision on the inner side of the foot, with a small amputating-knife; carry it across the dorsum (see Fig. 74 *b*), and terminate it at the point indicated, dividing integument only, and with a slight convexity forwards. Now divide all intervening structures down to the bones, and on a level with the retracted skin; open the articulations on the dorsal surface, depressing the foot with some force, so as to assist in exposing to view the articular surfaces of the astragalus and calcaneum.

[*Caution.*—The articulation between the astragalus and scaphoid bone is generally more readily found, and will probably be opened first; and on carrying the knife outwards to open the articulation between the os calcis and cuboid bone, the point of the knife is very liable to slip back upon the upper surface of the calcaneum, just external to the neck of the astragalus, and of course posterior to the calcaneo-cuboid joint. When superintending operations in Paris, I have repeatedly seen this accident happen to students; and unless the operator be aware of the possibility of such an occurrence, he will be very much puzzled to extricate himself. This accident is only liable to happen when operating on the left foot, unless the operator use the knife with his left hand when operating upon the right foot. The black triangular

space above the extremity of the os calcis in Fig. 83, is the locality indicated.]

Sever the plantar ligaments without puncturing the sole, and divide the tendon of the peroneus longus muscle, seen crossing the foot from without inwards. Cut the flap in the manner described in the tarso-metatarsal amputation. The head of the astragalus may or may not be removed at pleasure with the saw.

Fig. 83 shows the result of this operation on the left foot.

To operate on the *right* foot, hold it with the left hand placed upon the dorsum of the condemned member; and although individual steps of the operation will be reversed, it is not necessary to recapitulate the instructions.




FIG. 83.

*Another method* (Sedillot).—It is here proposed to obtain a flap from the inner side of the foot.

To operate on the right foot, and bearing in mind the situation of the various joints interested, commence the incision at the outer border of the foot, two fingers' breadth in front of the external ankle, and carry it to the centre of the dorsum, then turn abruptly forwards and inwards, to the inner border of the foot, as far as the central point of the first metatarsal bone; now continue the incision obliquely backwards and outwards across the plantar surface to the point of commencement; dissect back the

internal flap, keeping the knife close to the bones, to the astragalo-scaploid joint; open this and also the calcaneo-cuboid articulation, and separate the condemned portion of foot from the remaining attachment of the sole. By this means it will be seen (Fig. 84) that a flap, *c*, is formed from the inner




FIG. 84.

side of the foot: *a* is the astragalus, from which the head has been removed; *b* is the calcaneum.

To operate on the *left* foot, it will be readily understood that some of the steps will be conveniently reversed.

A modification of Chopart consists in leaving the scaphoid, as well as the astragalus and calcaneum, to the use of the patient: the flap must be cut in due proportion.

*Tibio-tarsal Amputation* (Syme).—This operation consists in the removal of the whole foot, and of the malleoli and inferior articular surface of the tibia. Two incisions are made, in such a manner as to meet



each other at a right angle. The foot being at a right angle with the leg, one incision is to be marked out, as it were, through integuments only, in front of the ankle-joint, extending from one malleolus to the other. (See Fig. 74, *a*.) The second is to be begun at one of the former: if on the inner side, a finger's breadth *below* the apex of the internal malleolus; if on the outer side, just in *front* of the external malleolus,—because the latter being on a plane posterior and inferior to the former, the points of commencement and of termination of the second incision would, if begun at the *apex* of *each* malleolus, not be upon the same plane. Commence then the second incision at one of the above points, and carry it downwards to one border of the sole, now across the sole to the other border, and then upwards to join one point of termination of the first or anterior incision, dividing all structures down to the bone. This cut is at a right angle to the sole of the foot, the anterior part of the foot being, as it were, isolated by a rectangular incision. The leg must now be supported at a convenient height, and the foot be firmly held at a right angle to the leg, while the operator effects the most difficult part of the operation, *i.e.*, the separation of the integuments of the heel from the inferior and posterior surfaces of the posterior portion of the os calcis. To do this readily, he must not forget the position of the tubercles on the inferior surface of the os calcis, and should be satisfied, at this point, with dissecting

back the integument only, without including any portion of the plantar fascia in the flap. Should the surgeon cut down to the bone in front of the tubercles, dividing plantar fascia and muscles, he will experience difficulty in dissecting back the heel-flap, because the edge of the knife will be liable to come into contact with the anterior surface of these tubercles, and so the operation will be prolonged. To avoid this, should the heel be prominent, he may direct his incision a little backwards.

Place the point of the left thumb in the wound, and cautiously cutting upon the bone, while the soft parts are protected by the thumb-nail, reflect them from all parts of the os calcis, and as high behind as the attachment of the tendo Achillis, which is also to be divided at this moment. While separating the soft parts from the *inner* side, especial care must be taken to keep the edge of the knife *close* to the bone (beneath the fleshy head of the flexor accessorius muscle) lest the plantar vessels be wounded above the original point of section, and the vitality of the heel-flap be endangered. The flap completed, all intervening structures on the dorsum of the foot may be cut through to the ankle-joint at the margin of the already retracted skin, and the superior articular surface of the astragalus being recognised, continue the disarticulation of the foot by a careful division of the external and internal lateral ligaments with the knife introduced from above between the sides of the astragalus and the malleoli; sever all posterior attachments and also any tendons still uncut, and

lastly, any remaining muscular or other adhesion to the inner side of the os calcis, allowing the knife to follow the curve of the sustentaculum tali. The foot is now separated, and as soon as the soft parts have been dissected up so as to expose the malleoli fully, the saw is to be applied, and sufficient bone removed to include the mere articular surface of the tibia, together with the former.

*Caution.*—The neck of the astragalus must not be mistaken for the articular surface.

Fig. 85 shows the result of the operation: *a*, the tibia; *b*, the fibula; *c*, the hollow of the flap, whence the tubercle of the calcis has been removed; *d*, the extremities of the divided plantar arteries.




FIG. 85.

The skin at the back of the tendo Achillis is thin, and is consequently very liable to be cut through, and a “button-hole” formed during the dissection of the flap. This aperture is often of service, allowing exit to secretions during the process of healing, which would otherwise lodge injuriously in the hollow flap; but since it is not one step in the operation, it is to be avoided.\* The heel-flap is now to be brought up into apposition with the anterior in-

\* In the two last cases operated upon, the author has punctured the heel-flap, and inserted a piece of drainage tube, apparently with advantage.

cision, and be so maintained by points of suture, as in Fig. 86.



FIG. 86.

*Tibio-tarsal Amputation (Pirogoff).—*

Two incisions similar to those recommended in Syme's operation are to be made as above described. Without opening the ankle-joint, the malleoli and front of the tibia immediately above the articulation are to be carefully cleared of soft parts, and then these latter being held aside and protected, the saw is to be applied, and the tibia and fibula are to be severed as in the former operation. This done, a few touches of the knife will lay bare the upper surface of the calcaneum in front of the tendo Achillis, and behind the astragalus. Here the saw is to be again applied as near to the insertion of the tendon as possible, and with the blade held obliquely from above, downwards and forwards, the os calcis is to be severed, the saw of course following the line of the incision through the soft parts. In this way a triangular piece of bone, apex upwards, is left in the heel-flap instead of a square piece, as would be the case if the saw were not worked obliquely as above indicated. The object of this manoeuvre is to favour the ready coaptation of the sawn surface of the os calcis to the cut surface of the tibia when the flap is brought up and adjusted by suture. If sawn otherwise, the tendo Achillis must be divided subcu-

taneously to remedy the defect, or a piece of os calcis or a wedge-shaped piece of tibia must be at once removed. Either of these methods complicates the operation, and the error should be avoided. Under the most careful dressing, the heel flap has a tendency by its own weight to fall back and to separate the bony surfaces, and this fact must be constantly borne in mind during the after-treatment, lest the piece of os calcis, getting more or less behind the level of the tibia, become permanently fixed there.

The operation completed, the flap must be adjusted and be maintained by suture. Should there be any strain on this latter, the leg should be kept somewhat flexed upon the thigh for a few days.




FIG. 87.



FIG. 88.

Fig. 87 shows the heel-flap with the posterior portion of os calcis, *a*, *in situ*.

Fig. 88 shows the appearance of the stump three months after Pirogoff's operation, taken from a



patient under the care of Mr. Maunder in the London Hospital.

Ten years have now elapsed, and the patient has a most useful stump.

*Tibio-tarsal Amputation* (Jules Roux).—It is here proposed to obtain a flap principally from the inner side of the foot.

Commence the incision at the back of the heel, just at the point of junction of the tendo Achillis with the os calcis (Fig. 89, *a*); carry it forwards on the outside of the foot immediately below the external malleolus, then turn inwards towards the inner border of the foot with a slight convexity forwards, passing from one to two fingers' breadth in front of the ankle-joint and continue the incision round the inner border of the foot (*b*) and in a direction obliquely backwards along the sole of the foot, and terminate at the point of commencement, *a*.




FIG. 89.

Open the ankle-joint in front; disarticulate and sever first all external attachments, as well as that of the tendo Achillis, then carefully separate the soft parts on the inner side of the foot from above downwards, by keeping the knife close to the bone, so as to avoid wounding the posterior tibial artery and its branches. Remove the malleoli with a thin layer of tibia, including the

whole inferior articular surface of it. The flap should be adjusted as usual.

The figure also shows the appearance of the foot when separated from the flap and leg ; from *a* to *b* a portion only of the line of incision is seen ; *c* is the astragalus.

The foot and malleoli may be removed together, without previously opening the ankle-joint.

#### COMPARATIVE VALUE OF THE ABOVE TRANSVERSE AMPUTATIONS OF THE FOOT.

*Amputation of Toes en masse.*—By this, organs comparatively useless are alone removed, and by leaving the heads of the metatarsal bones, the antero-posterior arch of the foot is not shortened.

*Tarso-metatarsal Amputation.*—The antero-posterior arch of the foot is here abbreviated by the length of the metatarsal bones, but should be preferred, when practicable, to the next.

*Medio-tarsal Amputation.*—Of the above described amputations, this one is the least desirable, as may be understood by a reference to the following diagram.

A well-formed foot represents two arches, of which the more important is the postero-anterior, indicated in Fig. 90 by the arc *F E G*, and of which the posterior extremity, *F*, is the heel, and the anterior extremity, *G*, is the ball of the great toe. The key of

this arch is shown by the perpendicular line let fall at E. If, therefore, any portion, and especially the




FIG. 90.

anterior half of the arch from E to G be cut away, it is evident that the weight of the body, falling perpendicularly in the direction of A B, and transmitted by the tibia, *a*, to the astragalus, *b*, which latter articulates with and rests upon the anterior part of the os calcis, *c*, and has a direction from above downwards, forwards, and inwards *c* D, will bring the anterior part of the astragalus and of the os calcis towards the ground, and tilt the heel up behind. In the natural condition of the foot, the weight of the body is received upon the astragalus, and from this is distributed to the remaining bones of the tarsus and to the metatarsus; but when these

latter are removed by operation, and the weight of the body is allowed to fall upon the stump, the astragalus is liable to become dislodged in a forward direction from the os calcis, and to cause disorganization of the joint, bones, and integuments, which are unduly pressed upon. To prevent this, Mr. Delagarde proposes to endeavour to get union of the tendon of the tibialis anticus to the wound by fixing its free end there with a hare-lip pin.

*Tibio-tarsal Amputation* (Syme).—By this method the foot and malleoli, with a thin layer of the inferior extremity of the tibia, are alone removed. When practicable, it should be preferred to amputation higher up through the leg, because a long stump is preserved, and the flap taken from the heel forms a good protection to the bones and a natural support for the body. It is preferable to Chopart, because certain bones which are disposed to caries, either idiopathically or in consequence of their altered anatomical relations, are removed. On the other hand, the flap is formed with some difficulty, and being hollow and composed of lowly-organized tissues, secretions are liable to lodge in the pouch, repair is often slow, and sloughing occasionally occurs if the surgeon be ignorant of the principles of the operation.

*Pirogoff's method*.—A desirable operation, because the limb is shortened less than by Syme's mode. It is applicable to cases of injury, rather than for the removal of carious bone; because, in the latter

instance, the original disease is liable to recur in the portion of os calcis left in the stump. It is also easy of performance.

*Roux's method.*—Theoretically a desirable mode. The flap is moderately fleshy and well nourished, and a ready exit is afforded to all secretions.

All the above operations on the foot are open to the objection that pus is liable to travel along the sheaths of the tendons, and delay the cure. To obviate this, cut the tendons long, so that when the muscles contract the sheaths shall not be left empty.

#### AMPUTATION OF THE LEG.

The leg may be amputated at any point in its continuity. Two points are preferred—either the junction of the middle and lower third, or the junction of the upper and middle third. To the former an artificial foot, to the latter an artificial leg, may be adapted.

Stand on the outside to operate upon the right leg, on the inside to amputate the left limb.

*Lower Third, by flap* (a short anterior and long posterior).—Assistants and patient being in position, the operator should hold the leg with his left hand, placing the points of the forefinger and thumb respectively upon the fibula and posterior margin of the tibia, not only to serve as guides to indicate the spot at which the bones are to be severed, but also to determine the points of commencement and of termi-



nation of the incision, or of entrance and exit of the point of the knife when transfixing the limb. Cut the short anterior flap by commencing the incision on the further side of the leg, just behind the point of the forefinger, with a double-edged knife, and carry the instrument across the front of the leg to the point of the thumb, in such a manner that a semilunar flap is marked out with convexity looking forwards. This done, enter the point of the knife behind the bones, transfix the limb on a level with the points of the thumb and forefinger, and cut the long posterior flap in the usual way. Dissect up the anterior flap to the requisite level, sweep the bones circularly at the bases of the flaps, and divide the interosseous muscles and membrane by passing the knife between the bones. The application of the saw completes the operation.

Should the crest of the tibia be sharp, the prominent angle may be removed by the saw.

*Teale's method* (by a long and a short rectangular flap) is somewhat the reverse of the above, and since it is applicable to this part of the leg, may be described at once.

The operation consists in cutting a long anterior flap (except in the case of the forearm, when the long flap is posterior), and a short posterior flap, and in the following manner and proportions. The united length of the two flaps should be equivalent to about two-thirds of the circumference of the limb at the point of division of the bone, while the short

posterior flap should measure only one-fourth of the length of the anterior flap ; also, the breadth of the anterior flap should be equal to one-half of the circumference of the limb. To form the anterior flap, make two parallel and longitudinal incisions through integument only, of the requisite length, and in such position, that the main vessels shall be left in the posterior flap. At the distal extremities of the above incisions, make a third and transverse cut to join them at right angles, and dividing the tissues down to the bone. Dissect up now this flap from off the bone, and form the posterior flap by a semicircular sweep of the knife through the soft parts to the bone ; separate this latter from the bone to the required height, and lastly sever the bone or bones as usual. By bringing the long flap into contact with the posterior flap, and so maintaining them by suture, the end of the bone will soon be found to occupy a position corresponding to the middle of the long flap.

Where two bones are interested, as in the leg and forearm, the interosseous muscles must be carefully dissected off the interosseous membrane, so as to form a part of the thickness of the flaps. This dissection renders the operation somewhat tedious, but no such obstacle is of course met with in the thigh or arm.

In the case of the lower part of the leg, Mr. Teale desires to advise the operator to be careful not to wound the anterior tibial artery at the base of the flap, lest sloughing of the latter ensue. This acci-

dent is best avoided by using the knife in dissecting up the long flap very little more than to detach the skin laterally and to divide the aponeurosis or deep fascia longitudinally at its attachment to the tibia on one side, and to the fibula on the other; the interosseous muscles beneath may then be separated upwards from the tibia, interosseous membrane and fibula by the finger, with very little assistance from the knife.




FIG. 91.

Fig. 91 delineates the length and proportion of the flaps to be formed at the lower part of the leg.

Fig. 92 shows the flaps cut according to the above proportions.



FIG. 92.

Fig. 93 exhibits the appearance of the stump when the flaps have been adjusted immediately after the operation.

Fig. 94 represents the stump after cicatrization has taken place.

Mr. Teale informs me that his experience since the publication of his work on the *rectangular flap operation* has fully substantiated the opinions therein expressed.




FIG. 93.

The chief advantage ascribed to this mode over others, consists in the fact that stumps resulting are much more serviceable to the owner than stumps formed in any other way. The end of the bone is at a distance from the cicatrix, and being protected by a moveable covering of soft parts, great pressure can be borne without inconvenience; whereas, by the



ordinary methods of amputation, the cicatrix is said to be generally adherent to the end of the bone, and pressure upon it is unendurable. All the more important vessels and nerves are also at a distance from the end of the bone.

*Caution.*—When amputation by rectangular flaps is performed on a conical limb, such as the leg, the long flap must be cut *wide* at its free extremity to allow for lateral shrinking, or it will be too narrow for accurate adaptation to the short flap.



FIG. 94.

*Upper Third, by flap* (a long posterior and short

anterior flap).—The steps of this operation correspond to those of the amputation at *lower third*. Place the points of the forefinger and thumb respectively upon the posterior margin of the tibia and fibula, to indicate the intended breadth of the flaps, and also the spot at which the bones are to be sawn across. Mark out the anterior flap first, beginning on the distal side of the limb behind the forefinger, and terminating on the proximal side behind the point of the thumb. This flap should be one-fourth of the length of the posterior flap, and with convexity looking towards the foot. Transfix the limb behind the




FIG. 95.

bones, and cut the long posterior flap (Fig. 95). Divide interosseous parts, &c., &c. The sharp angle

of tibia formed by the junction of the sawn surface with the natural crest of the bone should be removed by the saw, either before or after that the bones have been divided.

The assistant in charge of the distal portion of the leg should rotate the limb inwards, so as to bring the fibula forwards. By this step the operator will be less likely to commit the error of passing his knife between, instead of behind both bones when about to form the posterior flap.

By *double flap* (Luke).—By this method two flaps of equal length are cut; the anterior from skin to bone after the manner indicated at Fig. 95; the posterior by transfixion.

By *long external and short internal flap* (Sedillot).—The assistant in charge of the distal portion of the limb should extend the foot, and also flex the leg to an angle of about  $45^{\circ}$ , so as to relax the muscle of the calf. Cut first the long external flap by transfixion, entering a long, narrow, single-edged knife on the front of the leg at a point midway between the crest of the tibia and fibula, and causing it to reappear in the calf of the leg after it has traversed the limb, close to, but external to the fibula, and taking care to include as much of the integument and of the muscle of the calf as possible. To aid in forming a broad flap, the operator's left hand should seize and elevate the soft parts, so as to bring them within range of the knife (Fig. 96). The leg is here shown insufficiently flexed.

A well-rounded flap, in the direction of the dotted line, is to be cut out of the side of the leg, while a short anterior flap of integument must be formed on




FIG. 96.

the inside in the usual manner; and when this latter has been dissected up to the requisite height, the operation may be completed as already described above.

In whatever manner amputation at the upper third of the leg may be performed, the bones will be conveniently sawn across at the distance of three fingers' breadth below the tubercle of the tibia.

Although amputation may be performed at any

point in the continuity of the bones of the leg, still, as a rule, only one locality may be strictly looked upon as the *point of election*, and that the *upper third*. The operation is rarely requisite in the lower third, because one or other form of amputation at the ankle-joint should be preferred; and amputation ought not to be performed in the middle of the leg, unless the surgeon can insure to his patient a sound stump, and one capable of bearing upon its face a good share of the weight of the body.




FIG. 97.

*Cutaneous Flaps.*—The leg may be amputated at any point by flaps formed of skin and subcutaneous tissue only (Fig. 97), whether antero-posterior or lateral.



## AMPUTATION OF THE THIGH.

The thigh may be amputated at any point, either of its continuity or contiguity.

*Lower Third.*—This is the *point of election*, because through it amputation will be less severe than it would be if performed near the trunk; also, a useful stump is preserved to the patient.

In this locality, muscles on the posterior and internal aspects of the limb have their superior attachments at the pelvis, and when divided, will retract towards that point of origin, and in doing so, are liable to carry the integument with them, to lay bare the divided end of the femur, and to induce a conical and useless stump. To avoid this accident, amputation either by circular incision, or by a modified flap operation, must be performed.

By *circular incision*. — Assistants and subject being in position, the operator will find it convenient to stand on the outside to operate on either thigh. Divide first by circular sweep the integuments and deep fascia as near to the patella as possible. This done, the assistant who embraces with both hands the proximal portion of the thigh, should make equable traction upon the integuments, while the surgeon divides at the required points any resisting adhesion, such for example as those existing opposite to the internal and external intermuscular septa. The integuments having yielded to the same extent

throughout, the superficial set of muscles should be divided by a circular sweep, and in such a manner that the muscles at the back of the thigh are left longer than those in front, in order that all may be upon the same level when retraction has taken place. This effected, the assistant again retracts the divided tissues as much as possible, and now the operator, holding the knife with its edge looking upwards and towards the bone, severs the deep layer of muscles and all intervening structures down to the bone and close to the edge of the already retracted soft parts. The saw completes the separation.

If now the integuments and muscles be allowed to fall over the bone, and their relative positions be examined, it will be seen that the bone is completely embedded in muscle, and forms the apex of a hollow cone, the base of which is represented by the cut margin of integument (Fig. 71).

By *flap*.—In the lower third of the thigh the ordinary double flap operation, whether antero-posterior or lateral, is inadmissible for reasons above stated. If adopted, the flaps should be cut very long, to allow for retraction of the hamstring muscles.

The method by flaps of *integument only* may be adopted. Having determined the point at which the bone is to be severed, two semilunar flaps of integument, with convexity towards the knee, are to be cut and dissected up to the requisite height; if antero-posterior flaps be preferred, a portion of the muscular structures on the front of the thigh may

also be dissected up and be included in the flap: no muscular structure is to be left attached to the posterior flap, but the muscles on the back of the thigh should be cut *long*, and be carefully separated from the bone as high up as it may be necessary to apply the saw.

By leaving the hamstring muscles long and hanging into the wound unattached to the skin, the former can become retracted without carrying the skin with them.

In this instance, as in all cases, the knife should be held with its edge directed upwards and towards the bone when muscular structures are divided by a circular sweep.

By *long anterior flap* (Sedillot).—Cut a long semi-lunar flap, equal both in length and in breadth at its free end to two-thirds of the circumference of the limb, at the intended point of section of the bone; dissect up this flap composed of integument and muscular structure, but not including the main vessels; divide the parts on the posterior aspect of the limb with one sweep down to the bone, and on a level with the base of the long flap. The application of the saw completes the operation.

*Teale's method* (page 211) is equally applicable to this region, and is similar in principle to the above. In either case this long flap may be taken from the anterior aspect of the limb as low down as the tubercle of the tibia, and, except perhaps in the old subject, without danger of sloughing, provided that

its under surface be not *scored* by the knife during the operation, nor unduly compressed afterwards.

The operation as executed at the lower third of the thigh is indicated in the following illustrations.

Fig. 98 shows the dotted lines, indicating the position and relative extent of the incisions.




FIG. 98.

Fig. 99 illustrates the flaps formed according to the above relative proportions.

Fig. 100 gives the appearance of the stump when the flaps have been adjusted immediately after the operation.




FIG. 99.

Fig. 101 shows the condition of the stump after cicatrization.

*Through the Condyles.*—(a) By long posterior flap and short anterior flap.—By this means a covering to the end of the bone is obtained from the posterior region of the leg, and the femur may be sawn across just above the condyles.



Cut first a short anterior semilunar flap in front of the knee and turn it up; open the knee-joint by dividing transversely the insertion of the quadriceps femoris into the patella; flex the leg and traverse the joint, and after having severed the ligaments,




FIG. 100.

cautiously insinuate the knife behind the tibia and fibula, and cut a long posterior flap out of the calf of the leg. Sweep circularly the femur just above the condyles, and remove these latter with the saw.

In this way a long stump is preserved, and the end of the bone is also well covered, but the method is not to be preferred.

When large nerves are visible on the face of a flap, they should be cut short.



FIG. 101.

I saw an excellent stump resulting from this mode in Mercer's Hospital, Dublin, under the care of Mr. Butcher.

(b) *By a long anterior and short posterior flap.*—A well-rounded flap similar to that made in excision of the knee by semilunar incision is to be marked out; and then a second, but shorter, semilunar flap is to be cut, of integument only, at the back of the knee, and to be dissected up as high as the intended point of section of the bone. Then the anterior flap is to be raised in a similar manner and to the

same level. With a circular sweep of the knife immediately above the patella, sever all the soft structures down to the bone, manœuvring, at the same time, to cut the hamstring tendons as long as possible. The saw applied, the operation is completed by cutting across the femur just above the condyles.

*Middle and Upper Thirds.*—In these regions the muscles are severed at a shorter distance from their superior attachments than in the *lower third*, and consequently the amount of retraction will be much less in the former than in the latter case.

Amputation by the ordinary double flap by transfixion, is applicable here (see page 165).

*Knee-joint.*—*By long anterior and short posterior flaps.*—Unless contra-indicated, both patella and the articular cartilage of the femur may be preserved. Should the surgeon so determine, he must bear in mind how large a surface of bone has to be covered in; and to prevent exposure of this during the process of healing, the extremities of his incisions when making his flaps should scarcely reach the line of articulation between the tibia and femur; also, the anterior flap must be very broad, and should include the integument, which covers more than one-half the circumference of the limb.

Proceeding, then, to mark out the anterior flap, by begining on one side of the knee towards the popliteal space, he passes the knife down one side and then across the front of the leg two-and-a-half inches below the tubercle of the tibia, and terminates the

incision also towards the popliteal space, opposite the spot where it was begun. A shorter posterior cutaneous flap is now to be dissected up, opposite to the line of the joint. This done, the anterior flap is to be carefully lifted, without scoring its deeper surface, only as far as the line of its base, and then the skin about the knee being retracted by both hands of an assistant, the knife must traverse the articulation separating the leg from the thigh. In doing this, care should be taken to avoid injury to the articular cartilage, and the synovial sac should be disturbed as little as possible. The inter-articular fibro-cartilages ought to come away on the tibia. The operator may prefer to cut the posterior flap from within, outwards. A narrow-bladed knife should be used.

If the patella and articular cartilage are to be removed, the bases of the flaps must be higher than the point indicated above, and the cartilage will be best removed by the bow-saw applied so as to follow the curve of the condyles, cutting it away with a layer of bone.

If from any cause there is insufficient flap, an equivalent inch of bone may be removed by sawing off the portions of the condyles which project backwards.

*Caution.*—The operator must be always aware of the importance of preserving ample covering for large processes of bone, such as the condyles of the femur, the head of a metacarpal bone, or of the metatarsal bone of the great-toe, intended to form the end

of a stump. The tendency of skin to become retracted and contracted, longitudinally and laterally, partly by muscular action, partly by its own inherent quality, is in some instances almost beyond credit. The soft parts at the back of the thigh are specially prone to longitudinal retraction.




FIG. 102.

The woodcut (Fig. 102) represents the stump of a female patient, over fifty years of age, who was submitted to this amputation by the author. It will support the weight of the *whole* body without causing the least discomfort. The cicatrix lies behind the condyles and is not exposed to pressure.

*Hip-joint.*—Various modes have been adopted for disarticulation at this joint; and of these, that by anterior flap is preferred.

By *anterior flap*.—The buttocks of the subject should be well advanced upon the edge of a table; the trunk must be supported lest it slip forwards;



the sound limb must be cared for, and the condemned limb be supported at the knee and ankle by a strong assistant, who must be prepared to abduct and rotate the limb at the proper time. Either the abdominal aorta is to be compressed against the spine by an appropriate tourniquet, or the femoral artery must be commanded in the groin against the horizontal ramus of the pubis by the fingers of an assistant, who is also prepared to ligature the main vessels so soon as the flap be cut.

It will be convenient for the surgeon to stand on the outside to operate upon the left limb, on the inside to amputate the right limb. On the outside, two bony prominences will be worthy of note,—the antero-superior spine of the ilium and the trochanter major of the femur; on the inside of the thigh, two other prominences may be noticed,—the tuber ischii and the round tendon of the adductor longus muscle. Standing, then, on the outside, the surgeon, armed with a long knife, enters the point of it midway between the antero-superior spine of the ilium and the great trochanter of the femur, and causes it to make its appearance on the inside between the tuber ischii and tendon of the adductor longus muscle, avoiding to wound either the sound limb or scrotum, but causing the knife to pass close in front of the capsule of the joint, so as to avoid puncturing the femoral vessels. The soft parts in front of the thigh must now be grasped by the operator's left hand, so as to bring as much integument as

possible within range of the knife, while a broad, long (half the length of the thigh), and well-rounded flap, be cut from above downwards. This flap is at once seized, turned up, and assistants may proceed to ligature the larger vessels, while the operator effects disarticulation. To open the joint is difficult with a long knife, and must be done cautiously, lest the point slip into dangerous regions. The capsule bared, attack it on the anterior and inner surfaces; and as soon as it is opened, the assistant should abduct and rotate the limb outwards, so as to cause the head of the bone to protrude, and perhaps rupture the round ligament also; if not ruptured, it must be cut. During this manœuvre, air will be heard to enter the articulation. Divide now the posterior portion of the capsular ligament, and (caution) do not forget the position of the trochanter major, *behind* which the heel of the knife must be placed, while the blade is in front of the acetabulum and the point projects as before. Complete the separation of the limb by dividing all the structures forming the back of the thigh perpendicularly. By this means the anterior flap will be found to fall into apposition with the wound, while a ready exit is offered to all secretions. Instead of separating the limb by cutting from above downwards, the soft parts of the posterior region of the thigh may be severed by a semicircular sweep.

By *antero-posterior flaps* (Fig. 103).—The first steps of the operation are very similar to the preceding,

but the anterior flap must of course be cut shorter, and a second flap must be made of corresponding dimensions out of the soft parts at the back of the thigh after disarticulation.




FIG. 103.

By *oval incision*.—The subject placed upon the sound side (Fig. 104), the operator stands in front to amputate the right limb, and behind to operate on the left limb, and begins the incision immediately above the great trochanter of the femur, prolonging it along the anterior border of the trochanter in a direction from above, downwards, forwards and inwards, with slight convexity forwards across the front and inner side of the thigh to a point about three fingers' breadth in front of the tuber ischii, now turns out-

wards across the back of the thigh, and then upwards along the posterior margin of the great trochanter to terminate at the point of origin. This incision should divide integuments only. Now sever muscular attachments to the trochanter close to the




FIG. 104.

- retracted skin, open the articulation from behind, and divide the ligamentum teres as soon as the assistant shall have caused the head of the femur (*b*) to protrude from the acetabulum (*a*) by rotation of the

limb; place the knife (*c*) in the wound behind the bone, and sever the remaining soft parts and vessels while the assistant, following the knife with his hand, compresses the latter.

The fibro-cartilaginous border of the acetabulum and remains of the capsule may be removed with a scalpel.



## CHAPTER X.

### UPPER EXTREMITY.

*The Fingers.*—These members are of so great value to the owner, whether whole or mutilated by injury or operation, that no more of either is to be removed than is absolutely necessary. This remark applies with still greater force to the thumb. A finger may be amputated either in its continuity or contiguity, and various methods have been advised for this purpose.

*Anatomy.*—If a finger be examined from before backward, when extended, certain transverse markings will be seen and bony prominences may be felt. On the palmar aspect is a transverse linear depression in the skin, situated about a line posterior to the articulation of the second and third phalanges; further back are two well-marked lines with several incomplete lines between them—the posterior of the two former corresponds to the joint between the first and second phalanges; at the junction of the finger with the palm is another transverse depression, but which is much anterior to the metacarpo-phalangeal joint; the oblique markings in the palm are somewhat posterior to the joints to which they correspond.

On the dorsal surface the most distinct of the transverse lines corresponding either to the joint between the second and third, or between the first and second phalanges, is just opposite to the line of articulation. On the side of the finger opposite to the joint between the second and third phalanges, two elevations with a depression between, marking the line of articulation, may be recognised; on the dorsum and base of the second phalange a tubercle is situated, and immediately behind this is the articulation between the first and second phalanges. The superficial head of the metacarpal bone is not prominent; but if the finger be flexed to a right angle, the convex head becomes very prominent, and the line of articulation is much advanced. A tubercle, sometimes well marked, is situated on either side of the base of the first phalange, and is immediately in front of the joint.

Observations upon the second and third phalanges of the fingers are sufficiently applicable to the phalanges of the thumb, and need not to be repeated.

When operating upon the hand, the main vessels (radial and ulnar arteries) may be conveniently compressed against their respective bones by the fingers of an assistant, placed upon the anterior surface, while the thumbs rest upon the posterior surface of the forearm just above the wrist.

Amputation at the joint of the second and third phalanges, by *palmar flap*.

Assistants should hold aside the adjacent fingers,

with a loop of bandage cast around each. The operator holds the condemned phalange dorsum upwards, with the forefinger and thumb of his left hand, the thumb being upon the dorsal, the forefinger upon the palmar surface of the finger; recalling the anatomical landmarks mentioned above, and with a *narrow-bladed* knife he cuts transversely through the soft parts on the dorsal surface, directly into the joint of the extended finger. Flex now the phalange, and traverse the joint by dividing the lateral ligaments, first one and then the other, by elevating and depressing alternately the handle of the scalpel; turn the edge of the knife forwards so as to insinuate it behind the head of the condemned phalange, and cut forwards towards the tip of the finger, keeping the knife close to the bone while so doing; measure the length of flap requisite, by bringing up the raw surface of the soft parts which have been separated from the phalange against the exposed head of the second phalange, and complete the flap and remove the phalange by cutting forwards to the necessary extent.

Amputation at the joint of the first and second phalanges by *palmar flap*.

The above mode of operating is also to be observed at this joint. In either case the head of the phalange may be removed at pleasure.

Amputation in the *continuity* of a phalange by *palmar flap*.

The palmar flap is to be cut by transfixion, then

the soft parts on the dorsum are to be divided transversely or with slight convexity forwards, when the bone may be severed either by saw or forceps.

Amputation either in the continuity or contiguity of a phalange by *double flap*.

Cut a semilunar dorsal flap in the usual way, from skin to bone, the points of origin and of termination of the incision being allowed to correspond with the intended point of section or of separation of the bone; form the second flap by transfixion, or by cutting forwards after that the joint has been traversed.



FIG. 105.

Amputation by *a short and a long rectangular flap*. (Teale's method, page 211.)

Of the above methods, that by *long anterior flap* is perhaps to be preferred, because the bone will be protected by a good covering of soft parts, and the cicatrix being upon the dorsum, will not be exposed to pressure.

Amputation at the metacarpo-phalangeal articulation by *lateral flaps*. The head of the metacarpal bone being very prominent, a due proportion of integument must be left to cover it. The incision is to be begun on the dorsal surface, opposite to the centre of the joint, and to be carried forwards along and near to the centre of the phalange towards the junc-

tion of the web with one side of the finger, at which point the knife is to be turned across the palmar surface along the groove in the integument to a corresponding point on the other side of the finger, when it should be conducted back to the point of origin of the incision, dividing the parts as on the other side; or, after having cut one flap, the joint may be opened and traversed by the knife from one side to the other, when the second flap may be made by cutting forwards and outwards by the side of the phalange to be removed. Fig. 105 shows the lateral flaps with the head of the metacarpal bone between them.

A finger having been removed, and the edges of the wound united by suture, the adjacent fingers should be at once approximated by a bandage.




FIG. 106.

By *oval incision*.—Commence the incision opposite to the centre of the joint, and on the dorsal surface (Fig. 106, *a*); carry it obliquely forwards along the side of the finger (*b*), traverse the groove on the palmar surface, here indicated by a dotted line on the dorsum, and return along the opposite side of the

finger (*e*) to the point of commencement. Divide



the extensor tendon, traverse the joint, and complete the separation by section of the flexor tendons.




FIG. 107.




FIG. 108.

Fig. 107 shows the result of the oval incision: *i* is the subcutaneous tissue of the palm; *j*, the sheath of flexor tendons; *l*, the head of metacarpal bone; *m*, the extensor tendon. A linear cicatrix is the result (Fig. 108, *b b*).

Should it not be thought necessary to preserve the normal width of the hand, the head of the metacarpal bone may be removed (Fig. 109).

Amputation of *whole or part of a metacarpal bone*.—The cutaneous incision should be in the form of an elongated oval, or triangle with rounded angles, and made after the manner above described; the point of origin of the incision to correspond to the intended point of section or of separation of the bone. Separate

the soft parts from the condemned bone with the knife held parallel to the long axis of the latter,




FIG. 109.

while the muscular attachments are being divided on one side ; then, cautiously and without injuring the palm, pass the point of the instrument behind the bone and cause it to appear through the wound on the opposite side (Fig. 110), and complete the section of soft parts by cutting forwards : sever the bone with forceps, or disarticulate at the carpo-metacarpal joint, using the bared bone as a lever to assist.




FIG. 110.

Amputation of the *fifth metacarpal bone by oval incision*.—Commence the incision just above the base of the bone

(Fig. 106), carry it forward along the dorsum to one side of the finger as far as the junction of the web, then across the palmar surface of the finger in front of the normal groove, but on a level with the web; now back along the opposite side of the finger to the point of commencement. Carefully separate the attachments to the metacarpal bone without injuring the palm of the hand with the point of the knife, and using the bone as a lever to assist, disarticulate it at the carpo-metacarpal joint (Figs. 107, 108).

*By lateral flap.*—With the fingers and thumb of the left hand seize the soft parts on the inner side of the hand and opposite to the carpo-metacarpal joint, and while elevating them, as it were, from the bone, transfix them close to the above joint, and on the inner side of it. Now cut forward as far as the middle of the side of the first phalange and form a flap. Separate the soft parts from the outer and anterior surfaces of the metacarpal bone, carrying the incision forward to the opposite side of the first phalange, as far as the junction of the web with it, and so isolate the finger. Disarticulate at the carpo-metacarpal joint by opening it on the outer side.

*Amputation of the first metacarpal bone by oval incision.*—Commence the incision on the dorsum of the hand opposite to the articulation between the os trapezium and the metacarpal bone; carry it forwards on one side of the same to the point of junction of the web with the thumb, then turn outwards and

backwards across the palmar surface, and terminate above. Carefully separate the soft parts from the bone, not forgetting the position of the radial artery at the ulnar side of the base of the latter, and complete the operation by disarticulation begun on the outer side of the joint.

The operator must avoid the error sometimes made, of removing the trapezium as well as the metacarpal bone. In the male adult, the joint between the os trapezium and the first metacarpal bone will be about the length of the ungual phalange of the surgeon's thumb, inferior to the apex of the styloid process of the radius.

(*Caution.*)—I would again advise the student to use a *narrow-bladed* knife when operating in the contiguity of the bones of the hand and foot, otherwise he will often experience great difficulty in causing the instrument to traverse many of the articulations belonging to these members; also, to provide sufficient integument to cover the heads of prominent bones, such as of the metatarsal bone of great toe and of the metacarpal bones.

*Wrist-joint amputation by circular incision.*—The circular incision should be made through the integuments only, and when retracted to the requisite height, the various tendons and other structures are to be divided at the margin of the skin down to the bones. To open the joint readily, the operator must recollect the form of the articulation, the convex carpal bones being received into the concavity of the

radius and ulna ; and having opened the joint on one side just below either styloid process, should cause the knife, held perpendicularly, to follow the convexity of the carpal bones and to sever the hand, as it were, with one sweep.

By *double flap* (antero-posterior).—In consequence of the natural prominence of the styloid processes and their tendency, therefore, to project at the angles of a wound, the flaps should be begun and be terminated a finger's breadth below them ; also, in consequence of the mobility of the thumb, which, when adducted, causes puckering of the skin of the palm, the anterior flap should be marked out before the posterior be cut, otherwise the margin of the former would be irregular. The pisiform bone must be avoided when cutting the anterior flap.

The operator holding the condemned hand supine, with the thumb of it abducted, so as to make tense the integument of the palm, should mark out with the point of his knife a well-rounded semilunar palmar flap ; this done, pronate the hand, and dissect up to the requisite height, a similar flap of integument from the dorsum ; flex the hand forcibly, open the joint on the dorsal surface, and traverse it (Fig. 111) ; now turn the edge forwards, and avoiding the pisiform bone, complete the palmar flap, the extent of which has previously been determined.

*The forearm.*—Amputation may be performed at any point of the forearm ; but all methods are not equally applicable to each region. The limb being



eonieal, with the apex of the eonetowards the wrist, amputation by *circular incision* should not be attempted in



FIG. 111.

the lower half because retraction of the integuments could not be readily effected by consequence of the increasing size of the limb towards the elbow. Again, in the lower half amputation by *ordinary double flap* is not desirable by reason of the presence of many tendons, which, if they did not slough, would be useless in a stump.

Teale's method (page 211) is applicable to the lower half of the forearm. Fig. 112 shows the necessary incisions.




FIG. 112.

In the *upper half* amputation either by *flap* or by *circular incision* may be practised.

*Lower half* by *double cutaneous flap*.—Either divide the integument by circular incision, as described above, and then let fall a parallel incision on either

side of the arm to meet the first at a right angle, and so mark out two rectangular flaps of integument only; or, holding the hand prone, mark out an anterior and a posterior semilunar cutaneous flap: dissect up these to the requisite height; and now divide the muscles, &c., circularly down to the bones and as high as the bases of the flaps, sever the interosseous parts, and complete the separation with the saw. The ulna being the more firmly fixed bone, should be first attacked by the saw, then the radius is to be included and severed, while the separation is effected by completing the section of the ulna.

During the progress of the saw, it will be well for the assistants in charge of the limb, both above and below the intended point of section, either to hold each bone separately with a finger and thumb, or to press his thumb between the bones with a view to maintain their relative positions during the working of the saw.

Tendons are liable to glide from the edge of the knife and to escape division during a circular sweep; they may, under these circumstances, be divided separately, by passing the knife under them.

*Upper half.*—In this region, amputation by *ordinary double flap*, or by *circular incision*, may be performed.

*Elbow joint.*—If at all, amputation will be best performed at this articulation by *anterior flap*. To operate upon either arm, the surgeon will find it convenient to stand on the inner side. In consequence

of the natural prominence of the condyles of the humerus, the knife should enter the limb nearly one finger's breadth below the internal condyle; and in order to allow also for retraction of the supinator longus and other muscles arising from the humerus, should reappear on the outer side at a point nearly two fingers' breadth below the outer condyle.

The hand being supine and the forearm slightly flexed, the surgeon stands on the inside; and while his left hand is employed to seize and preserve as much integument as possible in the anterior flap, the knife held in the right hand should transfix the limb obliquely in front of the bones at the points above-mentioned, and form a long anterior semilunar flap, by cutting downwards and forwards. An assistant should at once withdraw this flap, when the operator, passing the knife behind the limb, divides the soft parts covering the posterior half of the forearm with a semicircular sweep, and at the same time opens the humero-radial joint. Any soft parts remaining in front of the articulation must be severed, as also the anterior and internal lateral ligaments, when the separation may be completed either with the saw, thus leaving the olecranon *in situ*, or by extension allowing the operator to pass the knife above the olecranon in order to divide its muscular attachments, and so the ulna is removed entire.

Amputation at the elbow joint is not a desirable operation, by reason of the large wound resulting.

*The arm.*—Amputation by *circular* or *flap* method

is equally applicable. The surgeon may stand on either side of the limb.

By *circular incision*.—Divide in the usual manner the integuments, and as soon as these have been well retracted by the appointed assistant, sever the superficial muscular fibres on a level with the retracted skin (except the biceps, which, having a high origin, may be cut lower, because it will become more retracted than the adjacent muscles); after a second retraction, divide all intervening structures down to the bone, the edge of the knife, during the circular



FIG. 113.

section of the muscles, being directed upwards and towards the bone, thus dividing the muscular struc-



tures obliquely, and leaving the bone, which may now be sawn across, at the apex of a cone. Fig. 70 shows the effect of the circular incision upon the soft parts of the arm, aided by retraction from above.

By *double flap*.—Amputation by *ordinary antero-*



FIG. 114.

*posterior* flaps by transfixion, care being taken to cut the anterior flap longer than the posterior to

allow for retraction of the biceps muscle; and by *ordinary lateral flaps* (Fig. 113) may be performed.

*Cutaneous flaps* only may be employed.

Teale's method (page 211) is applicable in this region. Fig. 114 shows the relation and extent of the necessary incisions.

*Shoulder Joint.*—Various methods have been proposed for the performance of amputation at this articulation. The movements of which this joint is capable in its normal state, as abduction, adduction, rotation both outwards and inwards, &c.; the position of bony eminences, such as the lesser and greater tuberosities to which muscles are attached, and their relation to the coracoid process on the inside and to the overhanging acromion, must be remembered.

By *external flap by transfixion*.—The subject should either be in the sitting posture and be well supported, or be semi-recumbent. One assistant will be required to control either the subclavian artery by compressing it upon the first rib behind the clavicle with a suitable compress, such as the handle of a door-key protected by a piece of lint tightly twisted round it, or to be ready to seize the axillary artery at the proper time; a second assistant will take charge of the arm, and if well tutored, will materially facilitate the operation. Two other assistants, armed each with a bent spatula, will be of service.

To operate on the *left* shoulder it will be convenient for the surgeon to stand on the outside and behind the subject, his left hand being free, while the

right is armed with a long narrow-bladed knife. The flap is to be formed chiefly of the deltoid muscle and integuments covering it. An assistant in charge of the arm should abduct it, so as to relax the deltoid, while the surgeon grasps with his left hand the soft parts covering the shoulder, in order to include as much as possible in the flap, which is to be made by entering the point of the knife behind the joint near the base of the acromion process, passing it carefully above the head of the bone without breaking its point




FIG. 115.

against the greater tuberosity, and causing it to reappear in front just outside the coracoid process.

This is a difficult manœuvre ; and should the subject be alive and very muscular, it will be well to cut the flap from skin to bone, unless the muscles be thoroughly relaxed by chloroform. A flap as broad as possible, well rounded inferiorly and reaching down the arm to the insertion of the deltoid (Fig. 115), should now be cut, and be held up by an assistant. The appointed assistant now carries the elbow to the patient's side, and the surgeon seizes the arm about its middle with his left hand and rotates the head of the humerus outwards, so as to expose the insertion of the subscapularis muscle into the lesser tuberosity. To facilitate this an assistant holds aside, either with a spatula or his finger, the soft parts on the inside, while the operator, holding the knife point downwards and parallel to the long axis of the humerus, severs the attachment of the subscapularis, at the same time carrying the knife over the head of the bone and down across the insertions of muscles into the greater tuberosity, so as to divide the capsule and long tendon of the biceps and the tendons of the supraspinatus, infra-spinatus and teres minor muscles, while the arm is being passed from a state of extreme rotation outwards to a position of extreme rotation inwards. (When cutting across the muscles attached to the tuberosities, it must be remembered that a few of the fibres both of the subscapularis and of the teres minor muscles, are inserted into the shaft of the humerus immediately below the tuberosities.) By this means the head of the bone will be liberated,

and the knife is to be introduced between it and the glenoid cavity (see Fig. 115); then the assistant seizes the soft parts on the inside, and compresses the axillary vessels, while the operator separates the limb by dividing all structures, intervening the knife




FIG. 116.

and the surface, at the point of junction of the folds of the axilla with the arm.

By *external flap cut from skin to bone*.—As by the above method, a long well-rounded, broad flap is to be made out of the soft parts forming the rotundity of the shoulder. On the left side commence the incision just external to the coracoid process, and



travel down the front of the arm as low as the point of insertion of the deltoid; then continue the section of the skin outwards and upwards nearly as high as the root of the acromion, and there terminate. Thus a well-rounded flap, base upwards, will be marked out. At the margin of the retracted integument sever the muscular structure, and dissect up the flap from off the bone. This done, the operation must be completed as above described.

To amputate the *right* extremity, the principal steps of the operations will be conveniently reversed.

By *anterior* and *posterior flaps*.—Excepting the use of the knife, the above instructions are applicable here.

To operate on the *left* shoulder, the surgeon will stand conveniently on the outside, and while manipulating the arm with his left hand, should enter the point of the knife held in the right hand immediately in front of the posterior cutaneous fold of the axilla; and, while elevating the elbow so as to depress the greater tuberosity and avoid striking it and carrying the instrument upwards and forwards, cause the point of it to reappear as much as possible in front of the apex of the acromion process, when the flap is to be formed by the knife cutting its way out in a downward direction as low as the junction of the posterior axillary fold with the arm (Fig. 116). Open the joint by dividing the capsule and adjacent tendons, pass the knife behind the head of the bone, and cut an anterior flap as low down as the junction of

the anterior fold of the axilla with the arm. (When attempting to liberate the head of a bone, such as that of the femur or of the humerus, the knife must not be allowed to run round the globular extremity with the flat of the blade upon it, but the edge of the knife must be held at right angles to the bone at each stroke ; if otherwise, the attached tendons, &c., will escape division.)

By *oval incision*.—Commence the incisions at the apex of the acromion process (Fig. 117), and divide the integuments on both sides of the arm, each terminating at the junction of its respective axillary fold with the arm ; retract integument and sever the




FIG. 117.

muscles down to the bone ; disarticulate ; pass the knife behind the humerus, and separate the limb by

dividing the muscles, vessels, and the integument on the inside, on a level with the axillary folds.

By this method the acromion is liable to protrude, and to avoid this accident, make first a perpendicular incision beginning at the apex of the acromion, and extending about two fingers' breadth down the arm, then complete the operation as above.

Of the various methods proposed for amputation at the shoulder joint, that by *external flap* is to be preferred, because a good covering to the wound is readily procured, and is also maintained, by its own weight, in position. Disarticulation can be effected with comparative ease.

It will be observed that the directions given above for performing amputation in certain regions are especially applicable when the integrity of the part has not been interfered with either by disease or injury ; under the latter circumstances, the ingenuity of the surgeon will devise how and whence the covering for the wound may be formed.

## CHAPTER XI.

### SPECIAL OPERATIONS.

#### TRACHEOTOMY.

BETWEEN the hyoid bone and sternum in the median line, two somewhat prominent organs, with a shallow depression between them, may be readily felt. These are from above, thyroid cartilage, crico-thyroid membrane corresponding to the depression, and cricoid cartilage. Between the cricoid cartilage and the sternum lies the trachea. Of these organs the rings of the trachea are incomplete posteriorly, and so also is the thyroid cartilage. The cricoid cartilage is a complete ring, and may therefore be firmly held and compressed between the finger and thumb without obstructing respiration. These parts are covered in front along the median line by integument and deep cervical fascia; the crico-thyroid membrane is crossed transversely by the crico-thyroid branch of the superior thyroid artery (the vessel running nearer to the thyroid than to the cricoid cartilage), the isthmus of the thyroid body lies upon the first rings of the trachea, and below this is a plexus of veins: also in front

of the trachea, but behind the first bone of the sternum, lie the vena innominata of the left side, the arteria innominata, and arising from the latter and ascending in front of the trachea, the arteria thyroidea ima is occasionally seen. On each side of the mesian line lies the sterno-hyoid muscle.

Chloroform may generally be used. When practicable, place the subject recumbent with the head thrown back over a pillow, and incise the integument and deep fascia in the mesian line to the extent of an inch to an inch and a half from the cricoid cartilage downwards; sever the areolar tissue and deep fascia immediately in front of the trachea, avoiding the veins if possible, but not necessarily the thyroid isthmus. Feel with the point of the forefinger for the rings of the trachea, and (while assistants, if there be any, with blunt hooks separate the edges of the wound and the adjacent borders of the sterno-hyoid muscles) open the trachea either above, through, or below the isthmus, as is most convenient, with a sharp-pointed bistoury from below upwards by dividing three or four of its rings longitudinally; if necessary, carefully introduce the canula, with or without a pilot, into the trachea, and maintain the same *in situ* by means of a tape passed around the neck. If the subject be alive, the constant rising and falling of the organ during deglutition and respiration will be often an obstacle to the act of opening the trachea; under these circumstances, if an adult, the cricoid cartilage may be held by the finger and thumb so as



to fix the trachea; or, in the case of a child, a sharp hook inserted into the cricoid cartilage and entrusted to an assistant to hold the organ elevated, will materially assist the operator.

Although the veins may bleed freely, open the trachea as quickly as possible, and the hæmorrhage will cease spontaneously.

The most difficult step of the operation is the introduction of a canula. To overcome the difficulty, I would suggest, to introduce the point of a *double* hook into the incised trachea, and holding the tube elevated with it, slip up the clasp and allow the halves of the hook to separate by their own elasticity and at the same time to open the wound in the trachea; now pass the canula into the windpipe. The double hook thus effects two objects—fixity of the trachea and widening of the incision already made into it. Sometimes, one edge of the tracheal wound may be caught by the nail of the forefinger, and thus fixed the introduction of the tube will be facilitated. The operator must avoid forcing the canula between the deep fascia and the trachea, instead of passing it into the latter. A tube so placed would be worse than useless, and in a child might fatally compress the windpipe. A double canula must be employed.

During the few hours subsequent to operation, a feather may be used to remove blood and mucus, but this latter soon becomes inspissated, and adhering firmly to the inner tube, offers a serious obstacle

to respiration. The operator will take care, therefore, that the inner canula project slightly beyond the outer at the tracheal end, when the two are *in situ*, so that as the former is withdrawn in order to be cleansed, the mucus may come with it.

Very often, as soon as the canula is safely lodged in the trachea, both the distress of the patient and the anxiety of the surgeon are removed; but in children already exhausted, the passage of blood into the trachea is often almost sufficient to cause death, because the expiratory effort is too feeble to expel the extraneous fluid. Under such circumstances, if he have the courage, the surgeon may sometimes save his patient by withdrawing such fluid with his mouth. *When practicable*, the operator should examine the interior of the trachea, with a view to the removal of false membrane, before inserting the canula; lest by detaching the former, the tube, instead of preventing, cause fatal obstruction.

When opening the trachea, avoid transfixing this tube, lest the œsophagus lying behind it be wounded.

In the absence of the above surgical appliances, a razor or sharp penknife will serve for the division of the tissues, and a quill might possibly answer as a temporary substitute for the canula.

Instead of using a canula, a small piece of one or two rings of the trachea may be cut away.

Various instruments for the ready performance of tracheotomy have been invented; but as either of

these will probably not be at hand when required, I shall not refer to them further.

The figures represent Mr. Durham's Tracheotomy Canula. This canula is so shaped as to pass directly backwards, and then to dip downwards in the middle of the trachea, instead of injuriously impinging against its anterior or posterior wall, as often occurs with canulas of the ordinary shape.




FIG. 118.

Fig. 118 represents the outer tube. The straight portion of the tube (A) slides backwards and forwards in the collar (B), but can be fixed at any point by means of the screw (c). The length of the portion of the tube in the wound may thus be proportioned to the depth at which the trachea lies. The collar (B) is attached to the small plate (D), which is connected with the neck plate (E) by means of two wings passing under little wire arches, in such a manner as to permit a certain amount of motion in various directions. The tube thus accommodates itself in position during the various movements of the head and neck.

Fig. 119 represents the inner tube. The “lobster-




FIG. 119.

tail” construction which has been adopted, renders its introduction and withdrawal very easy.

Fig. 120 represents the blunt-pointed Pilot Trocar upon which the canula is mounted to facilitate its




FIG. 120.

introduction into the trachea. The handle is represented cut off short.

#### LARYNGOTOMY.

This operation consists in opening the air-passage through the crico-thyroid membrane; it is performed with greater facility than tracheotomy, but is rarely so advantageous as the latter, the opening being small when effected, and probably unnecessarily near to the seat of disease requiring surgical interference. It is accomplished by a longitudinal incision in the mesian line to expose the crico-thyroid membrane, and a transverse cut in the latter. A small artery bleeding should be secured.

## PARACENTESIS THORACIS.

Should there be no special indication, the cavity of the pleura will be conveniently opened at the space between the sixth and seventh ribs, external to their angles.

The operation may be effected either by a trocar and canula, or by a scalpel, or by caustic. If it be determined to draw off a certain quantity only of the contained fluid, the wound in the integument should correspond with that of the pleura, only temporarily, in order to ensure closure of the opening after the completion of the operation; should a permanent opening be required, the relation of the integument to the pleura need not be altered. The point for puncture of the pleura having been determined upon, the skin is to be drawn either down or up, and be so maintained until the completion of the operation, when the tractile force being removed, the wound in the integument will no longer correspond with that of the pleura; incise the skin on a level with the superior border of the rib, with a view to avoid the risk of wounding the intercostal artery, which in this region runs along the lower border of the middle third of the rib; either continue to incise the muscles and even the pleura itself on the same level with a scalpel, or puncture the chest with a small trocar and canula. The contents having been drawn off to the requisite quantity, the skin may be allowed to return to its normal position, carrying the superficial wound with it, and so assisting, with a compress and strap;



ping which may now be adjusted, to close the deeper wound. If danger from entrance of air be apprehended, either a piece of wet rag may be adapted to the canula as a valve, or a special instrument must be employed.

#### ŒSOPHAGOTOMY.

In the cervical region, the œsophagus lies in front of the spine behind the trachea, but slightly to the left of the mesian line, and therefore can be more readily reached on the left than on the right side of the neck ; external to it is the sheath of the carotid vessels. This tube begins at the termination of the pharynx opposite to the cricoid cartilage, and must therefore be reached, if at all, between that cartilage and the sternum.

Place the subject recumbent, with the head thrown back, and make an incision three inches in length along the anterior and inner border of the sterno-mastoid muscle, dividing skin, superficial fascia, and platysma ; throw forward the head so as to relax the sterno-mastoid and other muscles, and let assistants separate the edges of the wound and protect the anterior jugular vein from injury ; seek the outer border of the sterno-thyroid muscle, and cautiously slit up the cervical fascia upon a director along that border ; this division of the fascia will expose, when the edges of the wound are well separated, thyroid veins, lower portion of lateral lobe of thyroid body, which, it must be remembered, is supplied by the inferior thyroid artery, and which vessel crosses

deeply the upper part of the line of incision behind the carotid sheath, the internal jugular vein being very prominent; in the groove between the trachea and œsophagus is the recurrent laryngeal nerve. Introduce through the mouth into the œsophagus an elastic catheter, or a probang, in order to dilate the tube and to point out its exact position in the wound open the tube by cutting upon the catheter, otherwise it will not be easy to find the interior of a canal the walls of which are naturally in contact.

In the case of a foreign body in the œsophagus, the projection of the same will probably indicate the spot at which the tube should be opened.

#### GASTRO-STOMACHOTOMY.

Place the subject recumbent, with the head and shoulders thrown forward, and make a linear incision about two inches in length along the outer border of the sheath of the rectus muscle, commencing at the ninth rib. Divide integuments, muscular aponeuroses, intercostal vessels and nerves, transversalis fascia (which in this region is very thin), and peritoneum, the two latter on a director; introduce the forefinger of the left hand and feel for the stomach (which, if the subject be alive, will probably be contracted and smaller than usual). The position of the organ detected, a fold of its anterior wall should be seized, either with the finger and thumb or by a pair of forceps, and be brought out at the wound; transfix the fold of stomach and both edges of the wound with needles

and ligature at two points, with a view to keep the viscus at the wound while being opened with the knife, and also to serve as a means of maintaining the cut edges of the stomach in apposition with the margins of the wound in the integuments when the operation is completed. Besides these, by means of several fine sutures, stitch the peritoneal coat of the stomach to the edge of the wound, so as completely to shut off the peritoneal cavity of the abdomen from the exterior. Now incise the protruding portion of stomach, without severing the threads which are traversing its cavity, sufficiently to admit the forefinger; and having secured by suture the edges of the aperture in the viscus to those of the skin, by making use of the sutures already referred to, and adding others, the operation will be completed.

To promote adhesion, the recumbent posture should be strictly maintained for several days; no food should be put into the stomach for twenty-four hours, and the left side of the chest may be somewhat fixed by the application of a broad strip of strapping extending from the ensiform cartilage to the spine.

#### PARACENTESIS ABDOMINIS.

Having ascertained by physical examination that distention of the abdominal walls is due to the presence of fluid and not of solid matter, also that the intestines are not near the surface, and that the urinary bladder is empty, place the subject upon the

side (if in the case of ovarian dropsy, upon the side corresponding to the supposed seat of the disease), with a bandage applied around the abdomen, and entrusted to assistants to tighten and to compress the belly during and after the evacuation of its contents. Select a spot in the linea alba about midway between the umbilicus and the pubis, and having incised the skin with the point of a lancet, plunge a well-oiled trocar and canula into the abdomen. As soon as the trocar has entered, as will be known by an absence of resistance to its progress, withdraw it, but push the canula further in to avoid the risk of its slipping out. The fluid having been drawn off, withdraw the canula and close the wound with lint and strapping, and support the whole abdomen with a thick pad and broad roller. Instruments specially adapted to this operation are made.

*The Trocar.*—When a trocar and canula are made to enter a cavity, the forefinger should be placed upon the canula at a short distance from the point of the trocar, that the instrument may not penetrate too far; also, a twisting motion should be given to the thrust, in order to facilitate the passage of the instrument through the soft parts, and to cause less pain to the subject if alive. The canula, too, should be removed by twisting it gently with the finger and thumb of one hand, whilst the fingers of the other hand, placed upon the integument around the puncture, offer resistance to the withdrawal of the tube.

## ABDOMINAL HERNIA.

*The Taxis.*—A hernia being strangulated requires surgical interference ; but before having recourse to the knife, the surgeon usually endeavours to return the protruded mass by pressure, effected by manipulation aided by other means. The principle of this taxis consists in the endeavour to lessen the bulk of the tumour both by diminishing the quantity of blood retained in the substance of it, and by expressing the contents of the bowel, if bowel there be, within limits which shall allow of the hernia being returned through the constricted aperture by which it left the abdomen.

Of the remedies employed to favour the success of the taxis, chloroform is to be preferred : it operates rapidly and without loss of time ; by its agency, the patient is rendered insensible to pain ; powerless as regards exerting muscular action, either upon the whole contents of the abdomen or in the immediate vicinity of the part interested in the strangulation ; the effect of the drug soon subsides, leaving the patient in an almost equally favourable position to undergo herniotomy. The warm bath, opium, tartar emetic, and bloodletting are slower in operation, more lasting in their effects, and if the taxis be unsuccessful, the subject is probably in a condition less favourable to recovery after herniotomy than he was previous to the trial of any of these latter remedies.



Besides these therapeutic agents, a knowledge of the relative anatomy of the part interested will dictate the position in which the subject is to be placed during the employment of the taxis.

The tumour, taken into the hand of the surgeon, is to be compressed *upon itself*, at first gently and slowly, but increasingly and continuously, for the space of from five to fifteen minutes, while, at the same time, a direction exactly the reverse of that by which the hernia protruded is to be given to the tumour. The taxis having been fairly tried and failed, should not be re-attempted, and in the case of a recent hernia, the result of a blow, or great muscular exertion, in which the neck of the tumour is very narrow, very painful, and the patient in great agony, the taxis should not be even attempted; neither if gangrene be supposed to have supervened should this means be employed; on the other hand, in the instance of old herniæ, with symptoms of strangulation setting in, the taxis will often avail.

As a general rule, less evil will result by an early use of the knife than by delay and the repeated taxis.

I would repeat, that in applying taxis, the hernial tumour is not to be pressed bodily and forcibly against the ring by which it has made its exit, because, by so doing, the mass would have a tendency to spread and occupy a large extent of surface *around* the aperture, rather than to retrace its steps *through* the ring, but is to be compressed *upon itself*.

## HERNIOTOMY.

Herniæ may occur at various points of the abdominal wall, but general principles will be applicable to all. Determine the variety of hernia in question; endeavour to ascertain the seat of stricture by observing, while compressing the tumour, the point at which the impulse or the yielding caused by pressure ceases; at that spot the seat of stricture will probably be found to exist. Shave the part if necessary; place the subject recumbent, and in such a position that muscles and fasciæ interested may be thoroughly relaxed.

Make an incision along the centre of and parallel with the long axis of the tumour, commencing just above the expected seat of stricture and terminating sufficiently low, that, in case of need, the contents of the sac may be easily exposed and examined; be prepared for any sudden movement on the part of the subject during the progress of the knife; divide the coverings of the hernia cautiously and separately on a director, always examining each layer as it comes into view, in order, if possible, to ascertain the relation of the edge of the knife to the hernial sac. As layer after layer is divided with more or less anatomical precision, the sac is at length reached, and may be recognised by its membranous character, in the case of a recent hernia being more or less transparent, and although some adhesions may exist, the finger can often be readily swept round it and

isolate it from the adjacent structures. The opened sac is known often by an escape of sero-sanguineous fluid ; by recognition of its contents, whether bowel or omentum, or both, these organs varying from pink to port-wine colour, in proportion to the degree of strangulation to which they have been subjected—the bowel being more or less smooth, tense, and glistening, and the omentum, though fatty, being membranous. The operator may satisfy himself that he has *not yet* opened the sac by seizing and raising a portion of the tumour with his finger and thumb, and then, allowing this portion to glide away partially and slowly from his hold, he will feel a substance slip from him, while the covering which is visible remains in his grasp. The sac reached, the operator (except under special circumstances) should endeavour to return the protrusion into the abdomen without dividing its peritoneal covering ; and to do this, should ascertain with the point of the fore-finger of his left hand the position of the expected stricture, and endeavour to insert either the nail or a director between the constricting fibres and the neck of the sac as a guide to the bistoury : should the finger be used, the blunt-pointed bistoury must be run along it with its blade flat, and when inserted, the edge of the knife turned towards the stricture, can be made to divide it to the requisite extent by nicking the part at one or more points. When using a director, the knife must be carried along its groove.

Instead of attempting to sever the constricting

fibres by insinuating the knife between these and the sac, the former may be advantageously divided from without to within at one or more points; by this means the constricting ring will become stretched and enlarged, and will probably admit of a reduction of the hernia without opening the sac.

This mode of liberating a stricture is especially applicable to cases of inguinal hernia. Fig. 121 shows



FIG. 121.

the blunt-pointed hernia knife, the edge of which is protected by a sliding sheath. The blade is to be introduced covered, and when through the strictured aperture, the sheath may be withdrawn to the requisite degree and the part be divided; this done, the sheath can be pushed forward again towards B by the thumb applied at A, and the knife be withdrawn. With this instrument, no risk is incurred of wounding the protruding bowel, and a director is not required.

The expected seat of stricture having been divided, the taxis re-applied will probably complete the operation; but if not, the sac must be opened. Seize the sac with a pair of forceps near its neck, and open it just sufficiently to admit the tip of the finger to explore; when, if the stricture be at the neck, it can be nicked, and the taxis re-applied will effect reduction. Should, however, the obstacle to reduc-

tion be in the body of the sac, this envelope must be slit up in the line of the original wound, in order to expose its contents fully. In doing so, take care that some portion of the contents do not intervene the director and the sac and suffer division by the knife; also when the sac is opened, serous fluid, of variable colour and quantity, will probably flow out, and the contents may be more or less adherent to the internal surface, and will therefore incur a greater risk of being wounded. The taxis applied gently will probably reduce the hernia, and that portion is to be returned first which came down last, and intestine before omentum; close the wound, provided that there be no contra-indication, with sutures, strapping, compress and Figure 8 bandage (the lower loop of the bandage should embrace the thigh, the upper loop the pelvis). The patient is to be placed in bed with the thighs semi-flexed upon the abdomen, and the knees supported by a pillow placed under them.

*Division of the Stricture.*—The mode of liberating a stricture must depend upon the relative anatomy of the parts adjacent to the hernia. In femoral rupture the usual seat of stricture is at Gimbernat's ligament, and to sever this structure the edge of the knife must be directed inwards. The femoral ring is bounded in front by Poupart's ligament and the spermatic cord in the male; behind, by the horizontal ramus of the pubis; externally, by the femoral vein, only a thin septum of the femoral sheath intervening; and in-



ternally, by Gimbernat's ligament. Thus it will be seen that a hernia making exit at the crural ring and becoming strangulated, the stricture will be liberated with less risk of injury to neighbouring parts by nicking Gimbernat's ligament, and whether the sac be opened or not by cutting *inwards*.

In inguinal hernia (complete), it is often quite impossible to decide whether or not the case be one of *direct* or *oblique* rupture; therefore, to avoid wounding the deep epigastric artery, it is desirable in *all* cases to sever the stricture in a direction nearly parallel to the course of this vessel, *i.e.*, *upwards*.

In rarer forms of hernia the stricture must be divided on the principle of inflicting as little injury as possible; and in the case of umbilical hernia the knife must be used throughout the operation with extreme caution, because the tissues covering the rupture are often very thin, and the peritoneal sac is either equally so or adherent to the integuments.

*Line of Incision.*—It is customary to cut down upon a hernia by incising the intervening structures along the median line and long diameter of the tumour; but in order, in case of recovery, to avoid any inconvenience which might arise from pressure of the pad of a truss upon a cicatrix, the incision may be made towards the inner side of the long axis of the tumour, and especially in the case of femoral hernia, where the seat of stricture is usually on the inner side.

## RADICAL CURE.

In some cases of reducible inguinal hernia, it may be justifiable to attempt the *radical cure* by one of the modes recommended, and of which that of Wood is to be preferred. The principle of this operation consists in the closure of the tendinous hernial canal and the obliteration of the hernial sac by one and the same proceeding. It is accomplished by drawing together the tendinous sides of the canal by wire sutures, which, at the same time, traverse and invaginate the sac, and produce a mass of adhesive effusion, binding the whole together. The valvular




FIG. 122.

arrangement of the canal in its normal condition is thereby reproduced, with its effective resistance to a hernial protrusion. The instruments required are a small sharp-pointed tenotomy knife, with a handle

tapered, and rounded at the end like a paper-knife (Fig. 122 *a*); a stout needle, with a semi-circular curve, its point flattened antero-posteriorly, containing a large eye, and mounted on a strong handle (Fig. 122 *b*), and a piece of stout copper wire, silvered, about two feet long. The wire is bent at each end into a short acutely curved hook, to be attached to the eye of the needle after it is passed through the tissues. The steps of the operation are conducted as follows :—The patient being laid on his back, with the shoulders well raised, and the knees slightly bent, the pubis is cleanly shaved, the rupture entirely reduced, and chloroform administered, until the stage of quiescent anæsthesia is produced. An oblique incision, about an inch long, is made with the tenotomy knife through the skin of the scrotum, about one and a-half inches below the pubic spine. The blade of the knife is then carried flatwise under the skin round the incision, separating it from the fascial coverings of the sac for about an inch or more all round; the thin end of the handle of the knife may be used to complete the separation. The forefinger is then passed into the wound, and the sac and fascia invaginated well up into the hernial canal as far as the deep hernial opening, and made to feel for the lower edge of the *internal oblique muscle*, which is to be raised well upon the finger. By this means the edge of the conjoined tendon of the *internal oblique* and *transversalis* muscles may be felt tense and prominent at the inner side of the

finger. The needle is then carried carefully along the same side of the finger till it reaches the point, where it is made to transfix the conjoined tendon, and carried through the tendon of the *external oblique* till its point raises the skin. The skin is then drawn towards the median line of the body as far as possible before the point of the needle is made to pierce it. One end of the wire is hooked on to the eye of the needle, drawn back with it into the scrotum, and then detached. The sac is then again invaginated by the finger, the point of which is now placed well behind the middle of Poupart's ligament, raising it prominently from the femoral vessels. The needle is again passed along the finger at its outer side, and pushed through Poupart's ligament, below the deep hernial opening. The point is then directed by outward traction of the skin through the puncture previously made, and, already transmitting one end of the wire, the hook at the opposite end of the wire is passed through the eye of the needle, drawn down also into the scrotum, and detached. Next, the sac and its coverings at the scrotal incision are pinched up between the finger and thumb, and the spermatic cord recognised and slipped back, as in taking up varicose veins, and the needle is passed across behind the sac, and between it and the cord, its point entering at one extremity of the scrotal incision and emerging at the other (as shown in Fig. 123). The inner hook of the wire is then again attached to the needle, and drawn

back with it. Both ends of the wire are next drawn down, until the loop which is left in the upper or groin puncture projects about an inch only. The ends are then twisted firmly together by three complete turns, and cut off with pliers, leaving a length of about three inches projecting, the ends of which are then to be bent into a hook. Traction is then made upon the upper loop until the sac and scrotal fascia is well and closely invaginated as high up as the deep hernial opening. The loop is then bent downwards, and the hook last made at the ends of the wire bent upwards until it reach the loop,




FIG. 123.




FIG. 124.



into which it is finally fixed (See Fig. 124, A, B). A stout pad of lint is passed under the arch thus made (as seen in Fig. 125, c). A spica band-




FIG. 125.

age, with its ends disposed so as to form a suspensory for the scrotum, completes the dressing. The wire is kept in for about a fortnight in the smaller, or three weeks in the larger cases; or longer, if the amount of adhesive consolidation is not satisfactory. Occasional sponging away of the small amount of discharge and changing the pad, if cleanliness requires it, is all the dressing that is subsequently needed. The bandage may be removed altogether in three or four days if it galls

the patient. At the end of a fortnight the wire usually becomes so loose by the ulceration of the tissues which it traverses that little difficulty is experienced in its withdrawal. This is accomplished by untwisting the three turns, cutting off the hooked ends, straightening the curves by traction with a couple of pairs of common pliers, and then pulling at the upper loop. When the upper puncture is healed, which usually occurs sooner than the lower, a horseshoe or a ring pad of Mr. Wood's pattern (see Figs. 126 and 127) should be applied, and the patient may then rise from the recumbent posture, but not before. An aperient of castor oil or haust. sennæ co. is usually required about the fourth or fifth day after the operation, and if any pain occurs in the abdomen, a hot flannel fomentation and a few doses of pil. saponis co., morphia, or chloral usually suffice to remove it. Sometimes the *ilio-inguinal* nerve is unavoidably included in the wire, which may give rise to pain along the iliac crest and loins, which has been, but should not be, mistaken for peritonitis. The truss should be worn for a few months in small cases, but longer in large ones, when it may be laid aside, unless in exceptional cases, or when the patient is likely to be subjected to violent strains, or lifting.


In large cases of *direct* hernia, Professor Wood crosses the wires in the canal, and obtains an additional hold upon the pillars of the ring, close to the pubis, and he recommends a ring-pad truss, of pecu-

liar construction (made by Matthews, of Portugal-street), to be worn for a year after the operation.

In small children's cases he employs a couple of *rectangular pins* (made by the same maker), one of which is made to traverse, from above downwards, the inner pillar of the superficial ring and the conjoined tendon; and the other, from below upwards, the centre of Poupart's ligament. During the application of the pins, one of the fingers is made to invaginate the scrotum into the canal, and to protect the deep-seated parts. Each of the pins traverses the same punctures as the other, but in opposite directions, and the point of each passes through a loop formed in the other at the position of the angle of the pin. On being pushed home, the pins draw together the parts which they traverse, in the same way as the wires in the operation just described. They are held in position by lint, pads and strapping, and require no bandage.

Out of 174 cases of inguinal rupture of all kinds and degrees of severity operated on by Professor Wood, 125 have proved, as far as can be ascertained up to the present time, satisfactory cures. Many were operated on twelve years ago, and none of the cases have been made worse, but almost all relieved by the operation, and in many a truss has been made available when it was not so before. Three have died—one from pyæmia, and two from peritonitis, death in one instance originating in the bowel previous to operation.

In order to support the parts after the operation for the radical cure, Mr. Wood requires the patient to wear a truss with a pad of a peculiar shape. Experience showed that the ordinary trusses with pads more or less *convex*, instead of supporting the parts, pressed into them like a plug. This involved the danger of breaking down the newly-formed adhesions and re-dilating the hernial openings, of injurious pressure on the spermatic cord, and of a tendency to increase the size of the hernial openings, which are common effects of wearing convex pads. The pads of Mr. Wood are founded on the principle of marginal pressure on the sides of the opening, avoiding its centre. The pad for oblique inguinal hernia is called "the horse-shoe pad," from its




THE HORSE-SHOE PAD.

FIG. 126.

resemblance to an obliquely eurved horse-shoe; the portions of it which press on the abdominal walls are flat with rounded edges, and the long slit in the pad placed over the pubic spine prevents any injurious pressure on the spermatic cord. The bifurcated extremities of the pad support the parts in the same

manner as the fingers of a hand when so applied. A “ring pad” is used in cases of direct hernia.



RING PAD.

FIG. 127.

In these cases, as the pad is placed over the deep hernial opening, the cord is not pressed upon. The pads are made of hard ebonite, boxwood, or, in irritable cases, of water contained in an india-rubber bag, and are now extensively employed both for the retention of hernia, and its cure in infantile and slight cases where the operation has not been deemed expedient.

Messrs. Matthews, of Portugal-street, who have fitted the pads in numbers of cases, assure us that they experience less difficulty in fitting these pads comfortably to the patients than the pads of the old-fashioned and other descriptions of truss.

#### LUMBAR ARTIFICIAL ANUS.

Usually performed to relieve either obstructive or painful disease of the rectum, both malignant and non-malignant, and generally on the left side.



The colon may be reached in either loin either by a transverse,\* an oblique, or a longitudinal incision. In any case, the point at which the loin should be opened corresponds to the outer border of the sheath of the quadratus lumborum muscle, just above the crest of the ilium, the length of the ungual phalange of the thumb from the outer border of the erector spinæ muscle, and this spot should be at the centre of the incision, no matter which be selected. The subjects of this operation are usually thin, and the oblique border of the quadratus can be readily detected by the finger of the surgeon carried from before backwards, with firm pressure across the loin. The direction generally given is, to make the transverse incision midway between the crest of the ilium and the last rib; but as the kidney sometimes hangs low, the loin should be opened near to the ilium in order to avoid it.

N.B.—When cutting down upon an artery, it is usual to divide all the structures to an equal extent, not so when cutting down upon the colon. It is most important, in operations upon the abdominal wall, to weaken this structure as little as possible to avoid hernia and its attendant danger and discomfort. In performing colotomy, the integument should be divided to the greatest extent, and each layer of tissue after less and less, and the lumbar fascia least of

\* The author, having performed the operation nine times, prefers the *transverse* incision.

all. Thus, the loin will be opened through a conical wound, the base of which corresponds to the incision in the skin. Supposing the operation to be undertaken for the relief of disease other than obstruction, the colon in the loin may be empty, and, if so, will be found with less facility than when distended. It may, however, be filled artificially by an enema—a quart or more of warm milk being gently thrown up when the patient is under the influence of chloroform. The milk is recognised when the bowel is opened.

By *longitudinal incision* (Callisen, Hilton).—Place the subject on the sound side, with a pillow under the loin, and if an adult, make a vertical incision in the costo-iliac space from two to three inches in length, parallel to the lumbar spines and four inches external to them, or one inch external to a vertical line drawn between the angle of the ninth rib and the crest of the ilium. Divide in order the integument, perhaps some fibres of the latissimus dorsi, the origin of the internal oblique, leaving the free margin of the external oblique external to the line of incision, the last dorsal nerve if seen coursing downwards and forwards, the tendon of the transversalis muscle, and the transversalis fascia. This done, the finger may be introduced and the psoas muscle recognised, and the inferior extremity of the kidney, if felt, must not be mistaken for hardened feces, nor *vice versâ*; more or less cellular tissue intervening must be either removed or turned aside

by the aid of two pairs of forceps, and the intestine, known by its longitudinal bands, will be reached, and should it be distended, pressure applied upon the anterior abdominal wall will probably cause it to bulge. Now pass a long needle armed with a ligature, so as to transfix the integument on either side as well as the intestine in the wound, and while thus fixed, open the bowel sufficiently to admit the finger. Complete the operation by fastening the margins of the wound in the colon to the edges of that in the integument, beginning with the suture already introduced, and adding as many more as may be necessary.

By *transverse incision* (Amussat).—This consists in making a transverse incision in the loin from three to four inches in length, a finger's breadth above the crest of the ilium, beginning at the outer border of the erector spinæ muscle, and dividing the integuments, some fleshy fibres of the free border of the external oblique muscle and the iliac origin of the latissimus dorsi, the origin of the internal oblique muscle and the tendon of the transversalis muscle and the transversalis fascia—perhaps also the outer border of the quadratus lumborum muscle and sheath. Any vessel bleeding should be ligatured. Having divided the transversalis fascia, a quantity of loose areolar tissue and more or less fat alone conceal the intestine. Complete the operation as above described.

By *oblique incision* (Bryant).—Instead of either of the foregoing, an incision corresponding to the outer

border of the sheath of the quadratus lumborum muscle may be preferred.

Neither this nor the sheath of the erector spinæ should be opened.

The object of these methods is to open the bowel without injuring the peritoneum, and for that reason either the ascending or descending colon is selected in a locality where the viscus is usually uncovered posteriorly by peritoneum, in preference to the operation recommended by the older surgeons of opening the abdominal cavity above Poupart's ligament, in order to reach the sigmoid flexure. Fig. 128 shows




FIG. 128.

the longitudinal incision on the left lumbar region. The integuments, &c., are incised an inch nearer the spines than they should be when the operation is performed, and the posterior layer of the sheath of the erector spinæ and of the quadratus lumborum muscles has been removed to show their relation and the course of their respective fibres. The longitudinal fibres are those of the erector spinæ; the fibres coursing from below upwards and inwards are those

of the quadratus lumborum muscle, the outer border of which is consequently oblique, and overlapping it is a portion of intestine which has been forcibly pulled out through the wound.

#### ABDOMINAL ARTIFICIAL ANUS.\*

Occasionally, it will be deemed right to open the abdomen in one or other groin with a view to remedy intestinal obstruction, and to establish a communication either with the small or large intestine.

The operation consists in making a small incision on a level with the anterior superior spinous process of the ilium at the outer edge of the rectus muscle. The peritoneum being reached, this membrane is to be slit up only sufficiently to allow the distended bowel to appear, but not to protrude. With a medium-sized curved needle and thread the bowel, *still unopened*, is to be stitched on either side to the edge of the wound, so as most carefully to avoid entrance of intestinal contents into the peritoneal cavity. This done, the bowel may be opened sufficiently to admit the tip of the index finger; and when the pent-up contents cease, for a moment, to flow, two or three more sutures may be used to

\* On February 11, 1872, the author shared with his colleague, Mr. McCarthy, the responsibility of advising the making an artificial anus in the *small* intestine in the right iliac region. Mr. McCarthy performed the operation in the manner described above, and the patient, a male, 52 years of age, recovered.



fasten the edges of the wound in the bowel to the skin.

Opening the sigmoid flexure in the groin is called Littre's\* operation. Whichever bowel be selected for operation, the operator will take care to recognise the distinctive anatomical characters.

#### OVARIOTOMY.

The bladder having been evacuated by a catheter, place the subject recumbent, with the head and shoulders raised and thrown forwards, the buttocks resting on the edge of a table or bed, while the legs hang over and are comfortably supported each on a chair or foot-rest. The operator stands between the thighs of the patient, having a receptacle at his feet for the fluid contents of the cyst, and makes an incision in the linea alba between the umbilicus and the pubes, sufficiently large to admit his hand into the cavity of the abdomen to explore the exterior of the cyst. This exploratory incision may be enlarged, if necessary, as far as the ensiform cartilage in one direction, and the pubes in the other direction. Bearing in mind the tension to which the abdominal wall has been subjected, and the consequent thinning of the parts covering the tumour, the integuments and linea alba must be cautiously divided, lest the abdomen be opened before it be expected. (I have known the

\* In 1870, the author performed Littre's operation on a patient of Mr. Cockell's, of Dalston. The infant died on the eighth day in convulsions.

cyst to be reached and its wall mistaken for the linea alba.) The peritoneum is to be slit up sufficiently to admit two fingers of the left hand, along which, forming a director for the knife and a protection to the organs behind, it is to be divided to the extent of the wound in the integuments; introduce the hand into the abdominal cavity and sweep it round the tumour, in order to ascertain its relation and extent of adhesion to the viscera, and probable amount of solid matter, of which it may be partly composed; slight adhesions to the abdominal wall may be broken down at once. Prepare to puncture the cyst through the wound at the most depending and fluctuating point with a full-sized trocar and canula, and at the moment of puncture an assistant seizes the cyst wall, either with a vulsellum, in order to maintain it at the wound, and to prevent the escape of its contents into the cavity of the abdomen, or Mr. Wells's trocar and claws may be used; at the same time another assistant, standing on one side, compresses the walls of the abdomen, with a hand placed on either side, in order also to prevent extravasation and to favour extraction. During the process of evacuation the tumour may gradually be drawn out of the abdomen through the wound, and the cyst may be incised to facilitate the more rapid escape of contents, while smaller cysts may often be emptied through the large one with the trocar *in situ*. False membranes must be torn across, and adhesions to viscera, if they cannot be readily

detached, must be liberated by isolating the adherent portion of cyst with the knife and leaving it attached. The tumour having been withdrawn, its pedicle is to be looked for, but before severing the latter, either fine strong whipcord ligature is to be passed through its centre to secure each half, or a carefully adjusted clamp may replace the ligature. Whichever mode be adopted, a strong pin should transfix the pedicle on a level with the ligature, or behind the clamp; so that in the case of hæmorrhage from the divided vessels of the pedicle, or unexpected partial retraction of the same towards the abdomen from the grip of the clamp, the bleeding vessel may be readily secured, and hæmorrhage into the abdominal cavity be avoided. In consequence of the variable density of a broad pedicle, it will be difficult to compress it equally throughout, and therefore more or less risk of the thinner portions slipping back into the abdomen is incurred. (I have known this accident to happen, and the patient to die of hæmorrhage.) When the clamp is used, the cut margin of the pedicle may be seared by the actual cautery, in order to avoid the possibility of hæmorrhage, and as an antiseptic agent. The pedicle secured, the edges of the wound must be carefully adjusted and be kept in apposition, either by sutures or pins, one of the pins being made to transfix the pedicle in order to keep the portion, which is either anterior to the ligature, or included in the clamp, outside of the abdominal cavity.

## TREATMENT OF THE PEDICLE.

Some difference of opinion still exists respecting the mode of dealing with the pedicle, and probably no one plan is applicable to all cases. As a general principle, it will be proper no doubt to tax the reparative powers as little as possible, and with that object in view, to keep the pedicle outside the abdomen at the lower angle of the wound, no matter whether it has been secured by clamp or by double ligature, or seared by the cautery, or the vessels tied separately. Either of these methods may be adopted in accordance with the fancy of the operator, provided the pedicle be long; but, should it be short, to keep it fixed in the wound would cause an undue and dangerous degree of tension to be exercised on the uterus and its attachments, and in that case the pedicle should be firmly tied with a fine whipcord ligature, the latter cut short, and the whole dropped back into the pelvis. The wound can then be closed throughout its whole extent. With regard to hæmorrhage from adhesions, the better plan, as a rule, is to secure the vessel with a fine ligature, and bring the ends out at the wound, unless the thread be altogether dispensed with, and torsion be substituted. In exceptional cases the ligature may be cut short, or the hot iron may be employed.

## CÆSARIAN SECTION.\*

The bladder having been emptied by a catheter, the patient should be placed on her back, with her head comfortably supported on pillows, and the legs hanging over the end of the table, and suitably sustained. The operator takes his position between the thighs, and a competent assistant is stationed on either side of the patient to fix the uterus, to support the abdomen, to prevent the escape of intestines, and the passage of blood, &c., into the peritoneal cavity. An incision, rather longer than a hand's-breadth, divides the anterior abdominal wall in the mesian line between the umbilicus and the pubis, somewhat nearer the former than the latter. As soon as the peritoneum is reached this should be cautiously severed, after a wound has been made in it sufficiently large to admit the first joints of two fingers of the left hand, to be introduced both to defend the uterus from the knife or probe-ended bistoury, and to serve as a director. A similar incision is to be made in the uterus, and as quickly as possible, due care being taken to avoid wounding the foetus. The womb is now opened, and blood may be flowing freely from its sinuses. To fix the uterus, and to prevent either egress of bowel or ingress of blood, it is advised that an assistant hold forward this organ by hooking the forefingers, one

\* See "Lectures on Obstetric Operations," p. 320, by R. Barnes.



under each angle of the wound in it. The operator now ruptures the membranes with his hand, and seizing the foetus by the feet, extracts it. The placenta must be detached either before or after the withdrawal of the foetus, in accordance with its relation to the wound. To favour the arrest of hæmorrhage, the uterus should be encouraged to contract by firm compression with the hand; ice may be placed in it, and the solution of perchloride of iron may be applied to the bleeding surfaces. To secure a ready escape of subsequent secretions, a free passage to the vagina should be made by the introduction, from within the uterus, of a probang or catheter through the os. Sometimes the uterine wound gapes, and then a suture must be used to close it. Dr. Barnes, in the "Obstetrical Transactions," vol. xii., p. 364, describes and figures a suture for this purpose, and the reader should study it.

The most simple form of suture\* would be that which included the edges of both the uterine and abdominal wounds. Mr. Spencer Wells, in a successful case, used an uninterrupted suture, leaving one end hanging out through the cervix and vagina, and by pulling on this latter end the suture came away after several days. I presume the piece of silk to be used for this uninterrupted suture would be best introduced from the vagina by the aid of the

\* See Dr. Braxton Hicks on Suture of Uterus, "Obstetrical Transactions," vol. x., p. 48.

probang previously passed to open up the os. The stitches would then be put into the uterus from below upwards. It is undesirable to use chloroform in this operation from fear of vomiting. Either the ether spray or nitrous oxide gas should be preferred.

#### REMOVAL OF TUMOURS.

In the case of a tumour of a doubtful nature, it will be well to adopt *exploration* (p. 160).

Tumours may be removed by the knife with or without portions of integument covering them, either by a simple incision along the centre and long diameter of the growth, dividing the soft parts and then reflecting them so as to lay bare the mass and favour enucleation; or by any other form of incision which may facilitate removal, or by two incisions including a portion of integument which may be either firmly adherent, implicated by the disease, or too abundant.

*Removal of Integument.* — Healthy integument, covering and stretched over a tumour, is often removed with the growth, lest too much skin should remain to cover the wound. Speaking generally this supposition is erroneous, and soon after an operation so performed, the integument is found to be retracted and the wound gaping, or sutures excite ulceration, and when removed the edges separate, delaying the cure, till at length a large cicatrix or an indolent

ulcer results. This accident is especially liable to happen when a tumour, together with healthy integument, is removed from over a prominence, such as the shoulder.

As a rule, healthy integument should not be cut away unless it cover a *natural* tumour, such as the mammary gland, which organ being removed, the whole of the integument would be more than sufficient to cover the wound, and in the following proportion. Let the cutaneous surface represent the arc of the segment of a circle, and the deep surface the chord of that arc; the difference in length between the arc and its chord will represent the extent of integument which may be removed as an equivalent to the tumour also excised. Thus, if arc = 15 inches and chord = 10 inches, the difference of 5 inches will represent the width of integument at the centre of the mamma which may be removed, the width being gradually diminished towards the circumference. In the case of enlargement of the mammary gland by disease, the extent of integument to be removed must be in proportion to the natural prominence of the healthy rather than of the diseased gland.

To excise the *mammary gland* or other tumour, one or more incisions may be employed, as in Fig. 129, *a a*, including an oval portion, or *a b*, enclosing a semilunar portion of skin; begin the incision at the most depending part, and if more than one, the more depending incision first, that the blood may flow

away and offer no obstacle to the ready completion of the operation. To prevent loss of blood assistants




FIG. 129.

should follow the knife closely, compressing the wound temporarily with sponge, and any large vessels with the points of the fingers. The tumour recognised, the skin is to be dissected off, and the dissection will be facilitated by the fingers of an assistant, or by spatulæ, the one seizing the tumour, the other the integument, or hooks and claw-forceps may be substituted. During the dissection, keep the edge of the knife either upon or towards the tumour. Excision effected, examine the raw surfaces to ascertain that the whole mass has been removed, and when the vessels are ligatured the wound may be closed by suture, compress, strapping and bandage; or the operator may prefer to wait two or three hours before closing the wound, lest secondary hæmorrhage

should occur. If possible, place the wound in a state of relaxation, with the raw surfaces in contact to favour rapid union and to prevent oozing of blood or bagging of secretions; let the inferior angle of the incision be uncovered, that secretions may flow out.

#### HARE-LIP.

The principles upon which this deformity is to be remedied, whether single, double, or complicated, are similar, and consist in the attempt to close the fissure or fissures, either by the knife, by mechanical apparatus, or by both. The operation may be performed at any period of life, but that of infancy is preferable, because the healing and nutritive powers being more vigorous, wounds readily close, either by immediate union or by primary adhesion.

*Single Hare-lip.*—In this variety the fissure of the upper lip is on one side only of the median line.

Place the subject either recumbent or in the sitting posture; if a child, it should either be seated on the lap of a nurse, with its body and extremities in a pillow-ease, or it may be recumbent with its head between the thighs of the operator, who is seated, and the legs resting on the lap of an assistant, also seated opposite to the operator. Commence the operation by detaching, more or less, but without injury to the true frenum, if possible, the lip from the gum on either side of the fissure in order to favour approximation of the edges of the fissure; seize the free



margins of the cleft consecutively with a pair of claw forceps, and while an assistant holds the lip “taut” with his finger and thumb—both to assist the action of the knife and to compress the coronary artery, the operator pares the borders of the fissure by cutting away its margin, beginning at the angle and terminating at the free margin of the lip; thus an inverted **A**-shaped fissure results (Fig. 130), and its edges are to be brought into contact and to be so main-



FIG. 130.



FIG. 131.

tained by two or more pins and the twisted suture; also it will be well to insert an interrupted suture at the red margin of the lip.

*Double Hare-lip* (Fig. 131).—The steps of the operation will be similar to those given above, and usually both fissures may be closed at one time. In all cases be sure to vivify the angle of the fissure and to carry the incisions through the thickness of the lip itself, rather than too near the margin of the fissure. Besides the inverted **A** incision, other forms may be employed, according to the fancy of the surgeon and the requirements of the case.

*Complications*, such as an absence of the columna nasi, a projection of one or both incisor bones, cleft hard palate, &c., &c., must be remedied by the ingenuity of the surgeon and of the dentist.\*

Collis's Method.†—The rules for the operation are—

1st. Never to interfere with the true frenum. It is not only unnecessary, but most pernicious.

2nd. Freely to divide all false frena, and if the alar cartilage is misplaced, let the incisions separate it freely, so that it may be fairly drawn into its proper place.

3rd. Never to attempt to close the lip, so long as the intermaxillary bone is misplaced to any extent.

4th. To preserve and utilize all the parings. They are all wanted, as they all have their proper place.

5th. To use interrupted sutures, and discard all pins or needles as far as possible.

6th. To leave the line of union exposed, using no dressings or plasters for some days.

The chief peculiarity of the operation consists in preserving all the parings; on the one side to make the lip thick, on the other to increase its depth.

\* See Paper by Sercombe, in Trans. Odont. Soc.

† The *Æsthetic Treatment of Hare-lip*. By M. H. Collis. *Dub. Quart. Journ.*, May, 1868, p. 292.

## CLEFT PALATE.

*Staphyloraphy* may be performed at almost any period of life by the aid of Mr. Thomas Smith's gag. The object of the operation is to close an abnormal fissure in the median line of the soft palate. Each half of the velum is under the influence of five muscles, four of which when in action tend to abduction, and consequently to separate the one portion from the other when a median fissure exists. To maintain the part at rest and ensure approximation of the edges of this fissure, one or more of these abductors must be divided. (Fergusson.) Of these muscles the levator palati exercises the most influence on the velum, and next to it the palato-pharyngeus; the tensor palati and palato-glossus are of minor interest. In the normal palate, and when looking through the mouth, the position of the palato-glossus and of the palato-pharyngeus can be readily detected, the former forming under cover of mucous membrane the anterior pillar, the latter, the posterior pillar of the fauces: between these two is the tonsil. The position of the levator and of the tensor palati cannot be so easily seen, but a knowledge of their action upon the velum and of their origin, insertion and consequent direction, will serve as a guide to their locality. Taking origin at the base of the skull, they pass from above downwards and inwards towards the mesian line, the levator being posterior to the tensor.

The levator palati muscle is more superficial posteriorly, and for that reason some prefer to divide it from behind forwards and without making a button-hole in the velum.

Fig. 132 is a posterior view of the muscles of the




FIG. 132.

palate after that the pharynx has been opened behind in the mesian line. A is the body of the sphenoid bone with the posterior nares below ; H is the tensor palati muscle, and *b* the hamular process of the internal pterygoid plate ; i is the levator palati muscle, and B its tendinous expansion ; L is the palato-glossus muscle ; M is the palato-pharyngeus muscle, the

supero-posterior fibres of which have been removed ; other adjacent parts are also seen.

*Operation.*—Let the patient be either seated or recumbent, with the face opposite to a good light, and the operator either in front of or by the side of the subject. An assistant should stand behind and steady the head. Instruments requisite are—Fig. 133, *a*, the



FIG. 133.

knife, the blade of which is very short and at a right angle to the handle ; *b*, the claw-forceps ; *c*, a double-edged knife ; *d*, a porte-aiguille ; *e*, round-pointed scissors. Seize the uvula with the forceps and draw it forwards so as to put the palato-pharyngeus on the stretch, and then with the scissors sever the muscle transversely to the extent of a quarter of an inch ; the palato-glossus may be similarly treated. Still holding the uvula, pass the blade of the knife (*a*) back through the fissure, and having placed it upon the posterior surface of the velum, cut, as it



were, forwards into the substance of the palate in a direction downwards and outwards, just internal to the hamular process of the internal pterygoid plate, which can be felt through the mucous membrane just behind the last molar tooth. Divide the levator palati on both sides, and their section may be recognised by an alteration in the shape of the fissure and their inability to contract.

Fig. 134 shows the appearance of a palate prior to the division of muscles, A B indicating the pillars of the fauces with the tonsil between them.




FIG. 134.




FIG. 135.

Fig. 135 shows the alteration in the shape of the fissure after section of muscles, c d marking the lines of division.

With a double-edged knife (*c*) pare the margin of the fissure and introduce two or more sutures with the *porte-aiguille* or other means, and fix them loosely to allow for swelling, with the *slip knot* or *double reef knot*. The thread is to be introduced on

one side, first from before backwards, one end of it being seized with forceps and held firmly in the fissure, while the needle is withdrawn by the way it went and detached from the thread; the needle must be again threaded with the end of the ligature appearing through the fissure, when it is to be passed through the opposite side of the cleft from behind forwards, and then the suture may be fixed by the slip knot and the simple knot. Bleeding during the operation must be checked by gargling the throat with iced water, and if the levatores palati be divided *after* section of the pillars has been effected, frothy sanguineous sputum will not interfere with division of the latter. Instead of dividing the levator palati from behind, some surgeons prefer to cut through the whole thickness of the palate from before, as in Fig. 136.




FIG. 136.

## FISSURE OF HARD PALATE.

Both soft and hard palate may be closed at one sitting; but success is more likely to attend a separate operation for either part. Hæmorrhage is often very free, and the vitality of the tissues detached from the hard palate is often compromised along the free border if the whole be done at one time.

The object of the operation is to detach the soft tissues covering the hard palate, so that, when these drop towards the tongue, their edges shall come into apposition, unite, and form a roof to the mouth. For the purpose, various raspatories, of different curves and sizes, sharp and blunt, are required. The free margin is first incised, and then a sharp raspatory is run along between the soft and hard tissues, so as to separate the one from the other, the instrument scraping the bone with a view of detaching some periosteum with the flap. Now a blunt instrument may be used, especially where the bone is rough, and where the vessels come out to supply the palate until the base of the alveolus is reached, and the halves fall together in the mesian line. Sutures having been introduced, the operation is completed. The operation is tedious both for patient and surgeon, although chloroform may be used more or less.

#### ABSCISSION OF TONSIL.

In the absence of a guillotine the tonsil may be excised by the knife. The surgeon may stand either behind or in front of the patient, and, seizing the enlarged organ with a pair of claw forceps, cuts away a portion of the gland in a direction from below upwards and inwards parallel with the pillars of the fauces. The knife employed should be a

probe-pointed bistoury with a cutting edge near the point only ; or, if an ordinary bistoury be employed, the posterior half of the blade should be rendered useless by wrapping a strip of lint around it, so as to avoid the possibility of wounding the upper lip. Avoid pulling the tonsil inwards with the forceps.

#### PLUGGING THE POSTERIOR NOSTRIL.

By Belloc's instrument, the use of which is shown at Fig. 137, A, and which somewhat resembles a




FIG. 137.

catheter, along which a piston can be worked, to the extremity of which a spring is attached and can be protruded at pleasure ; the end of the spring is per-

forated so as to admit of the passage of a thread attached to the plug (B).

In the absence of Belloc's instrument, an elastic catheter will suffice. Pass the catheter backwards along the floor of the nostril into the pharynx, introduce the finger through the mouth and bring forward into that cavity either the extremity of the catheter or a thread previously attached to the catheter, and attach the thread to the double ligature which holds the plug. The plug should be of soft sponge, about one inch in length and half an inch in width, and to its middle a double ligature should be made fast. The catheter must now be withdrawn as it came, carrying with it one end of the double ligature and plug; but the other end of the ligature should hang out of the mouth, to be used to pull down and remove the plug when no longer required. The placing of the plug may be assisted by the finger carried above the velum as the catheter is withdrawn. The posterior plug adjusted, the end of the double ligature will protrude at the anterior nostril, when another plug may be adjusted in front by this same ligature, and so the two plugs afford mutual support.

To remove the posterior plug, cut the ligature and take away the anterior plug; then pull upon the single ligature which protrudes at the mouth, and assist traction if necessary with a catheter passed back against the plug along the floor of the nostril.



## CATHETERISM OF NASAL DUCT.

A probe may be introduced into the nasal duct, either along the lacrymal canal, or from the nostril.

To pass the sound *from the nostril* the instrument should have a shape somewhat similar to that of the italic letter *s*; and the operator, facing the subject and holding one end of the probe with his finger and thumb, should pass the other end, oiled and point downward, back along the floor of the nostril to the extent of about an inch. The end of the instrument will now correspond with the inferior turbinated bone, under cover of, and near to, the anterior extremity of which is the inferior opening of the duct; by slight rotation of the probe or supination of the hand, the extremity of the instrument will also get under cover of the inferior turbinated bone, when it should be carefully brought forward towards the anterior nostril, till its progress be impeded by the ascending process of the superior maxillary bone; it is now opposite to the opening of the duct, and by depressing the handle gently, will probably enter the canal.

To pass the sound *from above*, slit up the lacrymal canal with a pair of scissors, one blade of which must have been passed through the punctum along the canal in order to do so. By this means a gutter is formed, and along it the probe is to be carried, and to be introduced into the lacrymal sac, and then

into the nasal duct by gradually raising the probe from the horizontal to the vertical position, and then directing it with gentle pressure downwards and slightly backwards and outwards.

Some prefer to lay open the lacrymal canal by slitting it up with a fine knife along a small grooved probe introduced at the punctum.

Catheterism may be repeated twice or thrice weekly.

#### CATHETERISM OF THE EUSTACHIAN TUBE.

The cartilaginous extremity of the Eustachian tube is situated in the pharynx posterior to the nose, about on a level with its outer wall and just above the inferior turbinated bone. To introduce the Eustachian catheter, stand in front of the subject and pass the curved extremity of the instrument, oiled and point downwards, along the floor of the nostril of the affected side to the posterior nasal aperture, and then either by rotation of the catheter or by supination of and depressing the hand, the point of the tube will be directed upwards and outwards, and will probably enter the canal.

Fig. 137 shows the instrument (c) traversing the nostril and entering the tube (D).

## REMOVAL OF TONGUE.

The whole or portion of the tongue may be removed either by the knife or by ligature, or by the heated wire. To remove a portion of the anterior half of the tongue, the organ should be drawn out of the mouth and be so maintained temporarily, either by a ligature passed through the healthy structure, or by claw-forceps, held by an assistant while one of the above methods for removal is employed. When the knife is used, any vessel may either be ligatured or be touched by the actual cautery. The whole organ may also be removed, either by the knife, by ligature, or by the *écraseur*.

By *ligature*.—Incise the integument to the extent of half an inch above the *os hyoides* and in the median line of the neck; and through this wound pass into the mouth between the side of the tongue and the base of the lower maxilla, a *porte-aiguille* armed with a strong double ligature; retain the ligature in the mouth and cut the loop, but withdraw the needle as it came, thus leaving two ends of ligature in the latter cavity, and two depending at the wound in the neck. Reintroduce the needle on the other side, but without a ligature; and now carry one ligature already in the mouth across the *dorsum* of the root of the tongue and put it through the eye of the needle while the other ligature is passed under the tip of the tongue in front of the *frænum*, and is also put through the

eye of the needle; the needle thus threaded should be withdrawn at the wound in the neck, carrying the ends of the two ligatures with it, thus adding two to the two already depending at the wound. The opposing ends must be firmly tied together, when the organ will be strangulated. The knots must be tightened daily.

*Excision.*—Let the subject be seated, and the head be well supported from behind. The operator standing in front, incises the lower lip down to the bone and the integument as low as the hyoid bone in the mesian line, and having extracted one or two incisor teeth of the lower jaw, severs the symphysis either longitudinally or angularly (Fig. 138, A, Sedillot). Forcibly separate the halves of the jaw; and having seized the tongue with a pair of strong claw-forceps,




FIG. 138.

drag the organ forwards and downwards, and separate it from its attachments with a straight round-pointed

bistoury. By division of the lower jaw, ligatures or the actual cantery can be more rapidly employed to check hæmorrhage, and the *angular* section of the bone favours apposition of the surfaces and rapid union.

By *écraseur* (Chassaignac).—I have seen M. Chassaignac remove the tongue, and in the following manner. The patient was seated in a chair, and depending from the throat through a small wound in the mesian line above the os hyoides were the two extremities of a *tube à drainage*. This tube had been introduced some days previously in order to form a sinuous channel for the passage of the chain of the *écraseur*. The chain was to replace this tube, and one end of the former was accordingly attached to one extremity of the latter, and then pulled upwards through the wound in the neck, passing between the side of the tongue and the side of the lower jaw to enter the mouth, now carried over the dorsum of the tongue and down between the opposite sides of the tongue and lower jaw, when it made exit at the wound in the neck, and was attached to the *écraseur*. Thus the tongue was inclosed perpendicularly by a loop of the chain. The shaft of the instrument was now pushed up so as to tighten the chain and constrict the tongue, and the operation of crushing begun. As soon as the tongue was severed longitudinally, the loop of the *écraseur* was cast over the almost separated organ, and the attachments of it to the back of the symphysis were severed in a similar



manner. The patient appeared to suffer exceedingly at the moment of constricting the tongue, but exhibited few signs of pain during the work of separation.

Sometimes a puncture, through the floor of the mouth, just in front of the hyoid bone, large enough to admit the passage either of the chain of the écraseur or of the ligature, will suffice.

*Regnoli's method.*—A semicircular incision is made under the base of the jaw through the integument, avoiding, if possible, wounding the facial arteries. From the centre of this a second incision must divide the skin from the point of the chin to the level of the hyoid bone. Two lateral flaps are now to be dissected back and then the floor of the mouth is to be opened, and the attachments of the tongue are to be divided, while the organ itself is held and manipulated by strong claw-forceps.

The tongue can be more readily removed, and its vessels secured, by Sedillot's method.

#### THE EYE.

*Extirpation of the globe.*—Place the subject recumbent, and expose the globe with a wire speculum; and by means of a pair of forceps and small curved round-pointed scissors, circumsise the conjunctiva near to the margin of the cornea; with a blunt hook take up the tendon of each rectus muscle *seriatim*,

and sever it with the scissors close to the globe; now push the lids back into the orbit so as to bring forward the eyeball; introduce the scissors into the apex of the orbit, and divide the optic nerve, and after that sever the tendons of the oblique muscles and any remaining fascial attachments, till the eye be liberated. Fig. 139 shows the relation of the




FIG. 139.

tendinous insertions of the muscles of the eye to each other.

*Strabismus, convergent* for example (sub-conjunctival method) (Critchett).—Place the subject recumbent, and expose the globe by separating the lids with a speculum. The lower border of the internal rectus muscle is on a level with the inferior border of the cornea; seize, therefore, the conjunctiva with a pair of small claw-forceps at a point midway between the cornea and the caruncula lacrymalis, and on a level with the lower border of the cornea, and open it with a round-pointed scissors sufficiently only to admit of the entrance beneath it of the scissors themselves; divide, also, in a similar manner the sub-conjunctival fascia, till the pearly

sclerotic be reached ; now introduce the blunt hook through the opening in the sub-conjunctival fascia and pass it between the sclerotic and the rectus, and while thus placed, with the convexity of the blunt hook looking forwards so as to remove the muscle from contact with the globe, introduce the scissors through the fascial opening and divide the tendon between the hook and its sclerotic attachment from below upwards. The hook will readily pass to the margin of the cornea while under cover of the conjunctiva *as soon as* the muscle has been severed ; some of the upper fibres of the muscle are liable to escape division, but can be readily brought within the range of the scissors by redipping the hook under them. By simply making an aperture into the conjunctiva so as just to admit the point of the scissors only, rather than by practising division of the conjunctiva to a similar extent as the muscle itself, sinking of the caruncula, increased prominence and undue eversion are avoided.

*Artificial pupil, by Iridectomy.*—Place the subject recumbent and expose the surface of the globe by the speculum, and having determined the point at which the operation is to be performed, incise the cornea with a spear-shaped knife, without wounding the iris, at its junction with the sclerotic sufficiently to admit either the point of a fine pair of forceps or a fine blunt hook, with which a corresponding portion of iris is to be withdrawn through the wound in the cornea, and to be then cut off by a pair of scissors.

A gap is thus formed in the iris by which the rays of light can enter the eye.

By *Iridodesis* (Critchett).—Open the anterior chamber by puncturing the cornea by means of a broad needle, then lay a loop of fine silk upon the eye at the seat of puncture; introduce a fine blunt hook through the loop and through the wound in the cornea into the anterior chamber, and entangle the pupillary margin of the iris; draw it out by means of the hook, and then let an assistant tighten the loop so as to strangulate the extracted portion of iris. In a few days the knot, together with the enclosed portion of iris, will separate, leaving it adherent to the cornea. This operation leads to the formation of a smaller artificial pupil than iridectomy does, and preserves the circular fibres of the iris and the contractility of the original pupil.

*Staphyloma removed by abscission* (Critchett).—Expose the globe by a speculum. Traverse the base of the protrusion with three or four small curved needles armed each with a fine silk ligature (somewhat after the manner of treating a *nævus*), and while the needles are thus *in situ* remove by two semi-elliptical incisions the projection inclosed by them; then remove the needles *seriatim* and substitute for them an equal number of interrupted sutures by means of the threads referred to, and by which the edges of the wound are to be maintained in contact. The semi-elliptical incisions should pass just within the points of entrance and of exit of the

needles ; and to favour ready approximation of the margins of the wound, may be prolonged on either side, beyond the staphyloma, into the sound structures. Upon this diminished but still existing globe, an artificial eye can be adapted with less perceptible deformity than when the entire eyeball is extirpated. By this method of operation the risk of hæmorrhage into the globe, or of suppuration of its cavity, is materially diminished ; the greater part of the vitreous humour is retained, and the approximated edges usually unite by *immediate union*.

*Cataract, hard, extraction of lens.—Flap method.*—Chloroform should not be administered. Place the subject recumbent, and stand behind to operate with the right hand upon the right eye, but in front and on the right side to operate on the left eye if not ambidexter. The sound eye may be covered or not by a bandage during the operation. To expose the globe an assistant depresses the lower lid with the



FIG. 140.




FIG. 141.

points of one or two fingers, Fig. 140, *b*, and fixes



it so depressed, but not everted, upon the margin of the orbit, and without exerting the least pressure upon the globe. The index and middle fingers of the operator's left hand are employed to draw up and to fix the upper lid, and to steady the globe without making undue pressure upon it. The operation is begun by forming a flap of the cornea, either the upper or lower half, according to the fancy of the surgeon; the upper half is usually preferred. Fig. 141, *a*, shows the mode of holding the knife, the little finger being allowed to rest upon the head of the subject to steady the hand. A Beer's knife is made to pierce the outer margin of the cornea on a level with the centre of the pupil, and having entered, is passed steadily across the anterior chamber in front of the iris, making exit through the cornea at a corresponding point on the inside (*b*), and having *nearly* completed the semilunar flap, is to be withdrawn so as to complete the flap during the withdrawal; allow the lids to close and wait half a minute; separate the lids as before, and carefully introduce under the flap and through the pupillary aperture the point of the curette, avoiding the iris, and tear the capsule of the lens; this done, withdraw the curette, avoiding the iris, and make gentle pressure upon the sclerotic just external to its junction with the cornea, with the spoon of the curette, in order to dislodge the lens, which having passed out at the wound, the operation is completed. Fig. 142, *a b*,

shows the curette behind the flap of the cornea. Fig. 143, *a b c*, shows the mode of forming the flap from the upper half of the cornea.




FIG. 142.




FIG. 143.

*Linear method.*—Chloroform having been administered, separate the lids by a speculum. Fix the globe by a pair of toothed forceps; introduce a broad needle with a cutting edge at the outer margin of the cornea at a point corresponding to the upper border of the pupil; traverse the chamber so as to emerge at the corresponding point on the opposite side, and divide the cornea between these two points close to the sclerotic border so as to form a slightly curvilinear section. Iridectomy must now be performed. The capsule must next be freely opened with the curette, and the cataract made to escape by means of gentle pressure from below, as in flap-extraction.

*Cataract, soft, solution of lens.*—The pupil having been widely dilated with atropine, a fine needle must be introduced through the cornea into the anterior

chamber towards the centre of the pupil. The capsule of the lens must then be lacerated and the surface of the lens broken up to such an extent as to expose it freely to the solvent action of the aqueous humour. In from six weeks or two months it is generally found necessary to repeat the operation; sometimes, even more than once, until the entire lens is absorbed, and a clear black pupil remains. In this operation care must be taken not to break up the lens too freely, or to bring any large fragments into the anterior chamber.

*Entropion, or inversion of the lid.*—In the case of the *lower* lid (spasmodic entropion) a fold of skin should be removed by means of a pair of scissors close to the tarsal border to such an extent as to retain the lid in position without producing eversion. The amount to be removed is estimated by pinching up the skin with a pair of forceps, and observing the effect upon the lid. Having removed the skin, the fibres of the orbicularis thus exposed should be also cut away. The edges of the wound are to be united by fine sutures.

In the case of the *upper* lid, the most effectual method is the extirpation of the entire row of lashes. A bone spatula should be introduced beneath the lid, so as to put its border on the stretch. An incision must then be carried along the edge of the lid behind the roots of the lashes from one canthus to the other, and to such a depth as to separate the bulbs of the lashes from their tarsal bed. Another

incision parallel to the former must be carried through the skin about one-eighth of an inch from the tarsal border, and the portion thus included with the lashes and their bulbs attached must be removed with scissors. The wound is allowed to heal spontaneously.

*Blepharoplasty.*—The eyelids are often rendered useless or are destroyed, either by disease or injury, and various plastic operations have been recommended to remedy the deformity, such as the following, indicated at Fig. 144, for the restoration of the




FIG. 144.




FIG. 145.

lower lid :—The dark triangular space ( $abc$ ) is a raw surface, from which cicatricial tissue, the result of burn, has been removed, and is to be replaced by a flap ( $bde$ ), dissected off the cheek, and to be maintained in its new position by fine sutures; or, at Fig. 145, in which two oblique incisions ( $acd$ ,  $bcd$ ) have been made to inclose a V-shaped portion of integument; this flap ( $acb$ ) is to be dissected up to an imaginary base ( $ab$ ), and to be maintained in its new position by pins and sutures.

The upper lid may be replaced by integument taken from the temple or forehead, as shown in Figs. 146 and 147.



FIG. 146.



FIG. 147.

*Rhinoplasty.*—The nose, too, may be replaced by a portion of integument taken from the forehead, as shown at Fig. 148. A large flap of integument (*a*) is to be marked out and dissected off the forehead towards the root of the nose, at which point it is to be twisted on itself but without strangulating the pedicle (*b*), in such a manner that it may fall over the nasal aperture, to the margins of which, previously pared, its edges are to be attached by suture; the portion of integument intended to replace the columna nasi must be fixed by suture to the centre of the upper lip, and the anterior nares



FIG. 148.



are to be kept patent by pieces of elastic catheter, *c c*, introduced on either side of the columna.

#### GENITO-URINARY ORGANS.

*Phymosis treated by circumcision.*—Introduce a probe between the prepuce and glans penis to ascertain that no adhesions exist, and if they do exist, to tear through them; endeavour to uncover the glans by drawing back the foreskin with the finger and thumb, and as soon as the line of junction between the mucous lining of the prepuce with the skin is seen, seize the extremity of the foreskin with a pair of forceps, Fig. 149, and draw it forwards; now embrace the prepuce with the blades of dressing forceps anterior to the glans, and sever the former anterior to the dressing forceps with one sweep of the knife. As soon as the forceps are removed, the skin will become retracted, leaving the mucous membrane still about the glans; slit up this membrane longitudinally as far as the corona, when it may be turned back, and its edge will come into apposition with the




FIG. 149.



FIG. 150.

circular wound in the skin. The operation is com-

plete; but in the adult it will be well to introduce a few interrupted sutures, Fig. 150, or better still the *serres fines*, Fig. 13. Slight adhesions of the mucous membrane to the glans may be torn through with the thumb-nail.

*Another method.*—Unless care be taken, more skin and less mucous membrane than is desirable will be removed, because by reason of the anatomical conditions, the operator is able, as it were, to draw upon the whole extent of the skin of the *penis*, but only upon the mucous membrane lining the skin anterior to the corona; again, the glans being longer anteriorly than posteriorly, and the prepuce being supported posteriorly by the frænum, a greater length of foreskin should be removed from the anterior surface.

With these objects in view, discover, as above indicated, the junction of the mucous membrane with the anterior border of the skin of the prepuce, and while holding this margin with a pair of forceps, introduce through the preputial aperture (and not into the urethra) the point of a long needle protected by a picce of bees'-wax, carry it along the upper surface of the glans, and opposite the corona pierce the foreskin and liberate the point of the needle; now take hold of the prepuce with the dressing forceps placed behind the needle, but in front of the glans, and including the whole circumference of the free margin of the prepuce, but less in length posteriorly than anteriorly, cut away the parts anterior

to the forceps. Complete the operation by uniting the cut edges of mucous membrane and skin. Twist or ligature any bleeding vessel to avoid secondary hæmorrhage.

By *simple incision*.—Introduce a director between the prepuce and glans down to the corona, either on the upper or under surface, and slit up the former longitudinally with a bistoury. This mode is useful in order to expose chancre or other disease. It must be remembered that should *soft* chancres exist, the new wound will in all probability become inoculated and take on chancreous ulceration; should an *indurated* chancre be present, such result will not be.\*

*Amputation of the Penis* (Hilton).—Introduce if possible No. 12 elastic catheter into the urethra, so as to define the extent of the corpus spongiosum; let an assistant draw the integument of the organ towards the pubis, that sufficient may be left to cover the wound, and then hold the body of the penis firmly between his finger and thumb, in order to compress the vessels. The operator defines the corpus spongiosum, and at the intended point of amputation transfixes the organ with a narrow-bladed scalpel, so as to separate at this point the corpus spongiosum from the corpora cavernosa; the edge of the knife must now be turned up, and be made to cut its way out by severing the corpora cavernosa; this done, these bodies are to be dissected off the

\* Ricord's "Lectures on Chancre," translated by Maunder.

corpus spongiosum in a forward direction to the extent of a quarter of an inch, and the catheter being now withdrawn, the amputation is completed by dividing the corpus spongiosum to the above extent anterior to the corpora cavernosa. The vessels having been ligatured, the projecting portion of corpus spongiosum is to be slit up longitudinally, so as to form two or three flaps, the borders of which are to be attached by suture to the margin of the integument. The advantage of this over the ordinary mode of amputation (by one sweep of the knife) is, that the orifice of the urethra is kept patent, and the tendency to contraction avoided.

*Hydrocele. Tapping.*—The testis is usually seated behind the distended tunica vaginalis, but occasionally it is in front of the swelling. The position of the testicle having been ascertained, the operator takes the tumour into the palm of his left hand, and makes tense the integument covering the lower part of it by pushing skin, testicle of opposite side, and penis, towards the pubis; this done, and avoiding any large vein which may be seen, he plunges a trocar and canula, oiled, in an upward direction, and not forgetting the locality of the testis, into the bottom of the sac, but rather anteriorly. As soon as resistance ceases, the trocar is to be withdrawn, and at the same time the canula is pushed into the tumour up to its hilt, and is to be so left till the tunica vaginalis be evacuated. The canula withdrawn, the operation is completed.

To *inject* the sac, let the canula remain after that the contents have been drawn off, and through it the intended fluid may be introduced with a suitable syringe. The canula should be well in the sac, lest the fluid intended for the interior of the latter escape into the areolar tissue of the scrotum; and, if desired, the fluid injected may be allowed to flow out also by the canula, and the latter is then withdrawn.

*Varicocèle.*—By *écraseur*. An assistant should hold aside the vas deferens with his finger and thumb; then the dilated veins and small fold of skin of scrotum are to be taken up by the finger and thumb of the operator, while a long needle is made to transfix the fold of scrotum, passing, at the same time, in front of the vas, but behind the veins; a second needle is now introduced in a similar manner, but at an angle to the first, and the veins being thus isolated the loop of the chain of the *écraseur* is to be passed behind the needles (after the manner of treating a *nævus*), and the lever worked every half-minute till the circumscribed part be removed. Collodion may be applied to the almost invisible wound.

By *ligature* there are various methods. The most simple consists in passing a needle, armed with a strong ligature, through the scrotum and between the veins and vas deferens; then the needle must be reintroduced through the aperture by which it made exit; but this time it must carry the ligature



between the veins and scrotum, making exit by the opening at which it had previously entered; thus the veins are inclosed by a loop of ligature, both ends of which hang out at one aperture, and include no portion of skin; a knot tied tightly strangulates the veins, which gradually become severed by ulceration.

When a ligature is employed, some means should be adopted by which the loop inclosing the veins is constantly becoming smaller and smaller; otherwise, some time will elapse before the ligature is cast off. Fig. 151, *a*, represents a varicose condition of the veins of the testis; *b c* are ligatures, one in front of, the other behind these vessels; *d* is the vas deferens behind both ligatures. The ligature may be of wire, and this can be twisted daily; but the process is a slow one, and is attended by suppuration.




FIG. 151.

By *subcutaneous section*.—Two pins are to be passed through the scrotum, between the veins and the vas deferens, about an inch apart. Opposite to each pin the skin is to be protected from pressure, either by a bit of cork or cardboard, and then a figure 8 suture is to be cast around each pin, so as to compress the veins firmly, and arrest the circulation through them. Thus, about an inch in length of the diseased veins is

isolated by the two needles. A fine knife must now be introduced carefully, having the veins in front and the vas behind it, and the veins are to be cut across between the needles subcutaneously. After the lapse of forty-eight hours the pins may be removed. To secure section of the veins, the cord of the affected side should be extended by making traction upon the testicle while the knife glides to and fro, and resistance is also offered by pressure with the thumb upon the skin, covering the isolated vessels.

*Castration.*—Place the subject recumbent, and shave the part, if necessary. Take the testicle into the palm of the left hand, and make tense the skin along the anterior surface of the tumour; make a longitudinal incision along the front of the organ beginning just below the external abdominal ring, and terminating just above the lower end of the testis. By compressing the organ with the left hand it will protrude at the wound, and as soon as the tissues are divided down to the pearly tunica albuginea, and the cord is exposed, the latter is to be seized with a pair of claw forceps and held by an assistant to prevent retraction, while the operator severs it and removes the testicle by dividing any existing attachments. The vessels of the cord—spermatic and artery of vas deferens—must be severally secured, as also any arteries of the scrotum; and as soon as the patient has thoroughly recovered, either from the effects of chloroform or the shock of

the operation, the wound may be closed by sutures, compress, and bandage.

It will be better to defer closing the wound for some hours after the operation, rather than to do so before the circulation is thoroughly established and incur the risk of secondary hæmorrhage. Any portion of integument engaged in the disease must be removed with the testis by means of two semi-elliptical incisions, instead of one incision.

*The Catheter.*—To explore the urethra, place the subject recumbent, with the head and shoulders raised on a pillow, and the thighs also slightly flexed upon the abdomen and abducted. If alive, engage the patient in conversation.

Take a medium-sized metallic catheter or sound warmed, and well oiled, and holding it in the right hand, while the penis is held in the left hand, introduce the curved end of the instrument into the urethra, and allow it to glide towards the bladder almost by its own weight, at the same time elongating the penis upon the sound, so as to avoid the occurrence of any folds in the course of the urethra, which might impede the advance of the instrument. When passing the catheter, the navel should be exposed to view, and be in a line with the penis; the catheter should be parallel with this line, *i.e.*, with the median line of the body; its point should be kept up against the upper surface of the canal, and as it glides towards the bladder the different angles formed by it with the trunk will

indicate the whereabouts of the point: when a right angle is formed, the point is in the membranous portion of the urethra opposite to the triangular ligament; and as the handle passes into the horizontal position between the thighs, the bladder is reached. In the healthy subject, provided that the bladder be not quite empty and contracted, the fact that the instrument is in the bladder may be known by the capability of rotating it with the finger and thumb applied to the handle; the rugæ also may be often felt.

One of the diseases common to the urethra is stricture, in some form or other, consequent either on a permanent or temporary narrowing of the canal, the treatment of which by the catheter requires the most delicate manipulation.

Under the term "Catheterism" various instruments are employed, such as the metallic catheter, the elastic catheter, bougies of various material, and metallic sounds. The curved or metallic catheter or sound has one advantage over the non-metallic and flexible instrument, inasmuch as the point of the former can be guided with more precision in any particular direction; on the other hand, it often becomes a dangerous weapon in the hand of the rash or inexperienced. The successful use of the catheter demands, both of the surgeon and the patient, the utmost patience and forbearance. The practitioner should at the outset explain to his patient, that any hurried attempt to reach the bladder will, in all

probability, be followed by injurious rather than by beneficial results. In many instances, unfortunately, the surgeon, fearing lest his patient should become dissatisfied at an apparent failure if the bladder be not reached on the first or second attempt, inflicts, by his too anxious and forcible endeavour to reach that viscus, a laceration of the urethra, which is liable to be followed by extravasation of urine, the formation of false passages, or both. Doubtless the incautious use of the catheter, rather than the original disease, is the cause of the severe cases of stricture which come before the surgeon.

The surgeon should commence the treatment by an attempt to introduce a medium-sized catheter, and, having failed, let us suppose the existence of a permanent stricture; and to overcome this he should carefully endeavour to pass a smaller and smaller instrument, metallic or otherwise, according to pleasure, until the size is arrived at which will pass through the stricture. Sometimes the instrument will enter the stricture, but will not traverse its whole extent; under these circumstances it should be retained, with gentle pressure, for perhaps ten or fifteen minutes, with the hope of inducing some amount of dilatation and absorption; also, when an instrument has traversed the stricture, it should be left in the urethra for a period of at least fifteen minutes, with a similar object in view.

An instrument of a certain diameter having traversed the stricture, the size of the instrument is to



be gradually increased till No. 9, and certainly No. 12 at most, be reached, and will traverse the stricture with ease.

(Wakley's instruments are very useful in the treatment of permanent stricture. The advantage which they enjoy consists in the absence of the necessity to reseek the aperture of the strictured portion of the urethra when the guide for the cylinders has once traversed the stricture; whereas with the ordinary catheter, one must be withdrawn before another can be introduced, and if false passages exist, the second instrument may enter the wrong channel.)

The frequency with which catheterism should be practised, in an individual case, must depend upon the degree of local and constitutional irritation excited; in one case the attempt may be made on alternate days, in another instance every third day, in a third case once a week.

But the surgeon may fail to reach the bladder by simple catheterism, and must employ other means to aid, such as the application of an escharotic, internal section, external section, or the bladder must be punctured.

By *escharotic*.—Introduce a medium-sized instrument as far as the stricture, and note the distance of the anterior orifice of the stricture from the meatus upon the instrument to be employed to carry the caustic, in order that the operator may know whether or not the caustic be in contact with the constriction. Take a bougie, No. 8 or 9, and scoop out one

extremity so as to form a cup-shaped cavity, into which a piece of caustic potash, the size of the head of a "grandmother's pin," may be pressed just previous to the moment of introduction; oil the bougie, and thus armed, pass it rapidly down so as to bring its extremity into contact with the stricture, and so maintain it for the space of five minutes. One application may be beneficial, allowing the urine to flow in a larger stream than usual, but if necessary the operation may be repeated.

Although the author has, some years ago, employed this method with temporary advantage, he questions the propriety of destroying, to the smallest extent, the lining membrane of the urethra.

By *internal division*.—One of the many urethrotomes invented may be employed for this purpose.

By *external section* (Syme).—This method presupposes the *capability* of passing a small grooved staff *through* the stricture, upon which the intervening structures are to be divided in the mesian line from without. The subject must be in the lithotomy position. The advantage of a staff consists in its serving as a guide to the urethra behind the stricture, into which portion of the canal the knife is to be first entered, and when inserted in the groove, is to be carried forward through the stricture, so as to divide the diseased tissues. An ordinary director is now passed into the urethra through the wound, towards the bladder, while a full-sized elastic catheter is

introduced at the meatus, and having reached the wound, is guided into the bladder upon the director; the latter is then removed, but the former is maintained for four-and-twenty hours, after which it also may be taken out of the bladder. Probably for some days urine will flow, both at the wound and at the meatus; but as the former closes, and indeed for some weeks after the cure appears to be effected, a full-sized catheter must be occasionally passed along the urethra into the bladder.

*Another method*—presupposes the *impossibility* of passing an instrument *through* the stricture. Pass a large metallic catheter down to the stricture, and make prominent its extremity; from without, cut down upon this, and open the urethra anterior to the stricture. Seek the orifice of the stricture, as soon as bleeding has ceased, and, if possible, pass a fine probe or director along the narrow channel as a guide for the knife; if this cannot be accomplished, divide the indurated tissues in the median line in a direction towards the bladder, with the hope of finding the track of the urethra, and while so doing let the patient strain to make water, in order that any dilatation of the portion of urethra behind the stricture consequent on this effort may indicate the line for the incision. The urethra opened, and the indurated tissues divided, the catheter must be carried on into the bladder, and may be there maintained for twenty-four hours, provided that the patient be not intolerant of the instrument, or

urethral fever threaten. Indeed, it is yet to be shown what good, as a rule, a retained catheter can effect in these cases of external urethrotomy.

It is always difficult to find the orifice of the urethra through a wound in its continuity; therefore, before removing one catheter from the bladder, in order to replace it, an ordinary director should be introduced into the canal towards the bladder through the external wound to serve as a guide for the catheter.

A Syme's staff is preferable to an ordinary grooved director, because the thicker portion having been introduced down to the stricture, and the knife having cut the tissues along the groove up to the thicker portion of the staff, divides the stricture with certainty, and nothing more.

*Another method* (Cock).—When attempting to open the urethra in the perinæum, the subject should be placed in the lithotomy position. The patient being so placed, the operator's left forefinger, well oiled, should be passed into the rectum, to ascertain the exact position of the apex of the prostate, and be there maintained; with the right hand a double-edged scalpel incises the median line of the perinæum anterior to the anus, the point of the knife being carried back, with the intention of opening the membranous urethra in the direction of the apex of the prostate, to which latter the finger in the rectum serves somewhat as a guide. As soon as the knife has entered the perinæum it should not

be withdrawn till the requisite section of parts is completed.

There are cases in which the urethra is so disorganised by long-standing disease that no treatment will restore it to its natural use, and the patient is in great misery. Under such conditions this last operation may be undertaken with a view to establish a permanent urinary fistula to take the place of the diseased urethra, and perhaps several fistulae now existing, and threatening to increase in number.

*Puncture of Distended Bladder above the Pubis.*—Place the subject recumbent, with the head and shoulders raised, and the thighs flexed and abducted. In the median line, and one finger's breadth above the pubis, incise the integuments sufficiently to admit the point of the trocar and canula, which, whether straight or curved, are to be plunged into the bladder in this region. The trocar is to be withdrawn so soon as the bladder is entered, but the canula or an elastic catheter may be retained, by suitable tapes passed around the pelvis and thighs.

*Puncture of Bladder per Rectum.*—Place the subject in the lithotomy position, and pass the left forefinger into the rectum, to feel the distended bladder immediately behind the prostate, and in the median line: while the point of the finger rests against the bladder, introduce into the rectum the curved canula (Fig. 152, *a*), its concavity looking upwards, and guiding it along the retained finger, place the end



(c) also in contact with the wall of the bladder; this done, the trocar (b) is to be run along the canula, and as soon as the point reaches the end of the canula (c), the instrument is to be made to penetrate the anterior wall of the rectum, and to enter the bladder; the bladder entered, the trocar is to be withdrawn, and the canula retained as long as may be necessary, by tapes attached to a band passed around the pelvis.

By relieving the bladder <sup>a</sup> by puncture, and allowing <sup>b</sup> the urine to flow away through an artificial opening, the urethra is put into a state of rest, and a favourable opportunity is




FIG. 152.

afforded for treating the existing disease. This operation may also be performed while the patient is on his hands and knees.

*Forcible dilatation of Stricture (Holt's method).—*The force acts on the principle of a wedge. The instrument is conical, the smaller end being intended to traverse the stricture and to enter the bladder. It is made up of two grooved blades and a centre fine tube, all three being welded together at the smaller end only. This, being of the size of a No. 2 or 3 catheter, is first passed into the bladder; and

then along the central tube as a guide, a hollow cylinder is pushed also through the stricture and towards the bladder. By this the stricture is either forcibly dilated or ruptured. The whole instrument should now be withdrawn, and if the desired object has been accomplished, a full-sized catheter can be at once passed into the bladder, and this latter should then be emptied. The catheter should be introduced on alternate days for the first week subsequent to the operation, and then the intervals may be gradually, but after the first month, rapidly lengthened. Ultimately, once in six or twelve months will suffice in many instances.

Sir H. Thompson's Dilator. "The plan which I have adopted and prefer is as follows: The instrument consists of two long and narrow steel rods accurately applied to each other, but both forming, when closed, a cylindrical instrument the size of No. 3, 4, or 5. These rods are united at each end and throughout four inches of the shaft, and are surmounted by a handle containing a screw, which when turned, causes the rods to diverge from each other very slowly and gradually, at a given spot, forming a spindle-shaped figure three or four inches in length, and the third or half of an inch in diameter. There is an index near the handle which shows the exact degree of distention made, by pointing out that number of the catheter-scale which is reached as the operation proceeds. The reason for carrying distention beyond the size which the meatus of the

urethra will admit, is the fact, too often overlooked, that the great majority of strictures, that is, those situated at or near the bulbous portion of the urethra, occupy a part of the canal which naturally possesses a calibre of at least 16 or 18 of the catheter-scale, and that ordinary dilatation up to No. 10. or 12 inefficiently acts upon them. The method of applying the power by this instrument differs materially from that in others, in being made very slowly (better, therefore, under the influence of chloroform), so that from seven to ten minutes are occupied in slowly reaching the maximum point of distention, the object being to over-stretch the morbid tissues as much, and to rupture them as little, as possible, in order to destroy, or at all events to greatly impair, the natural tendency of the stricture to contract. Before operating, the distance of the stricture from the external meatus is measured by passing a full-sized bougie down to the stricture; the slide is then placed upon the figure on the stem which denotes that distance. The instrument is passed until the slide arrives at the meatus, and the blades are slowly separated. When the maximum distention is reached, the screw is turned back only about half way, so as not to close the blades; the instrument is withdrawn; a full-sized gum catheter is at once passed, and allowed to remain twenty-four hours. On the third day after the operation a large metallic sound is passed, and subsequently at longer intervals."

*Lithotomy.*—Previous to the operation, the presence of a stone in the bladder should have been detected with the sound. On the night before the day fixed for operation, a dose of castor oil should be administered, and on the morning of the day, a warm water enema, to empty the rectum. Shave the perinæum, if necessary. Assistants necessary are: one for each lower extremity, a third to hold the staff, and a fourth to attend to the wants of the patient, &c. &c. The operation usually performed in this country is by *lateral* incision; and instruments requisite are a grooved staff, scalpel, the back of which is rounded towards the point, that it may glide readily in the groove of the staff; forceps of different sizes, both straight and curved, and a scoop.

The *staff* may be either curved, rectangular, or straight. The two former can be more securely fixed under the arch of the pubis, and being firmly held by the assistant till the cutting part of the operation be completed, there is less risk of failing to reach the bladder than when the straight staff is used.

*The Scalpel.*—Some surgeons use a simple scalpel to divide the superficial strictures, and to open the membranous portion of the urethra only, and as soon as that is done, the scalpel is laid aside and replaced by a knife having a button at its extremity, and which is used to complete the section of parts; others use a gorget. The buttoned scalpel runs

readily in the groove of the staff, and is less likely to transfix the bladder and to open the peritoneal cavity than the ordinary lithotomy knife.

*The Gorget.*—The blunt gorget either dilates or tears the prostate, while the cutting gorget divides the prostate with precision, and also on either side, if double-edged.

The urine should either be retained in the bladder some hours before the operation, or warm water may be injected at the time of the operation. Place the subject recumbent, and introduce the staff into the bladder (the largest that will pass), and ascertain the presence of a stone before proceeding further: perhaps, if the subject be a child, or the prostate be much enlarged, the long curve of the staff will not dip sufficiently low towards the floor of the bladder, and will fail to detect the stone. Under these circumstances, the staff must be withdrawn, and a sound, with a short curve, be introduced, when, if the stone be felt, the operation may be proceeded with. On no account is the patient to be cut, unless the stone be recognised at the time of operation.

Do not mistake the promontory of the sacrum for a calculus.

The staff in the bladder, the subject is to be drawn to the edge of the table, so that the buttocks may project slightly beyond it, and the appointed assistants flex each a thigh upon the abdomen and the leg upon the thigh, and having attached one end of a suitable bandage to the wrist, the foot is placed in



the palm of the corresponding hand, and the two are then to be firmly bound together; the head and shoulders are to be thrown forward, and the trunk is to be raised to an angle of about thirty degrees, on pillows. Each assistant in charge of a lower extremity holds the foot with one hand, and, if possible, should put the knee into his axilla, so as to have perfect command over the extremity, and should make pressure upon it in a direction downwards and inwards; the assistant on the other side does likewise; and thus the two antagonistic forces have a tendency to fix the pelvis upon the table. The operator sits on a suitable stool, or kneels on a pillow, in front of the perinæum, his chin being on a level with the anus. At the last moment he satisfies himself that the staff is still in the bladder, and having hooked it firmly under the arch of the pubis, with the groove slightly inclined to the left, he entrusts the handle to an assistant, who, standing on one or other side of the subject, facing the operator, maintains the staff in the same position till desired to alter or remove it altogether; if requisite, one hand must be employed to hold aside the scrotum. The surgeon now surveys the perinæum, observing particularly the distance between the most prominent points of the tubera ischii, and determining with his eye the extent and course of the intended incision. The length of incision will vary in proportion to the age and degree of obesity of the subject, the probable size of the stone and depth of

perinæum; it will, therefore, vary from one-and-a-half to three inches, although the skin of the perinæum in front of the anus may be incised freely in a forward direction to favour extraction of a large stone. In the adult, the incision is to be begun about one-and-a-half inches in front of the anus—in the child, about half that distance will suffice,—and is to be carried downwards and outwards on the left side to or beyond a point midway between the anus and most prominent point of the tuber ischii, or even rather nearer to the ischium than to the anus. As a guide for the commencement of this oblique incision in the adult, the breadth of the two first fingers of the operator's left hand will assist, the length of the nail indicating the distance on the left from the raphe at which it is to be begun. In the child, one finger's breadth and half the length of the nail will suffice.

The surgeon, seated as above mentioned, holds the knife as he would a pen, and being on a low stool cannot fail to use it with the point directed upwards towards the umbilicus of the patient rather than inclined downwards towards the rectum. The incision is begun by entering the knife in the perinæum at the point indicated, and carrying it downwards in the right direction, and to the requisite extent, dividing probably the skin, common superficial fasciæ, a few fibres of the external sphincter, and some fat in the ischio-rectal space; another sweep of the knife from above downwards

deepens the wound, dividing perhaps the deep perineal fascia, the transverse perinæi muscle and artery, and more ischio-rectal fat. The forefinger of the left hand should be passed into the upper end of the wound, to put aside the bulb, *a* (Fig. 153 being a side view of the male genito-urinary organs, &c.),




FIG. 153.

and to feel for the staff through the membranous portion (*b*); the staff recognised, the point of the knife (not carried too high, lest it wound the artery of the bulb) is to cut its way into it through the urethra, and the two metals having come into contact, the scalpel is to be run back along the groove into the bladder, cutting the prostate (*c*), in a direction from above downwards and outwards, and perhaps nicking the neck of the bladder, and as it is

withdrawn, may be made to deepen the existing wound by dividing a few fibres of the levator ani muscle. Fig. 154 shows the relative position of the prostate and rectum beneath the arch of the pubes, the prostate being perforated by the urethra and traversed by dotted lines coursing from the urethra in different directions, and indicating the variable depth of the gland; the greatest depth of the prostate being in direction from the urethra downwards and outwards to *c* or *e*.




FIG. 154.

As the knife is withdrawn, the forefinger of the left hand already in the wound is to be carried along the staff into the bladder, both to dilate the opening, to fill the aperture made by the knife and prevent the escape of urine, and also to feel and fix the stone. Desire the assistant to remove the staff; take now a suitable pair of forceps, warmed, in the right hand, and while removing the finger from the bladder, introduce the forceps, and as soon as possible separate their blades, with the hope that the first gush of urine may send the stone between them; if not so fortunate, close the forceps, and quietly using them as a sound to discover the whereabouts of the calcu-

lus, endeavour to seize it, and having succeeded, proceed to extract it by pulling gently forwards and downwards, and from side to side, so as gradually to dilate the parts sufficiently; the stone may be lying with its long axis across the wound, and to alter this position may be dropped and seized again, or it may perhaps be turned by the forefinger of the left hand. Sometimes a stone is shot out of the bladder into the wound by the urine, and consequently none is found in the bladder; or it may be carried out upon the floor, and fall without being heard, and the operator suddenly becomes alarmed lest he may have cut his patient unnecessarily. A small stone, or fragments of stone, may be removed by a scoop and finger. The stone may be so large that the incision on one side only will not suffice for its extraction. Under these circumstances, it must either be broken by a lithotrite, or the opposite side of the prostate must be cut by introducing upon the finger retained in the bladder a straight probe-pointed bistoury, and directing its edge downwards and outwards towards the right-hand side. The stone having been extracted, the finger should be passed into the bladder, in order to ascertain that a second calculus does not exist, and fragments of stone may be removed by injecting warm water into the bladder through the wound.

Hæmorrhage from a superficial vessel may be checked by ligature; general bleeding, by plugging the wound with a sponge around a tube previously introduced into the bladder, through which urine



may escape. Slight bleeding will cease when the sides of the wound come into apposition by approximating the thighs. The operation completed, the




FIG. 155.

bandages may be removed from the hands and feet, and the patient be returned to bed.

By *median* incision.—Excepting the site and extent

of incision, the above remarks will be equally applicable here.

The operation is performed by introducing the forefinger of the left hand into the rectum, to feel the apex of the prostate, the groove of the staff, and to press upon and fix the latter (Fig. 155 showing a side view of the pelvis); then a long sharp-pointed knife held in the right hand, edge uppermost, is made to enter the perinæum in the median line, and about half an inch in front of the anus, and is pushed on towards the bladder, and parallel with the finger, with a view to open the membranous portion of the urethra, and to enter the groove of the staff. The contact of the two metals having been recognised, the knife is to be withdrawn in an upward direction, cutting the membranous urethra towards the bulb, and from behind forwards, and also severing the integument of the perinæum towards the root of the scrotum, so as to enlarge the superficial wound; now pass a long *grooved* probe along the staff into the bladder, and after trying to touch the stone with it withdraw the latter, and using the probe as a guide, introduce the finger above it, both to feel the stone and to dilate the prostate and neck of the bladder as much as may be necessary. This done, introduce the forceps, and extract the calculus.

If the finger, by gentle pressure, cannot be insinuated into the bladder, the wound should be enlarged by a straight blunt-ended bistoury, carried along the groove in the probe.

The simplicity of this method compared with the *lateral* is evident; no important structures are divided, and the bladder is nearer the surface. In more than one instance in which the author has performed this operation there has been perfect control over micturition throughout the period of recovery, and the patient enjoyed the luxury of a dry bed. This desideratum never attends the lateral operation.

Fig. 156 shows the line of incision, A, for the lateral operation; B, the position of the incision for the median operation.



FIG. 156.

*Lithotrity.*—The instrument in general use is shaped somewhat like an ordinary sound, and con-

sists of two blades, a screw, and handle. The handle is attached at an angle to the larger blade, in one end of which a screw works; the smaller blade runs in a groove of the large blade, and can be pushed home by the screw, Fig. 157. Weiss' new



FIG. 157.

instrument, with cylindrical handle, is highly approved by some.

Before proceeding to lithotrity the surgeon must, by a careful examination, ascertain the size of the stone, and the condition of the prostate, but not on the day on which the operation is performed. Chloroform may or may not be exhibited. The bladder must be capable of holding four or five ounces either of urine or of warm water. If warm water be preferred, the bladder should be emptied of urine before the water is injected, and the latter slowly.

If the stone be small or of moderate size, the patient may lie flat upon his back; if of large size, the normal position of the stone is just behind the neck of the bladder, where it cannot be so readily caught, and then the patient should lie with his pelvis well raised, so as to throw the calculus towards the fundus of the bladder. Such should also

be the position of the subject if the prostate be enlarged. The legs will hang over the table or sofa or bed, and should be comfortably supported.

There are two methods of using the lithotrite: one consists in *bringing the stone to the instrument*, the other in *bringing the instrument to the stone*. In each case the surgeon stands or sits between the thighs of the patient, and having introduced the lithotrite, previously warmed and oiled, will use it with one object only—to seize and crush the stone.

Method I.—The instrument being well in the bladder, the handle is to be raised, and this will bring the convexity of the female blade in contact with the floor of the viscus (Fig. 158). Separate now




FIG. 158.

the blades to an extent proportionate to the suspected size of the stone, and, at the same time,



depress the floor of the bladder towards the rectum, in order that the calculus may fall between the blades of the instrument. Approximate the blades, and if the stone be caught it can be crushed. If not seized, the lithotrite should be turned to an angle of 45 deg., first to the right and then to the left, to seek the stone, and then the blades are to be re-opened. If still unsuccessful, each of these manœuvres is to be repeated, with the addition of giving a gentle blow to the handle, so as slightly to shake the bladder and dislodge the stone. Compared with the following, which is a most elegant operation, the above is very rude.

Method II.—The instrument is barely to touch




FIG. 159.

the vesical walls. The blades are to represent the radius of a circle, the centre of which is the centre of the bladder (Fig. 159). The lithotrite having passed to the fundus of the bladder, the male blade

is to be withdrawn, the whole inclined slightly, and the blade then returned. Should the stone not be caught, again withdraw the male blade, and turn the instrument all round upon its axis, if necessary, until the angle is found in which the stone is lying, and is seized. Before the blades are passed from one angle to another they should be returned closed to their original vertical position, and then, being separated, are to be turned in the desired direction. If, while lying at a certain angle (in which, though unknown to the operator, the stone is also lying), the male blade be withdrawn, the calculus will inevitably be pushed away from the bite of the blades. Should the operator have reason to suspect the position of the calculus, he may at once search in that locality, gradually exploring the rest of the circle afterwards if necessary.

Hitherto the female blade has only been moved upon its own axis, but to catch a stone which persists in lying just within the neck of the bladder a different plan may be adopted.

As soon as the instrument enters the bladder, retain the male blade, but push on the female, and then incline them towards the stone. In this way there is less risk of injuring the neck of the bladder, because the male blade is not brought towards it. To pick up a small fragment of stone or one behind an enlarged prostate, the blades of the lithotrite should be short and be inverted, while at the same time the handle of the instrument is somewhat

depressed between the thighs to avoid injury to the floor of the bladder with the points of the blades.

By this method of Civiale the blades of the lithotrite are not intended to touch the walls of the bladder; and if the operation be carefully and systematically performed no more delicate or less irritating manipulation can be imagined possible. The operation will often be quite bloodless. On the contrary, by the method of Brodie, the first step towards catching the stone necessitates firm contact with the floor of the bladder, and more or less irritation results. The sitting completed, the fluid in the bladder should not be drawn off; micturition should be postponed as long as possible, and the act is best performed in the recumbent posture to prevent large fragments passing into the urethra.

The stone broken, fragments will pass with the urine, and some may lodge in the urethra, and must be removed, either by pushing them back into the bladder with a full-sized catheter, or by extracting them with a bent probe or urethral forceps, or other means devised by the ingenuity of the surgeon to meet the circumstances of the case.

Lithotripsy should always be attempted, unless there be some special contraindication, after the age of fifteen, provided that the urethra be capacious, the bladder tolerant of the presence of the instrument, and capable of containing from four to five ounces of water. In the adult, mortality after lithotomy is great; but in the boy the urethra is

small and the bladder sensitive, and the mortality after lithotomy is slight; in the old man the prostate is often more or less enlarged,—a circumstance favourable to lithotomy, because a free incision may be made in it without great risk; but somewhat unfavourable to lithotrity, because the fragments of calculus are liable to lodge in the vesical pouch behind the enlarged gland.

*Lacerated Perinæum.*—Whether partial or complete, the steps of the operation are similar, and consist in vivifying the margins of the rent, and in the introduction of sutures. The patient should be in the lithotomy position, and the floor of the vagina will be best exposed to view by the duck-bill speculum. A new perinæum is to be made out of the remnants of the original, and any rent in the recto-vaginal septum must at the same time be closed. The chief point to be remembered is, to have from before backwards a large raw surface, with a view to the formation of a thick and substantial septum. Both mucous membrane and skin must therefore be dissected up and removed to an extent proportionate to the demands of the case; the greatest depth of raw surface being on the floor of the vagina. Hæmorrhage having ceased, three or more double sutures must be passed deeply on a strong curved needle set in a handle, the eye being near the point. The needle, armed either before or after its introduction, must be inserted about one inch external to the margin of the cleft on one side,

and after traversing the soft parts under the raw surfaces, should appear at a corresponding point on the other side. When all the threads or wires are in position, the suture nearest the anus should be made first and quilled: one piece of bougie on each side, of sufficient length, will suffice. Besides these deep sutures, the cutaneous edges of the cleft may be approximated by superficial sutures. Should the laceration be severe, the operator may prefer to sever the sphincter ani on both sides. Should the threads be of wire, they may probably be left in seven or ten days; but if from any cause they excite undue irritation, they must be removed earlier. Primary union is desired; but if this fail, union by granulation need not be despaired of. At all events, while healing is awaited, the bladder must be carefully emptied periodically by the catheter, and the bowels, which previous to operation had been cleared out, must be kept at rest by opium. The knees should be held approximated.

*Catheterism in the Female.*—Place the subject recumbent, with the right thigh semiflexed upon the abdomen; stand on the right side and introduce the tip of the forefinger of the left hand from before backwards, just within the orifice of the vagina; then gradually retracing this step, the finger passes out of the vagina, and immediately above it detects a slight depression corresponding to the meatus; the right hand, armed with a catheter warmed and oiled,



is passed under the elevated thigh, and, guided by the point of the left forefinger still maintained at the meatus, the instrument enters the urethra and the bladder. If possible, do not expose the patient in order to evacuate the bladder.

#### VESICO-VAGINAL FISTULA.

The operator will determine the position for his patient: whether on the back (the lithotomy position) or on her three-quarters face; with the shoulders low but the hips high. Should the opening be small and accessible, it is not absolutely necessary to administer chloroform, the operation being comparatively painless. The chief steps of the operation are two: to vivify the margin of the aperture, and to introduce sutures.

Mucous membrane lining the vagina is to be removed at least three-quarters of an inch from all sides of the fistula; thus the vagina alone will be encroached upon, the coats of the bladder being carefully avoided, and the capacity of its cavity not diminished. Bleeding having ceased, the sutures are to be introduced. This is best effected by means of a tubular needle armed with wire (Fig. 164). The needle should be introduced from before backwards, its point being entered the third of an inch from the rawed surface, and then carried along *under* the rawed surface till it is made to appear the third of an inch beyond the rawed surface on the proxi-

mal side of the fistula. The projecting end of wire must now be seized with a pair of forceps, and be firmly held while the needle is slowly withdrawn. Wires (three or more) having been thus placed, the speculum used should be partially or altogether withdrawn, while, at the same time, firm traction is made upon the ends of the wires. This manœuvre will tend to bring the cut surfaces in contact, when each wire may be twisted in the usual way, and the suture is effected. A linear wound results. The sutures should be removed after the lapse of not more than a week, lest they become imbedded.\* An italic s catheter may be retained for a few days, or the bladder may be evacuated periodically.

The author finds the duck-bill speculum very efficient both for dilating and lighting the vagina; while a scalpel with a short blade and long handle, and a pair of forceps with small teeth, suffice for the first part of the operation.

N.B.—It should be stated that this operation is sometimes very difficult and tedious of performance, and not unfrequently must be repeated more than once. Various instruments exist, and are used by some surgeons with a view to facilitate the operation, and doubtless occasionally do so.

*Calculus in the Female Bladder.*—The female urethra

\* To-day, September 4th, 1872, the author operated for the second time, with an interval of ten years, on a patient who, during that period, has had seven children. The operation disclosed a piece of wire, part of a former suture, inserted ten years ago.

is short (Fig. 160, *a*), and more readily dilated to a considerable extent than that of the male. Dilatation of this canal by Weiss' dilator will usually suffice for the extraction of the stone. This dilatation should be effected rapidly rather than slowly, with the




FIG. 160.

expectation of avoiding incontinence. If the stone be large, it may be crushed with a lithotrite, and the smaller fragments be allowed to escape either on micturition or by the aid of the lithotrity syringe,\* while the larger pieces are extracted by forceps.

*Lithotomy* may be rarely practised by introducing into the bladder a grooved staff, and upon this a straight probe-pointed knife, which latter is to lay open the urethra anteriorly on either the right or

\* "London Hospital Reports," vol. iii., p. 217.

left side, or on both, external to the vagina in a direction downwards and to one side. Introduce the finger, and withdraw the staff, and having dilated the neck of the bladder sufficiently, insert the forceps and withdraw the calculus. The neck of the bladder must not be cut, lest incontinence follow.

Again, a stone may be extracted after longitudinal incision of the floor of the bladder, and the wound, at once, closed by suture.

*Tenotomy.*—This operation has for its object the section of one or more tendons, which, being contracted, distort the limb and interfere with the healthy and useful movements of a joint. The *subcutaneous* section of tendons is preferred, with a view to inflict as little injury as possible to the parts covering and adjacent to the tendon; also, to avoid the occurrence of suppuration by excluding the air, and so to promote rapid union of the divided ends of the tendon by the natural interposition of organizable lymph. When practicable, tendons should be divided at a distance from nerves and vessels; where they are superficial; not immediately opposite to an articulation; and devoid of muscular fibres. The knife is to be introduced on the side of the tendon on which are the more important organs; and having passed transversely along the deep aspect of the tendon till its point reaches the opposite border of it, should sever the organ by cutting it towards the skin, partly by pressure and partly by drawing the edge of the blade across the tendon.

The principle is the same in most instances, therefore one example will suffice.

The tendon frequently requiring division is the tendo Achillis, the contracted state of which is shown in Fig. 161. To divide this tendon,

the subject will be conveniently placed on its face; one assistant should hold the leg while another endeavours to flex the foot upon the leg, and by so doing tighten the tendon; the operator, having previously clearly defined the extent and position of the tendon, introduces the point of a fine knife (flat of the blade towards the leg) on the inner side of the tendon,




FIG. 161.

and almost perpendicularly to the surface. Having penetrated to the margin of the tendon, the point of the blade must be made to turn round the border of it and to pass across it to the opposite margin; this done, the edge of the knife must be turned towards the tendon, and be caused to divide it, partly by pressure against it and partly by drawing the blade of the knife across it from heel to point; when divided, the assistant holding the foot will experience a *snap*, which perhaps may be heard, and the operator will be able to detect a gap caused by the retraction of the end of the tendon connected with muscular fibre from the end attached to bone. Withdraw the knife *flat* as it entered, following it



with the thumb, so as to express extravasated blood, and to prevent the entrance of air into the wound ; close the wound with a compress, strapping, and a bandage from the toes upwards. Leave the parts at rest for from three days to a week, and on removing the compress the wound will probably be found healed, and an appropriate apparatus may be adapted to the limb.

After having punctured the integuments, some surgeons prefer to effect division of a tendon with either a square or probe-pointed knife. (Fig. 161.)

When performing a delicate operation, tenotomy for example, the hand using the knife should rest, even with the point of a finger only, upon the limb of the subject, becoming, as it were, for the moment a part of the member itself, lest during any unexpected movement on the part of the patient the limb be brought into forcible contact with the knife, and serious injury be incurred.

#### THE SPRING-EYED NEEDLE.

Mr. Vincent Jackson, the introducer of this instrument, writes :—"This needle (Fig. 162) is useful




FIG. 162.

wherever the surgeon desires to carry a double ligature, as in operations requiring the quilled suture, such as those upon the perinæum in females ;

again in nævi, and in Ricord's operation for varicocele, and in ligaturing hæmorrhoids. The thread or wire is passed through the spring and doubled; then after the needle has done its work by traction upon the ligature, it is pulled beneath the spring and rapidly and easily disengaged. (Fig. 163.) The needle is commendable on account of its simplicity and its inability ever to get out of order. It can be made either straight or curved, and of any size."




FIG. 163.

#### ANEURISM AND SUTURE NEEDLE.

Mr. Richard Davy states:—"The two diagrams exhibit the form of needle that has been invented and used by me for the last six years in hospital and private surgical practice. The handle contains concealed reel, tramway, and wheel for extrusion or intrusion of wire, and a universal collar for the fixing of any shaped tubular or plain needle. The instrument will carry well wire, gut, string, or carbolized catgut. The tubular aneurism needle is also shown; it inflicts less injury on the vascular sheath than the ordinary aneurism needle. Surgeons may yet be seen in daily practice and in operating theatres tugging away at sutures to the annoyance of their own fingers and their patients' skin; such

inconveniences and constant threadings are entirely obviated by the use of this mechanism."




FIG. 165.

## INDEX.

---

- Abdominal aorta, ligature of, 79  
compression of, 231
- Abscess, acute, 157  
chronic, 158  
in bone, 149
- Acupressure, 37, 39
- Acupuncture, 159
- Amputation, on, 163  
double flap, 165  
by circular incision, 173  
by oval incision, 178  
in the contiguity of a limb, 179  
through the foot, 181  
of the toes, 181  
of metatarsal bone of great toe, 189  
tarso-metatarsal, 192  
medio-tarsal, 197  
(caution), 198  
tibio-tarsal (Syme), 200  
    "    "    (Pirogoff), 204  
    "    "    (Jules Roux), 206  
of the leg, 210-220  
of the thigh, 221-228  
through knee-joint, 228  
through hip-joint, 230-235  
(caution), 232  
fingers, 236  
metacarpal bone, 241
- Amputation, at wrist joint, 244  
of forearm, 245  
at elbow-joint, 248  
of arm, 249  
at shoulder-joint, 252
- Anchylosis, false, 153  
true, 154  
subcutaneous section of, 154  
by W. Adams, 154  
by L. S. Little, 154
- Aneurism needle, 42, 367
- Ankle-joint, excision of, 142  
author's case of, 144  
Syme's amputation at, 200  
(caution), 203  
Pirogoff's amputation at, 204  
author's case of, 205  
Jules Roux' amputation at, 206
- Anus, artificial, 285  
lumbar, 285  
(N. B.), 286  
by transverse incision, 288  
author's experience of, 286  
by longitudinal incision, 287  
by oblique incision, 288  
abdominal, 290  
McCarthy's case of, 290  
Littre's method, 291  
author's case of, 291

- Arteries, operations on, 29  
 compression of, 29  
 torsion of, 31  
 cauterization of, 31  
 ligature of, 33-36  
 ligature in continuity of, 39-45
- Arteriotomy, 32
- Artery, innominate,  
 anatomical relations of, 46  
 ligature of, 46  
 another method of, 48  
 carotid, common, anatomical relations of, 49  
 ligature of, 51,  
 author's case of, 53  
 Heath's case of, 53  
 between heads of sterno-mas-  
 toid muscle, 54  
 author's case of, 54  
 carotid, external, anatomical relations of, 54  
 ligature of, 55  
 carotid, internal, anatomical relations of, 56  
 ligature of, 57  
 thyroid, superior, 57  
 lingual, course of, 58  
 ligature of, 58  
 another mode of, 59  
 facial, course of, 59  
 ligature of, 59  
 occipital, 60  
 temporal, 60  
 subclavian, course of, 60  
 first part of, anatomical relations of, 61  
 ligature of, 61  
 third part of, anatomical relations of, 62  
 ligature of, 63  
 author's case of, 64
- Artery, second part of, 65  
 vertebral, 65  
 thyroid, inferior, 66  
 mammary, internal, 66  
 axillary, anatomical relations of, 67  
 ligature of, 67  
 another mode, 69  
 at lower third of, 69  
 brachial, anatomical relations of, 71  
 ligature of, at middle of arm, 72  
 at bend of elbow, 73  
 radial, anatomical relations of, 74  
 ligature of, in upper third, 75  
 at lower third, 76  
 ulnar, course of, 76  
 ligature of, at upper third, 77  
 at lower third, 78  
 abdominal aorta, relations of, 79  
 ligature of, 79  
 another mode, 79  
 iliac, common, relations of, 80  
 ligature of, 83  
 author's case of, 83  
 iliac, external, relations of, 80  
 ligature of, 81  
 iliac, internal, relations of, 81  
 ligature of, 83  
 femoral, relations of, 83  
 ligature of, at base of Scarpa's triangle, 88  
 at apex of Scarpa's triangle, 86  
 at middle of thigh, 89  
 caution, 90  
 popliteal, relations of, 91  
 ligature of, 91  
 tibial posterior, relations of, 92  
 ligature of, at middle of leg, 92



- Artery (caution), 94  
     another method of, 94  
     at lower third, 94  
     tibial, anterior, relations of, 96  
     ligature of, 97  
     caution, 97  
     dorsalis pedis, relations of, 98  
     ligature of, 99
- Bandage, 2  
     figure 8, 5  
     the T, 5  
     simple roller, 3  
     double-headed, 4  
     starched, 6  
     plaster of Paris, 6  
     many-tailed, 6  
     four-tailed, 7  
     broad roller, 7  
     anti-chordee, 8
- Brachial, anatomical relations of, 71  
     ligature of, 71  
     in the middle of arm, 72  
     at bend of elbow, 73
- Breast, removal of, 298
- Bladder, puncture of, above pubis, 340  
     per rectum, 341
- Blepharoplasty, 324
- Blood, transfusion of, 28
- Bone, abscess in, 149  
     subcutaneous section of, 154
- Bones, operation on, 100
- Bryant, on lumbar colotomy, 288
- Buckles and straps, 6
- Butcher's saw, 156
- Buttons and clamps, 13
- Caesarian section, 295  
     Barnes' suture, 296  
     Hicks' suture, 295  
     Wells' suture, 296
- Calenhus, in female, 362
- Carotid artery, common, anatomical relations of, 49  
     ligature of, 51  
     one of the author's cases of, 54  
     external, anatomical relations of, 54  
     ligature of, 55  
     internal, anatomical relations of, 56  
     ligature of, 57
- Castration, 332
- Cataract, extraction of, by flap method, 320  
     by linear method, 322  
     soft, solution of, 322
- Catheter, in male, 333  
     in female, 360
- Caustics, fluid, 159  
     solid, 159
- Cautery, actual, 159
- Clamps and buttons, 13
- Clavicle, excision of, 112  
     Mr. Couper's case of, 113
- Clove hitch, 14
- Cock, perineal section, 339
- Compress, 1
- Couper, removal of clavicle, 113
- Cupping, 20  
     dry, 20
- Davy's tubular needle, 367  
     ,, aneurism needle, 367
- Dorsalis pedis artery, anatomical relations of, 98  
     ligature of, 99
- Duct, catheterism of nasal, 311  
     from nostril, 311  
     from above, 311
- Durham's tracheotomy tube, 263

- Elbow-joint, excision of, 118  
     various incisions for, 119  
     author's method for, 120  
     to insure extension after, 122
- Entropion, 323
- Eustachian tube, catheterism of, 312
- Excision of, upper jaw, 100-106  
     lower jaw, 106-112  
     author's method, without  
         wound of cheek, 111-112  
     clavicle, 112  
     scapula, 113  
     head of humerus, 114-117  
     author's case, 117  
     in continuity of humerus, 117  
     elbow-joint, 118-126  
     author's method to insure ex-  
         tension, 120  
     radius, 126  
     ulna, 126  
     wrist-joint, 127  
     metacarpal bone of thumb, 133  
     phalangeal articulation, 135  
     hip-joint, 135-138  
     in continuity of femur, 138  
     knee-joint, 138  
     portion of fibula, 141  
     ankle-joint, 142  
     metatarso-phalang joint, 144  
     tarsal bones, 146  
     os calcis, 147  
     un-united fracture, 147  
     exostoses, 149
- Exploration, 160
- Eye-lid, operation on, 324
- Eye, 316  
     extirpation of globe, 316  
     strabismus, 317  
     artificial pupil, 318  
     by iridectomy, 318
- Eye, by iridodesis, 319  
     by staphyloma, 319  
     extraction of cataract by flap  
         method, 320  
     by linear method, 322  
     solution of soft cataract, 322
- Facial artery, ligature of, 59
- Femoral artery, anatomical rela-  
     tions of, 83  
     ligature of, 85  
     at apex of Scarpa's triangle, 86  
     at base of, 88  
     in Hunter's canal, 88
- Fibula, excision of portion of, 141
- Fingers and toes, bifid, 146
- Fistula, vesico-vaginal, 361
- Flaps, length of, 170
- Fluids, injection of saline, 28
- Forceps, artery, 34  
     lion, 103
- Fracture, compound, 149
- Gastro-stomachotomy, 267  
     sutures in, 268  
     after-treatment in, 268
- Handkerchief, the, 7
- Hare-lip, pin for, 11-13  
     operation for, 300
- Heath, ligature of arteries, 53
- Hernia, abdominal, 270  
     taxis in, 270  
     chloroform in, 270  
     warm bath, &c., in, 270  
     herniotomy in, 272  
     the incision in, 272  
     the sac in, 272  
     the stricture in, 273  
     to open the sac in, 274  
     division of stricture in, 275  
     inguinal, 277

- Hernia, radical cure of, 277  
     Wood's method for, 277  
     instruments for, 277  
     steps of operation, 278  
     after-treatment in, 281  
     statistics of, 283  
     Wood's trusses for, 284  
 Hilton, on amputation of penis, 328  
     on lumbar colotomy, 287  
 Hip-joint, excision of, two methods  
     of, 137  
     amputation at, 230  
 Holt's stricture dilator, 341  
 Humerus, excision of head of, 114  
     by longitudinal incision, 115  
     by flap, 116  
     case of, by author, 117  
     excision in un-united fracture  
     of, 117  
 Hydrocele, 329  
 Iliac artery, common, anatomical  
     relations of, 80  
     ligature of, 83  
     author's case of, 83  
     external, anatomical relations  
     of, 80  
     ligature of, 81  
     internal, anatomical relations  
     of, 81  
     ligature of, 83  
 Incisions, 10  
 Injection of saline fluids, 28  
 Innominate artery, ligature of, 46  
     anatomical relations of, 46  
 Integument, removal of, 297  
 Internal mammary artery, ligature  
     of, 66  
 Issue, 160  
 Jackson's V spring-eyed needle, 366  
 Knee-joint, excision of, 138  
     apparatus after, 141  
 Knots, 14.  
     simple, 14  
     double reef, 14  
     surgeon's, 14  
     slip, 14  
 Laryngotomy, 264  
 Ligatures, uses of, 16  
     thread, 16  
     silk, 16  
     cord, 16  
     catgut, 16  
     wire, 16  
     for tumours, 16  
     figure 8, 18  
     carbolic, 36  
 Ligature of the, innominate, 46  
     common carotid, 49  
     external carotid, 54  
     internal carotid, 56  
     superior thyroid, 57  
     lingual, 58  
     facial, 159  
     temporal, 60  
     occipital, 60  
     subclavian, 60-65  
     vertebral, 65  
     inferior thyroid, 66  
     internal mammary, 66  
     axillary, 67-71  
     brachial, 71-74  
     radial, 74-76  
     ulnar, 76-79  
     abdominal aorta, 79  
     common iliac, 80  
     author's case of, 83  
     external and internal iliac, 80-83  
     femoral, 83-90  
     popliteal, 91

- Ligature of posterior tibial, 92-96  
     anterior tibial, 96-98  
     dorsalis pedis, 98
- Lingual artery, ligature of, 58
- Lister, on excision of wrist joint, 129
- Lithotomy, lateral, 344  
     staff in, 344  
     scalpel in, 344  
     gorget in, 345  
     median, 351  
     dry bed after, 353  
     vaginal, 364  
     in female, 363
- Lithotrity, 353  
     method I, 355  
     method II, 356  
     in female, 363  
     syringe, 363
- Little, L. Stromeier, on subcutaneous section of bone, 154
- Littre's operation, 291
- Lower jaw, excision of, one half, 106  
     symphysis, 108  
     from symphysis to angle, 109  
     from angle to joint, 110  
     author's method without wound of cheek, 111
- McCarthy's case of artificial anus, 290
- Mammary gland, removal of, 298
- Necrosis, 149
- Needle, V. Jackson's, 366  
     R. Davy's, 367
- Nose, restoration of, 325
- Nostril, plugging the posterior, 309
- Nævus, treatment of, 26  
     by ligature, 16  
     by pressure, 26
- Nævus, by injection, 26  
     by seton, 27  
     by vaccination, 27  
     by subcutaneous incision, 27  
     by actual cautery, 27  
     by ligature of an artery, 27  
     by caustics, 27  
     by excision, 27
- Occipital artery, ligature of, 60
- Operations, are minor or capital, 9
- Oesophagotomy, 266
- Ovariectomy, 291  
     pedicle in, 294
- Palate, fissure of hard, 307  
     operation for, 308  
     fissure of soft, 303
- Paracentesis thoracis, 265  
     abdominis, 268
- Perinæum, lacerated, 359
- Penis, amputation of, 328
- Phalangeal-joint, excision of a, 135
- Phymosis, by circumcision, 326  
     by another method, 327  
     by simple incision, 328
- Popliteal artery, anatomical relations of, 91  
     ligature of, 91
- Radial artery, anatomical relations of, 74  
     ligature of, in upper third, 75  
     " in lower third, 76
- Radius, excision of part of, 126
- Rhinoplasty, 325
- Saw, to, 167  
     chain, 102  
     bow, 156
- Scapula, excision of, 113
- Serres-fines, 14

- Seton, 160  
     needle, 161  
 Smith's, Thomas, gag (See Bartholomew's Hospital Reports, 1871), 303  
 Splints, 1  
 Sponging, 36  
 Staphyloraphy, 303  
     with T. Smith's gag, 303  
     operation of, 305  
 Strapping, 8  
     a wound, &c., 8  
     to remove, 9  
 Straps and buckles, 6  
 Stricture, catheterism in, 334  
     treated by, escharotic, 336  
     internal division, 337  
     external section, 337  
     other methods, 338  
     forcible dilatation, 341  
     Wakley's catheter, 336  
 Subclavian artery, ligature of, 60  
     in first part, 61  
     in third part, 62  
     one of author's cases of, 94  
     value of small vein in, 64  
     in second part, 65  
 Sub-periosteal excision, 145  
 Surgery, manipulative and operative, 1  
 Suture, 11  
     twisted, 11, 13  
     threads for, 11  
     before using a, 11  
     the knot of, 11  
     interrupted, 12  
     uninterrupted, 12  
     the quill, 12  
     the zigzag, 13  
     metallic, 13  
     to remove, 13  
 Syme, external urethrotomy, 337  
 Syringe, lithotrixy, 363  
 Tapes, 6  
 Taxis, 270  
 Toale's amputation, 211  
 Temporal artery, ligature of, 60  
 Tenaculum, 33  
 Tenotomy, 364  
 Thompson's stricture dilator, 342  
 Threads for suture, 11  
 Thumb, excision of metacarpal bone of, 133  
 Thyroid artery, inferior, ligature of, 66  
     superior, ligature of, 57  
 Tibial artery, anterior, anatomical relations of, 97  
     ligature of, in middle of leg, 97  
     posterior, ligature of, 92  
     at middle of leg, 92  
     at lower third of leg, 94  
 Tongue, removal of, 313  
     by ligature, 313  
     by excision, 314  
     by écraseur, 315  
     by Regnoli's method, 315  
 Tonsil, abscission of, 308  
 Tracheotomy, 259  
     anatomy of, 259  
     chloroform in, 260  
     difficulties in, 261  
     after-treatment in, 261  
     canulæ in, 263  
 Transfusion of blood, 28  
 Trocar, the, 269  
     introduction of, 269  
     withdrawal of, 269  
 Tumours, removal of, 297  
     exploration of, 297  
 Ulna, excision of part of, 126



- Ulnar artery, ligature of, in upper third, 77  
in lower third, 78  
Un-united fracture, 147  
Upper jaw, excision of, several methods of, 100-106  
  
Vaccination, 161  
Varicocele, treated by *écraseur*, 330  
by ligature, 330  
by subcutaneous section, 331  
Varix, operation on, 25  
by needle and ligature, 25  
  
Varix, by subcutaneous section, 26  
Vein on subclavian artery, 64  
Venæsection, 21  
at bend of elbow, 21  
at external jugular vein, 24  
Vertebral artery, ligature of, 65  
  
Wakley's catheters, 336  
Wood's operation for hernia, 277  
Wound, strapping a, 8  
Wrist-joint, excision of, 127  
various methods of, 128  
Lister's method of, 129



77







